

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING						FORM 3 AMENDED REPORT				
APPLICATION FOR PERMIT TO DRILL						1. WELL NAME and NUMBER Three Rivers 4-36T-820				
2. TYPE OF WORK DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>						3. FIELD OR WILDCAT THREE RIVERS				
4. TYPE OF WELL Oil Well Coalbed Methane Well: NO						5. UNIT or COMMUNITIZATION AGREEMENT NAME				
6. NAME OF OPERATOR ULTRA RESOURCES INC						7. OPERATOR PHONE 303 645-9810				
8. ADDRESS OF OPERATOR 304 Inverness Way South #295, Englewood, CO, 80112						9. OPERATOR E-MAIL dghani@ultrapetroleum.com				
10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE) FEE			11. MINERAL OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/>			12. SURFACE OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/>				
13. NAME OF SURFACE OWNER (if box 12 = 'fee') UPL Three Rivers Holdings, LLC						14. SURFACE OWNER PHONE (if box 12 = 'fee') 303-645-9810				
15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee') 304 Inverness Way South Suite 295, Englewood, CO 80112						16. SURFACE OWNER E-MAIL (if box 12 = 'fee') dghani@ultrapetroleum.com				
17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')			18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS YES <input type="checkbox"/> (Submit Commingling Application) NO <input checked="" type="checkbox"/>			19. SLANT VERTICAL <input type="checkbox"/> DIRECTIONAL <input checked="" type="checkbox"/> HORIZONTAL <input type="checkbox"/>				
20. LOCATION OF WELL	FOOTAGES		QTR-QTR	SECTION	TOWNSHIP	RANGE	MERIDIAN			
LOCATION AT SURFACE	1529 FSL 2373 FEL		NWSE	4	8.0 S	20.0 E	S			
Top of Uppermost Producing Zone	1780 FSL 1780 FEL		NWSE	4	8.0 S	20.0 E	S			
At Total Depth	1780 FSL 1780 FEL		NWSE	4	8.0 S	20.0 E	S			
21. COUNTY UINTAH			22. DISTANCE TO NEAREST LEASE LINE (Feet) 454			23. NUMBER OF ACRES IN DRILLING UNIT 40				
			25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed) 40			26. PROPOSED DEPTH MD: 6849 TVD: 6782				
27. ELEVATION - GROUND LEVEL 4752			28. BOND NUMBER 022046398			29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE 49-2262				
Hole, Casing, and Cement Information										
String	Hole Size	Casing Size	Length	Weight	Grade & Thread	Max Mud Wt.	Cement	Sacks	Yield	Weight
SURF	11	8.625	0 - 1000	24.0	J-55 LT&C	8.8	Premium Lite High Strength	80	2.97	11.5
							Class G	115	1.16	15.8
PROD	7.875	5.5	0 - 6849	17.0	J-55 LT&C	10.0	OTHER	225	3.54	11.0
							OTHER	450	1.35	14.0
ATTACHMENTS										
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES										
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER					<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN					
<input checked="" type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)					<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER					
<input checked="" type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)					<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP					
NAME Katherine Skinner				TITLE Permitting Assistant			PHONE 303 645-9872			
SIGNATURE				DATE 05/13/2014			EMAIL kskinner@ultrapetroleum.com			
API NUMBER ASSIGNED 43047544200000				APPROVAL Permit Manager						

ULTRA RESOURCES, INC.

MASTER
8 - POINT DRILLING PROGRAM

Slim Hole Design
8 5/8" Surface & 5 1/2" Production Casing Design

DATED: 06-01-14

Directional Wells located on Ultra leases in
Three Rivers Project:

Three Rivers 4-36T-820

SHL: Sec 4 (NWSE) T8S R20E

Uintah, Utah

ONSHORE OIL & GAS ORDER NO. 1
Approval of Operations on Onshore
Federal and Indian Oil and Gas Leases

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (CFR 43, Part 3160) and the approved Application for Permit to Drill. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations.

RECEIVED: June 02, 2014

1. Formation Tops

The estimated tops of important geologic markers are as follows:

<u>Formation Top</u>	<u>Top (TVD)</u>	<u>Comments</u>
Uinta	Surface	
BMSW	1,350' MD / 1,350' TVD	
Green River	2,820' MD / 2,790' TVD	
Mahogany	4,179' MD / 4,115' TVD	
Garden Gulch	4,757' MD / 4,690' TVD	Oil & Associated Gas
Lower Green River*	4,927' MD / 4,860' TVD	Oil & Associated Gas
Wasatch	6,702' MD / 6,635' TVD	Oil & Associated Gas
TD	6,902' MD / 6,835' TVD	

Asterisks (*) denotes target pay intervals

All shows of fresh water and minerals will be reported and protected. A sample will be taken of any water flows and a water analysis furnished to the BLM. Oil and gas shows will be adequately tested for commercial possibilities, reported and protected by casing and cement.

2. BOP Equipment

- A) The BOPE shall be closed whenever the well is unattended. The Bureau of Land Management will be notified 24 hours prior to all BOPE pressure tests. The State of Utah, Division of Oil, Gas and Mining will be notified 24 hours prior to all BOPE pressure tests.
- B) The BOPE shall be closed whenever the well is unattended.
- C) As per 43 CFR 3160, Onshore Oil and Gas Order No. 2, Drilling Operations, Part A:
- 1) All BOPE connections subjected to well pressure will be flanged, welded, or clamped.
 - 2) Choke Manifold
 - 3) Tee blocks or targeted 'T's will be used and anchored to prevent slip and reduce vibration.
 - 4) Two adjustable chokes will be used in the choke manifold.
 - 5) All valves (except chokes) in kill line choke manifold and choke line will not restrict the flow.
 - 6) Pressure gauges in the well control system will be designed for drilling fluid.
- D) BOPE Testing:
- 1) BOPE shall be pressure tested when initially installed, whenever any seal subject to pressure testing is broken, or after repairs.
 - 2) All BOP tests will be performed with a test plug in place.
 - 3) BOP will be tested to full stack working pressure and annular preventer to 50% stack working pressure.

INTERVAL

0 - 1,000' MD / 1,000' TVD

1,000' MD / 1,000' TVD – 6,902' MD / 6,835' TVD

BOP EQUIPMENT

11" Diverter with Rotating Head

3,000# Ram Double BOP & Annular with Diverter & Rotating Head

NOTE: Drilling spool to accommodate choke and kill lines.

3. Casing and Float Equipment Program**CASING:**

Directional Well	Hole Size	OD	Depth MD/TVD	Wt.	Grade & Connection	Cond.
Surface	11"	8 5/8"	1,000' MD / 1,000' TVD	24.0 ppf	J-55, LTC	New
Production	7 7/8"	5 1/2"	6,902' MD / 6,835' TVD	17.0 ppf	J-55, LTC	New

CASING SPECIFICATIONS:

Directional Well	Casing OD	Casing ID / Drift ID	Collapse (psi)	Int. Yield (psi)	Ten. Yield (lb)	Jt. Strength (lb)
Surface	8 5/8"	8.097" / 7.972"	1,370	2,950	381,000	244,000
Production	5 1/2"	4.492" / 4.767"	4,910	5,320'	273,000	229,000

FLOAT EQUIPMENT:

SURFACE (8 5/8")

Float Shoe, 1 joint casing, float collar

Centralizers: 1 each 1st 4 Joints then every 4th joint to surface

PRODUCTION (5 1/2")

Float Shoe, 1 joint casing, float collar

Centralizers: 1 each 1st 4 Joints then every 3rd joint to 500' into surface casing**4. Cementing Programs****CONDUCTOR (13 3/8")**

Ready Mix – Cement to surface

SURFACE (8 5/8")

Surface – 500'

Cement Top - Surface

Lead: 80 sks, Premium Lightweight Cmt w/ additives, 11.5 ppg, 2,97 cf/sk 50% excess

500' – 1,000' MD / 1,000' TVD± Tail: 115 sks Glass G Cement w/ additives, 15.8 ppg, 1.16 cf/sx, 50% excess

Note: The above volumes are based on a gauge-hole + 50% excess.

PRODUCTION (5 1/2")

500' - 4,000' TVD ±

Cement Top – 500'

Lead: 225 sks – Econocem Cement w/ 0.25 lbm Poly-E-Flake, 1% Granulite TR 1/4, 5 lbm Kol-Seal; 11.0 ppg; 3.54 cf/sx; 15% excess

4,000' – 6,902' MD / 6,835' TVD Tail: 450 sks, Expandacem Cement w/ 0.25 lbm Poly-E-Flake, 1 lbm Granulite TR 1/4, 2 lbm Kol-Seal; 14.0 pp; 1.349 cf/sk; 15% excess

Note: Lead Cement will be brought to 4,000' which will give a minimum of 500' above Lower Green River.

- A) For Surface casing, if cement falls or does not circulate to surface, cement will be topped off.
- B) Cement will not be placed down annulus with a 1" pipe unless BLM is contacted.
- C) The Bureau of Land Management will be notified 24 hours prior to running casing and cementing.
- D) As per 43 CFR 3160, Onshore Oil and Gas Order No.2, Drilling Operations, Part B:
- 1) All waiting on cement times shall be adequate to achieve a minimum of 500 psi compressive strength at the casing shoe (minimum of 8 hours) prior to drilling out.
 - 2) Prior to drilling out cement, casing will be pressure tested to 1500 psi. Pressure decline must not be greater than 10% (150 psi) in 30 minutes.
 - 3) Progress reports, Form 3160-5 "Sundry Notices and Reports on Wells", shall be filed with the Field Manager within 30 days after the work is completed.
 - 4) Setting of each string of casing, size, grade, weight of casing set, hole size, setting depth, amounts and type of cement used, whether cement circulated or the top of the cement behind the casing, depth of cementing tools used, casing test method and results, and the date work was done. Show the spud date on the first reports submitted.
 - 5) Temperature or bond logs must be submitted for each well where the casing cement was not circulated to the surface.

- 6) A pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed after drilling 5-10 feet of new hole.

5. Mud Program

The proposed circulating mediums to be employed in drilling are as follows:

Interval	Mud Type	Viscosity	Fluid Loss	pH	Mud Wt. (ppg)
0 – 1,000' MD / 1,000' TVD	Water/Spud Mud	32	No Control (NC)	7.0 -8.2	<8.8
1,000' MD / 1,000' TVD - 6,902' MD / 6,835' TVD	DAP System	40 - 60	10 - 18	7.0-8.2	<10.0

- A) For Surface Sufficient quantities of mud materials will be maintained or readily accessible for the purpose of assuring well control during the course of drilling operations. A mud test shall be performed every 24 hours after mudding up to determine, as applicable: density, viscosity, gel strength, filtration, and pH.
- B) The mud monitoring equipment on location will be installed by top of Green River and will be able to monitor at a minimum the pit volume totalizer (PVT), stroke counter, and flow sensor
- C) Flare line discharge will be located no less than 100 feet from the wellhead using straight or targeted 'T' and anchors.

6. Evaluation Program - Testing, Logging, and Coring

- A) Cores: None anticipated.
- B) Testing: None anticipated.
- C) Directional Drilling: Directional tools will be used to locate the bottom hole per the attached directional plan +/-.
- D) Open Hole Logs: TD to surface casing: resistivity, neutron density, gamma ray and caliper.
- E) Mud Logs: None anticipated.
- F) Formation to TD; record and monitor gas shows and record drill times (normal mud logging duties).


7. Anticipated Pressures and H.S.

- A) The expected bottom hole pressure is 3,500 – 3,650 psig. Normal pressures are anticipated from surface to approximately TD. These pressures will be controlled by a blowout preventer stack, annular BOP, choke manifold, mud/gas separator, surface equipment and drilling mud. A supply of barite to weight the mud to a balancing specific gravity, if necessary, will be on location.
- B) Maximum expected surface pressure will be based on the frac gradient of the casing shoe. The design of the casing assumes that the MASP will be the fracture pressure at the shoe less a column of gas.
- C) No hydrogen sulfide gas is anticipated, however if H₂S is encountered, the guidelines in Onshore Oil and Gas Order No. 6 will be complied with.

8. Other Information and Notification Requirements

- A) There shall be no deviation from the proposed drilling and/or workover program as approved. Any changes in operation must have prior approval from the **Utah Division of Oil, Gas and Mining**, and the BLM Vernal (when drilling on Federal leases).

- 1) Anticipated starting date will be upon approval. It is anticipated that completion operations will begin within 15 days after the well has been drilled.
 - 2) It is anticipated that the drilling and completion of this well will take approximately 90 days.
- B) Notification Requirements for ***Utah Division of Oil, Gas and Mining***:
- ***Within 24 hrs. of spud (Carol Daniels at 801/538-5284)***
 - ***24 hrs. prior to testing BOP equipment (Dan Jarvis 801/538-5338 or 231-8956)***
 - ***24 hrs. prior to cementing or testing casing (Dan Jarvis)***
 - ***Within 24 hrs. of making any emergency changes to APD (Dustin Doucet 801/538-5281 or 733-0983)***
- C) Notification Requirements BLM Vernal ***when drilling on Federal leases as follows: (Cade T Taylor @ cctaylor@blm.gov and [Blm ut vn opreport@blm.gov](mailto:Blm_ut_vn_opreport@blm.gov):***
- ***Within 24 hrs. of spud (Carol Daniels at 801/538-5284)***
 - ***24 hrs. prior to testing BOP equipment (Dan Jarvis 801/538-5338 or 231-8956)***
 - ***24 hrs. prior to cementing or testing casing (Dan Jarvis)***
 - ***Within 24 hrs. of making any emergency changes to APD (Dustin Doucet 801/538-5281 or 733-0983)***
- D) Any changes in the program must be approved by the ***Utah Division of Oil, Gas and Mining*** and or the BLM Vernal Office. "Sundry Notices and Reports on Wells" (form 3160-5) must be filed for all changes of plans. Emergency approval may be obtained orally, but such approval does not waive the written report requirement.
- 1) Should the well be successfully completed for production, the BLM Pinedale Field Office must be notified when it is placed in a producing status. The notification shall provide, as a minimum, the following information items:
 - Operator name, address, and telephone number.
 - Well name and number.
 - Well location (1/4 1/4, Section, Township, Range and P.M.)
 - Date well was placed in a producing status (date of first production for which royalty will be paid).
 - The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).
 - The Federal or Indian lease prefix and number on which the well is located. As appropriate, the unit agreement name, number and participating area name. As appropriate, the communitization agreement number.

T8S, R20E, S.L.B.&M.**LEGEND:**

- 90° SYMBOL
- PROPOSED WELLHEAD.
- TARGET BOTTOM HOLE.
- SECTION CORNERS LOCATED.
- SECTION CORNERS RE-ESTABLISHED. (Not Set on Ground.)



S89°29'04"W - 5279.27' (Meas.)

CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

REGISTERED LAND SURVEYOR
REGISTRATION NO. 161319
STATE OF UTAH

NAD 83 (TARGET BOTTOM HOLE)	NAD 83 (SURFACE LOCATION)
LATITUDE = 40°08'57.41" (40.149281)	LATITUDE = 40°08'54.88" (40.148578)
LONGITUDE = 109°40'13.79" (109.670497)	LONGITUDE = 109°40'21.40" (109.672611)

BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION

BASIS OF ELEVATION

BENCH MARK (38EAM) LOCATED IN THE SW 1/4 OF SECTION 9, T7S, R20E, S.L.B.&M. TAKEN FROM THE PELICAN LAKE, QUADRANGLE, UTAH, UTAH COUNTY, 7.5 MINUTE QUAD (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 4942 FEET.



ULTRA RESOURCES, INC.


THREE RIVERS #4-36T-820
NW 1/4 SE 1/4, SECTION 4, T8S, R20E, S.L.B.&M.
UINTAH COUNTY, UTAH

SURVEYED BY: M.P. T.P.	SCALE: 1"=1000'	DRAWN BY: H.W.
DATE: 04-22-14		DATE: 04-30-14

WELL LOCATION PLAT

UELS, LLC
Corporate Office * 85 South 200 East
Vernal, UT 84078 * (435) 789-1017

RECEIVED: May 13, 2014



LEGEND:

 **PROPOSED LOCATION**

ULTRA RESOURCES, INC.

**THREE RIVERS #4-36T-820, #4-34-820 & #4-38T-820
SECTION 4, T8S, R20E, S.L.B.&M.
NW 1/4 SE 1/4**

DRAWN BY: J.M.C.

DATE DRAWN: 05-06-14

SCALE: 1:100,000

REV: 00-00-00

ACCESS ROAD MAP


TOPO A

UELS, LLC

Corporate Office * 85 South 200 East
Vernal, UT 84078 * (435) 789-1017



RECEIVED: May 13, 2014



NOTE: PARCEL DATA SHOWN HAS BEEN OBTAINED FROM VARIOUS SOURCES AND SHOULD BE USED FOR MAPPING, GRAPHIC AND PLANNING PURPOSES ONLY. NO WARRANTY IS MADE BY UINTAH ENGINEERING AND LAND SURVEYING (UELS) FOR ACCURACY OF THE PARCEL DATA.

LEGEND:

- EXISTING ROAD
- - - PROPOSED ROAD
- - - PROPOSED ROAD (SERVICING OTHER WELLS)
- - - EXISTING 2-TRACK
- * * EXISTING FENCE
- - - EXISTING POWER LINE



UELS, LLC
Corporate Office * 85 South 200 East
Vernal, UT 84078 * (435) 789-1017



ULTRA RESOURCES, INC.

THREE RIVERS #4-36T-820, #4-34-820 & #4-38T-820
SECTION 4, T8S, R20E, S.L.B.&M.
NW 1/4 SE 1/4

DRAWN BY: J.M.C.

DATE DRAWN: 05-06-14


SCALE: 1" = 2000'

REV: 00-00-00

ACCESS ROAD MAP

TOPO B

RECEIVED: May 13, 2014

**LEGEND:**

- DISPOSAL WELLS
- PRODUCING WELLS
- SHUT IN WELLS
- WATER WELLS
- ABANDONED WELLS
- TEMPORARILY ABANDONED

ULTRA RESOURCES, INC.

THREE RIVERS #4-36T-820, #4-34-820 & #4-38T-820
SECTION 4, T8S, R20E, S.L.B.&M.
NW 1/4 SE 1/4

DRAWN BY: J.M.C.

DATE DRAWN: 05-06-14


SCALE: 1" = 2000'

REV: 00-00-00

WELL PROXIMITY MAP**TOPO C****UELS, LLC**

Corporate Office * 85 South 200 East
 Vernal, UT 84078 * (435) 789-1017

RECEIVED: May 13, 2014



APPROXIMATE TOTAL PIPELINE DISTANCE = 116' +/-

NOTE: PARCEL DATA SHOWN HAS BEEN OBTAINED FROM VARIOUS SOURCES AND SHOULD BE USED FOR MAPPING, GRAPHIC AND PLANNING PURPOSES ONLY. NO WARRANTY IS MADE BY UTAH ENGINEERING AND LAND SURVEYING (UELS) FOR ACCURACY OF THE PARCEL DATA.

LEGEND:

- PROPOSED ROAD
- EXISTING PIPELINE
- PROPOSED PIPELINE
- PROPOSED PIPELINE (SERVICING OTHER WELLS)

ULTRA RESOURCES, INC.

**THREE RIVERS #4-36T-820, #4-34-820 & #4-38T-820
SECTION 4, T8S, R20E, S.L.B.&M.
NW 1/4 SE 1/4**

DRAWN BY: J.M.C.

DATE DRAWN: 05-06-14

SCALE: 1" = 2000'

REV: 00-00-00


PIPELINE MAP

TOPO D



UELS, LLC
Corporate Office * 85 South 200 East
Vernal, UT 84078 * (435) 789-1017



RECEIVED: May 13, 2014



APPROXIMATE TOTAL POWER LINE DISTANCE = 157' +/-

NOTE: PARCEL DATA SHOWN HAS BEEN OBTAINED FROM VARIOUS SOURCES AND SHOULD BE USED FOR MAPPING, GRAPHIC AND PLANNING PURPOSES ONLY. NO WARRANTY IS MADE BY UINTAH ENGINEERING AND LAND SURVEYING (UELS) FOR ACCURACY OF THE PARCEL DATA.

LEGEND:

-  EXISTING ROAD
 PROPOSED ROAD
 EXISTING POWER LINE
 PROPOSED POWER LINE
 PROPOSED PIPELINE (SERVICING OTHER WELLS)

ULTRA RESOURCES, INC.

**THREE RIVERS #4-36T-820, #4-34-820 & #4-38T-820
SECTION 4, T8S, R20E, S.L.B&M.
NW 1/4 SE 1/4**

DRAWN BY: J.M.C.

DATE DRAWN: 05-06-14

SCALE: 1" = 2000'

REV: 00-00-00

POWER LINE MAP

TOPO E



UELS, LLC

**Corporate Office * 85 South 200 East
Vernal, UT 84078 * (435) 789-1017**



ULTRA RESOURCES, INC

Location: Three Rivers Slot: Three Rivers 4-36T-820 (1529' FSL & 2373' FEL)
 Field: UINAH COUNTY Well: Three Rivers 4-36T-820
 Facility: Sec.04-T8S-R20E Wellbore: Three Rivers 4-36T-820 PWB

Targets

Name	MD (ft)	TVD (ft)	Local N (ft)	Local E (ft)	Grid East (US ft)	Grid North (US ft)	Latitude	Longitude
Three Rivers 4-36T-820 1780' FSL & 1780' FEL	4729.27	4662.00	256.03	550.94	2151778.05	7228330.12	40°08'57.410"N	109°40'13.790"W



Well Profile Data

Design Comment	MD (ft)	Inc. (°)	Az. (°)	TVD (ft)	Local N (ft)	Local E (ft)	DLS (°/100ft)	VS (ft)
Tie On	13.00	0.000	66.575	13.00	0.00	0.00	0.00	0.00
End of Tangent	1200.00	0.000	66.575	1200.00	0.00	0.00	0.00	0.00
Build (S)	1844.34	12.867	66.575	1838.92	28.69	66.21	2.00	72.16
End of Tangent (S)	4084.93	12.867	66.575	4023.08	227.34	524.73	0.00	571.87
Drop (S)	4729.27	0.000	66.575	4662.00	256.03	590.94	2.00	644.02
End of Tangent	6902.27	0.000	66.575	6835.00	256.03	590.94	0.00	644.02

Location Information

Facility Name	Grid East (US ft)	Grid North (US ft)	Latitude	Longitude
Sec.04-T8S-R20E	215127.011	723055.135	40°08'53.110"N	109°39'53.807"W
Slot	Local N (ft)	Local E (ft)	Grid East (US ft)	Grid North (US ft)
Three Rivers 4-36T-820 (1529' FSL & 2373' FEL)	-255.03	-187.95	2151102.509	7228662.008
Rig on Three Rivers 4-36T-820 (1529' FSL & 2373' FEL) to Mud line (At Slot Three Rivers 4-36T-820 (1529' FSL & 2373' FEL))				4765.48
Mean Sea Level to Mud line (At Slot Three Rivers 4-36T-820 (1529' FSL & 2373' FEL))				0
Rig on Three Rivers 4-36T-820 (1529' FSL & 2373' FEL) to Mean Sea Level				4765.48

Plot reference wellpath is Three Rivers 4-36T-820 PWB	Grid System: NAD83 / Lambert Utah SP, Central Zone (4302), US feet
True vertical depths are referenced to Rig on Three Rivers 4-36T-820 (1529' FSL & 2373' FEL) (RT)	North Reference: True north
Measured depths are referenced to Rig on Three Rivers 4-36T-820 (1529' FSL & 2373' FEL) (RT)	Scale: True distance
Rig on Three Rivers 4-36T-820 (1529' FSL & 2373' FEL) to Mean Sea Level: 4765.4 feet	Depths are in feet
Mean Sea Level to Mud line (At Slot Three Rivers 4-36T-820 (1529' FSL & 2373' FEL)): 0 feet	Coordinates are in feet referenced to Slot
	Created by: ewilliams on 5/27/2014





Planned Wellpath Report

Three Rivers 4-36T-820 PWP

Page 1 of 5



REFERENCE WELLPATH IDENTIFICATION

Operator	ULTRA RESOURCES, INC	Slot	Three Rivers 4-36T-820 (1529' FSL & 2373' FEL)
Area	Three Rivers	Well	Three Rivers 4-36T-820
Field	UINTAH COUNTY	Wellbore	Three Rivers 4-36T-820 PWB
Facility	Sec.04-T8S-R20E		

REPORT SETUP INFORMATION

Projection System	NAD83 / Lambert Utah SP, Central Zone (4302), US feet	Software System	WellArchitect® 3.0.0
North Reference	True	User	EWilliams
Scale	0.999914	Report Generated	5/27/2014 at 2:11:57 PM
Convergence at slot	1.17° East	Database/Source file	WellArchitectDB/Three_Rivers_4-36T-820_PWB.xml

WELLPATH LOCATION

	Local coordinates		Grid coordinates		Geographic coordinates	
	North[ft]	East[ft]	Easting[US ft]	Northing[US ft]	Latitude	Longitude
Slot Location	-2553.03	-1987.95	2151192.51	7228062.10	40°08'54.880"N	109°40'21.400"W
Facility Reference Pt			2153127.51	7230655.14	40°09'20.110"N	109°39'55.800"W
Field Reference Pt			2156630.96	7236613.42	40°10'18.270"N	109°39'09.100"W

WELLPATH DATUM

Calculation method	Minimum curvature	Rig on Three Rivers 4-36T-820 (1529' FSL & 2373' FWL) (RT) to Facility Vertical Datum
Horizontal Reference Pt	Slot	Rig on Three Rivers 4-36T-820 (1529' FSL & 2373' FWL) (RT) to Mean Sea Level
Vertical Reference Pt	Rig on Three Rivers 4-36T-820 (1529' FSL & 2373' FWL) (RT)	Rig on Three Rivers 4-36T-820 (1529' FSL & 2373' FWL) (RT) to Mud Line at Slot (Three Rivers 4-36T-820 (1529' FSL & 2373' FEL))
MD Reference Pt	Rig on Three Rivers 4-36T-820 (1529' FSL & 2373' FWL) (RT)	Section Origin
Field Vertical Reference	Mean Sea Level	Section Azimuth

CONFIDENTIAL



Planned Wellpath Report

Three Rivers 4-36T-820 PWP

Page 2 of 5



REFERENCE WELLPATH IDENTIFICATION

Operator	ULTRA RESOURCES, INC	Slot	Three Rivers 4-36T-820 (1529' FSL & 2373' FEL)
Area	Three Rivers	Well	Three Rivers 4-36T-820
Field	UINTAH COUNTY	Wellbore	Three Rivers 4-36T-820 PWB
Facility	Sec.04-T8S-R20E		

WELLPATH DATA (82 stations) † = interpolated/extrapolated station

MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Vert Sect [ft]	North [ft]	East [ft]	Latitude	Longitude	DLS [°/100ft]	Comments
0.00†	0.000	66.575	0.00	0.00	0.00	0.00	40°08'54.880"N	109°40'21.400"W	0.00	
13.00	0.000	66.575	13.00	0.00	0.00	0.00	40°08'54.880"N	109°40'21.400"W	0.00	
113.00†	0.000	66.575	113.00	0.00	0.00	0.00	40°08'54.880"N	109°40'21.400"W	0.00	
120.00†	0.000	66.575	120.00	0.00	0.00	0.00	40°08'54.880"N	109°40'21.400"W	0.00	Base Gravel
213.00†	0.000	66.575	213.00	0.00	0.00	0.00	40°08'54.880"N	109°40'21.400"W	0.00	
313.00†	0.000	66.575	313.00	0.00	0.00	0.00	40°08'54.880"N	109°40'21.400"W	0.00	
413.00†	0.000	66.575	413.00	0.00	0.00	0.00	40°08'54.880"N	109°40'21.400"W	0.00	
513.00†	0.000	66.575	513.00	0.00	0.00	0.00	40°08'54.880"N	109°40'21.400"W	0.00	
613.00†	0.000	66.575	613.00	0.00	0.00	0.00	40°08'54.880"N	109°40'21.400"W	0.00	
713.00†	0.000	66.575	713.00	0.00	0.00	0.00	40°08'54.880"N	109°40'21.400"W	0.00	
813.00†	0.000	66.575	813.00	0.00	0.00	0.00	40°08'54.880"N	109°40'21.400"W	0.00	
913.00†	0.000	66.575	913.00	0.00	0.00	0.00	40°08'54.880"N	109°40'21.400"W	0.00	
1013.00†	0.000	66.575	1013.00	0.00	0.00	0.00	40°08'54.880"N	109°40'21.400"W	0.00	
1113.00†	0.000	66.575	1113.00	0.00	0.00	0.00	40°08'54.880"N	109°40'21.400"W	0.00	
1200.00	0.000	66.575	1200.00	0.00	0.00	0.00	40°08'54.880"N	109°40'21.400"W	0.00	
1213.00†	0.260	66.575	1213.00	0.03	0.01	0.03	40°08'54.880"N	109°40'21.400"W	2.00	
1313.00†	2.260	66.575	1312.97	2.23	0.89	2.04	40°08'54.889"N	109°40'21.374"W	2.00	
1350.07†	3.001	66.575	1350.00	3.93	1.56	3.61	40°08'54.895"N	109°40'21.354"W	2.00	BMSW
1413.00†	4.260	66.575	1412.80	7.91	3.15	7.26	40°08'54.911"N	109°40'21.306"W	2.00	
1513.00†	6.260	66.575	1512.38	17.08	6.79	15.67	40°08'54.947"N	109°40'21.198"W	2.00	
1613.00†	8.260	66.575	1611.57	29.72	11.81	27.27	40°08'54.997"N	109°40'21.049"W	2.00	
1713.00†	10.260	66.575	1710.26	45.81	18.21	42.03	40°08'55.060"N	109°40'20.859"W	2.00	
1813.00†	12.260	66.575	1808.33	65.33	25.97	59.95	40°08'55.137"N	109°40'20.628"W	2.00	
1844.34	12.887	66.575	1838.92	72.16	28.69	66.21	40°08'55.163"N	109°40'20.547"W	2.00	
1913.00†	12.887	66.575	1905.85	87.47	34.77	80.26	40°08'55.224"N	109°40'20.366"W	0.00	
2013.00†	12.887	66.575	2003.33	109.77	43.64	100.72	40°08'55.311"N	109°40'20.103"W	0.00	
2113.00†	12.887	66.575	2100.81	132.07	52.51	121.19	40°08'55.399"N	109°40'19.839"W	0.00	
2213.00†	12.887	66.575	2198.30	154.38	61.37	141.65	40°08'55.486"N	109°40'19.576"W	0.00	
2313.00†	12.887	66.575	2295.78	176.68	70.24	162.12	40°08'55.574"N	109°40'19.312"W	0.00	
2413.00†	12.887	66.575	2393.26	198.98	79.10	182.58	40°08'55.662"N	109°40'19.049"W	0.00	
2513.00†	12.887	66.575	2490.74	221.28	87.97	203.05	40°08'55.749"N	109°40'18.785"W	0.00	
2613.00†	12.887	66.575	2588.22	243.59	96.84	223.51	40°08'55.837"N	109°40'18.522"W	0.00	
2713.00†	12.887	66.575	2685.70	265.89	105.70	243.98	40°08'55.925"N	109°40'18.258"W	0.00	
2813.00†	12.887	66.575	2783.18	288.19	114.57	264.44	40°08'56.012"N	109°40'17.995"W	0.00	
2819.99†	12.887	66.575	2790.00	289.75	115.19	265.87	40°08'56.018"N	109°40'17.976"W	0.00	Green River Top
2913.00†	12.887	66.575	2880.66	310.49	123.44	284.90	40°08'56.100"N	109°40'17.731"W	0.00	
3013.00†	12.887	66.575	2978.15	332.80	132.30	305.37	40°08'56.187"N	109°40'17.468"W	0.00	
3113.00†	12.887	66.575	3075.63	355.10	141.17	325.83	40°08'56.275"N	109°40'17.204"W	0.00	
3213.00†	12.887	66.575	3173.11	377.40	150.03	346.30	40°08'56.363"N	109°40'16.940"W	0.00	
3313.00†	12.887	66.575	3270.59	399.70	158.90	366.76	40°08'56.450"N	109°40'16.677"W	0.00	
3413.00†	12.887	66.575	3368.07	422.01	167.77	387.23	40°08'56.538"N	109°40'16.413"W	0.00	
3513.00†	12.887	66.575	3465.55	444.31	176.63	407.69	40°08'56.625"N	109°40'16.150"W	0.00	
3613.00†	12.887	66.575	3563.03	466.61	185.50	428.16	40°08'56.713"N	109°40'15.886"W	0.00	
3713.00†	12.887	66.575	3660.51	488.91	194.37	448.62	40°08'56.801"N	109°40'15.623"W	0.00	
3813.00†	12.887	66.575	3758.00	511.22	203.23	469.08	40°08'56.888"N	109°40'15.359"W	0.00	



Planned Wellpath Report

Three Rivers 4-36T-820 PWP

Page 3 of 5



REFERENCE WELLPATH IDENTIFICATION

Operator	ULTRA RESOURCES, INC	Slot	Three Rivers 4-36T-820 (1529' FSL & 2373' FEL)
Area	Three Rivers	Well	Three Rivers 4-36T-820
Field	UINTAH COUNTY	Wellbore	Three Rivers 4-36T-820 PWB
Facility	Sec.04-T8S-R20E		

WELLPATH DATA (82 stations) † = interpolated/extrapolated station

MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Vert Sect [ft]	North [ft]	East [ft]	Latitude	Longitude	DLS [°/100ft]	Comments
3913.00†	12.887	66.575	3855.48	533.52	212.10	489.55	40°08'56.976"N	109°40'15.096"W	0.00	
4013.00†	12.887	66.575	3952.96	555.82	220.96	510.01	40°08'57.064"N	109°40'14.832"W	0.00	
4084.93	12.887	66.575	4023.08	571.87	227.34	524.73	40°08'57.127"N	109°40'14.643"W	0.00	
4113.00†	12.325	66.575	4050.47	577.99	229.78	530.35	40°08'57.151"N	109°40'14.570"W	2.00	
4178.89†	11.008	66.575	4115.00	591.31	235.07	542.58	40°08'57.203"N	109°40'14.413"W	2.00	Mahogany
4213.00†	10.325	66.575	4148.52	597.63	237.58	548.37	40°08'57.228"N	109°40'14.338"W	2.00	
4313.00†	8.325	66.575	4247.19	613.83	244.02	563.24	40°08'57.291"N	109°40'14.147"W	2.00	
4413.00†	6.325	66.575	4346.37	626.58	249.09	574.94	40°08'57.341"N	109°40'13.996"W	2.00	
4513.00†	4.325	66.575	4445.93	635.86	252.78	583.46	40°08'57.378"N	109°40'13.886"W	2.00	
4613.00†	2.325	66.575	4545.76	641.66	255.09	588.78	40°08'57.401"N	109°40'13.818"W	2.00	
4713.00†	0.325	66.575	4645.73	643.98	256.01	590.90	40°08'57.410"N	109°40'13.791"W	2.00	
4729.27	0.000	66.575	4662.00†	644.02	256.03	590.94	40°08'57.410"N	109°40'13.790"W	2.00	
4757.27†	0.000	66.575	4690.00	644.02	256.03	590.94	40°08'57.410"N	109°40'13.790"W	0.00	Garden Gulch
4813.00†	0.000	66.575	4745.73	644.02	256.03	590.94	40°08'57.410"N	109°40'13.790"W	0.00	
4913.00†	0.000	66.575	4845.73	644.02	256.03	590.94	40°08'57.410"N	109°40'13.790"W	0.00	
4927.27†	0.000	66.575	4860.00	644.02	256.03	590.94	40°08'57.410"N	109°40'13.790"W	0.00	Lower Green River (Top of Production)
5013.00†	0.000	66.575	4945.73	644.02	256.03	590.94	40°08'57.410"N	109°40'13.790"W	0.00	
5113.00†	0.000	66.575	5045.73	644.02	256.03	590.94	40°08'57.410"N	109°40'13.790"W	0.00	
5213.00†	0.000	66.575	5145.73	644.02	256.03	590.94	40°08'57.410"N	109°40'13.790"W	0.00	
5313.00†	0.000	66.575	5245.73	644.02	256.03	590.94	40°08'57.410"N	109°40'13.790"W	0.00	
5413.00†	0.000	66.575	5345.73	644.02	256.03	590.94	40°08'57.410"N	109°40'13.790"W	0.00	
5513.00†	0.000	66.575	5445.73	644.02	256.03	590.94	40°08'57.410"N	109°40'13.790"W	0.00	
5613.00†	0.000	66.575	5545.73	644.02	256.03	590.94	40°08'57.410"N	109°40'13.790"W	0.00	
5713.00†	0.000	66.575	5645.73	644.02	256.03	590.94	40°08'57.410"N	109°40'13.790"W	0.00	
5813.00†	0.000	66.575	5745.73	644.02	256.03	590.94	40°08'57.410"N	109°40'13.790"W	0.00	
5913.00†	0.000	66.575	5845.73	644.02	256.03	590.94	40°08'57.410"N	109°40'13.790"W	0.00	
6013.00†	0.000	66.575	5945.73	644.02	256.03	590.94	40°08'57.410"N	109°40'13.790"W	0.00	
6113.00†	0.000	66.575	6045.73	644.02	256.03	590.94	40°08'57.410"N	109°40'13.790"W	0.00	
6213.00†	0.000	66.575	6145.73	644.02	256.03	590.94	40°08'57.410"N	109°40'13.790"W	0.00	
6313.00†	0.000	66.575	6245.73	644.02	256.03	590.94	40°08'57.410"N	109°40'13.790"W	0.00	
6413.00†	0.000	66.575	6345.73	644.02	256.03	590.94	40°08'57.410"N	109°40'13.790"W	0.00	
6513.00†	0.000	66.575	6445.73	644.02	256.03	590.94	40°08'57.410"N	109°40'13.790"W	0.00	
6613.00†	0.000	66.575	6545.73	644.02	256.03	590.94	40°08'57.410"N	109°40'13.790"W	0.00	
6702.27†	0.000	66.575	6635.00	644.02	256.03	590.94	40°08'57.410"N	109°40'13.790"W	0.00	Wasatch
6713.00†	0.000	66.575	6645.73	644.02	256.03	590.94	40°08'57.410"N	109°40'13.790"W	0.00	
6813.00†	0.000	66.575	6745.73	644.02	256.03	590.94	40°08'57.410"N	109°40'13.790"W	0.00	
6902.27	0.000	66.575	6835.00	644.02	256.03	590.94	40°08'57.410"N	109°40'13.790"W	0.00	TD



Planned Wellpath Report

Three Rivers 4-36T-820 PWP

Page 4 of 5



REFERENCE WELLPATH IDENTIFICATION

Operator	ULTRA RESOURCES, INC	Slot	Three Rivers 4-36T-820 (1529' FSL & 2373' FEL)
Area	Three Rivers	Well	Three Rivers 4-36T-820
Field	UINTAH COUNTY	Wellbore	Three Rivers 4-36T-820 PWB
Facility	Sec.04-T8S-R20E		

HOLE & CASING SECTIONS - Ref Wellbore: Three Rivers 4-36T-820 PWB Ref Wellpath: Three Rivers 4-36T-820 PWP

String/Diameter	Start MD [ft]	End MD [ft]	Interval [ft]	Start TVD [ft]	End TVD [ft]	Start N/S [ft]	Start E/W [ft]	End N/S [ft]	End E/W [ft]
16in Conductor	13.00	120.00	107.00	13.00	120.00	0.00	0.00	0.00	0.00
12.25in Open Hole	120.00	1000.00	880.00	120.00	1000.00	0.00	0.00	0.00	0.00
8.625in Casing Surface	13.00	1000.00	987.00	13.00	1000.00	0.00	0.00	0.00	0.00
7.875in Open Hole	1000.00	6902.27	5902.27	1000.00	6835.00	0.00	0.00	256.03	590.94
5.5in Casing Production	13.00	6902.27	6889.27	13.00	6835.00	0.00	0.00	256.03	590.94

TARGETS

Name	MD [ft]	TVD [ft]	North [ft]	East [ft]	Grid East [US ft]	Grid North [US ft]	Latitude	Longitude	Shape
1) Three Rivers 4-36T-820 1780' FSL & 1780' FEL	4729.27	4662.00	256.03	590.94	2151778.05	7228330.12	40°08'57.410"N	109°40'13.790"W	point

CONFIDENTIAL



Planned Wellpath Report

Three Rivers 4-36T-820 PWP

Page 5 of 5



REFERENCE WELLPATH IDENTIFICATION

Operator	ULTRA RESOURCES, INC	Slot	Three Rivers 4-36T-820 (1529' FSL & 2373' FEL)
Area	Three Rivers	Well	Three Rivers 4-36T-820
Field	UINTAH COUNTY	Wellbore	Three Rivers 4-36T-820 PWB
Facility	Sec.04-T8S-R20E		

WELLPATH COMMENTS

MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Comment
120.00	0.000	66.575	120.00	Base Gravel
1350.07	3.001	66.575	1350.00	BMSW
2819.99	12.887	66.575	2790.00	Green River Top
4178.89	11.008	66.575	4115.00	Mahogany
4757.27	0.000	66.575	4690.00	Garden Gulch
4927.27	0.000	66.575	4860.00	Lower Green River (Top of Production)
6702.27	0.000	66.575	6635.00	Wasatch
6902.27	0.000	66.575	6835.00	TD

CONFIDENTIAL

AFFIDAVIT OF SURFACE OWNERSHIP

I, **Ned Higgins**, Affiant, being duly sworn, depose and say:

THAT, I am a Senior Landman, for **Ultra Resources, Inc.**, a Wyoming corporation authorized to do business in Utah (hereinafter referred to as "Ultra"), whose address is 304 Inverness Way South, Suite 295, Englewood, Colorado 80112 and that Ultra operates and manages oil and gas interests in the State of Utah including the lands in Uintah County, Utah described herein below ("Lands"):

See Exhibit "A" attached hereto for a description of the Lands

WHEREAS, UPL Three Rivers Holdings, LLC ("Three Rivers"), whose address is 304 Inverness Way South, Suite 295, Englewood, Colorado 80112, purchased the surface estate in and to the lands described herein above as reflected in that certain Warranty Deed dated May 1st, 2014 and recorded at Book 1378, Page 940 of the Uintah County Clerk and Records Office Official records and;

WHEREAS, Ultra and Three Rivers are both wholly owned subsidiaries of Ultra Petroleum Corp. and Ultra is operating on behalf of Three Rivers;

THEREFORE, Ultra is filing this Affidavit in the Records of Uintah County, Utah to provide notice to the public and all concerned parties so that any inquires or emergencies that may occur which require immediate notification and attention by Ultra should be directed to:

Ultra Resources, Inc.
304 Inverness Way South, Suite 295
Englewood, Colorado 80112
Main Phone: 303-708-9740
Emergency Phone: 1-800-770-9210

FURTHER Affiant sayeth not.

Subscribed and sworn to this the 9th day of May, 2014.

Ned Higgins
Ultra Resources, Inc. - Senior Landman

STATE OF COLORADO)
 :SS
COUNTY OF DOUGLAS)

The foregoing Affidavit of Surface Ownership was acknowledged before me by Ned Higgins as Senior Landman of Ultra Resources, Inc., on this 9th day of May, 2014.

WITNESS my hand and official seal.

My Commission Expires:

3/3/15



My Commission Expires March 3, 2015

NOTARY PUBLIC

EXHIBIT A

Description of Lands

Parcel #1

Section 4, Township 8 South, Range 20 East, Salt Lake Meridian:

The East half of the Southeast Quarter of the Northwest Quarter; and the Southwest Quarter of the Northeast Quarter.

Serial No. 09:003:0001

Parcel #2

Beginning at a point which is 20 rods East of center of Section 4, Township 8 South, Range 20 East, Salt Lake Meridian; running thence South 80 rods; thence East 121.29 feet; thence North 238.71 feet; thence East 208.71 feet; thence North 1081.29 feet; thence West 20 rods to the point of beginning.

Serial No. 09:003:0016

Parcel #3

Beginning at the Northwest corner of the Northeast Quarter of the Southwest Quarter of Section 4, Township 8 South, Range 20 East, Salt Lake Base and Meridian and running thence South 80 rods; thence East 100 rods; thence North 80 rods; thence West 100 rods to the point of beginning.

Serial No. 09:003:0005

Parcel #4

Section 4, Township 8 South, Range 20 East, Salt Lake Base and Meridian:


The West half of the Southeast Quarter of the Northwest Quarter.

Serial No. 09:003:0014


Parcel #5

Beginning at a point 660 feet East and 30 feet North of the Southwest corner of the Northwest quarter of the Southeast quarter of Section 4, Township 8 South, Range 20 East, Salt Lake Meridian; thence North 208.71 feet; thence West 208.71 feet; thence South 208.71 feet; thence East 208.71 feet to the point of beginning.

Serial No. 09:003:0015



BOP Equipment 3000psi WP





Ultra Resources, Inc.

May 13, 2014

Mr. Dustin Doucet
Utah Division of Oil, Gas & Mining
1594 West North Temple
Salt Lake City, Utah 84116

RE: **Directional Drilling – Docket No. 2013-030 / Cause No. 270-02**

Three Rivers 4-36T-820
SHL: 1529' FSL, 2373' FEL, NWSE, Sec 4, T8S, R20E
BHL: 1780' FSL, 1780' FEL, NWSE, Sec 4, T8S, R20E
SLB&M, Uintah County, UT

Mr. Doucet:

Ultra Resources, Inc. ("Ultra") respectfully submits the below specifics concerning the proposed directional drilling of the subject well:

- Ultra is the sole owner of 100% of the leasehold rights with respect to all tracts within 460' around the full wellbore path of the proposed directional well.
- There are no unleased mineral interests with respect to all tracts within 460' around the full wellbore path of the proposed directional well.
- The anticipated points of intersection with the objective (spaced) formation and the anticipated productive interval are within the established setbacks.
- The bottom hole location is within the established setbacks.
- The directional drilling of the well is proposed to limit surface disturbance within the project and affected surface owners.

Therefore, based on the above stated information, Ultra requests the permit be granted pursuant to Cause No. 270-02.

Thank you in advance for your consideration. Please feel free to contact me at 303-645-9810 if you have any questions or comments.

Sincerely,

Debbie Ghani
Sr. Permitting Specialist

304 Inverness Way South, Suite 295, Englewood, CO 80112
Telephone 303-708-9740 Facsimile 303-708-9748

RECEIVED: May 13, 2014




PHOTO: VIEW FROM CORNER #5 TO LOCATION STAKE

CAMERA ANGLE: SOUTHERLY




PHOTO: VIEW FROM BEGINNING OF PROPOSED ACCESS

CAMERA ANGLE: WESTERLY

ULTRA RESOURCES, INC.


**THREE RIVERS #4-36T-820, #4-34-820 & #4-38T-820
SECTION 4, T8S, R20E, S.L.B&M.
NW 1/4 SE 1/4**





UELS, LLC
Corporate Office * 85 South 200 East
Vernal, UT 84078 * (435) 789-1017

DRAWN BY: J.M.C.	DATE DRAWN: 05-06-14
TAKEN BY: B.H.	REV: 00-00-00
LOCATION PHOTOS	PHOTO

RECEIVED: May 13, 2014



RECEIVED: May 13, 2014



APPROXIMATE EARTHWORK QUANTITIES	
(12") TOPSOIL STRIPPING	3,370 Cu. Yds.
REMAINING LOCATION	3,590 Cu. Yds.
TOTAL CUT	6,960 Cu. Yds.
FILL	2,480 Cu. Yds.
EXCESS MATERIAL	4,480 Cu. Yds.
TOPSOIL & PIT BACKFILL (1/2 Pit Vol.)	4,480 Cu. Yds.
EXCESS UNBALANCE (After Interim Rehabilitation)	0 Cu. Yds.

APPROXIMATE SURFACE DISTURBANCE AREAS		
	DISTANCE	ACRES
WELL SITE DISTURBANCE	NA	±3.352
30' WIDE ACCESS ROAD R-O-W DISTURBANCE	±103.77'	±0.071
30' WIDE PIPELINE R-O-W DISTURBANCE	±86.63'	±0.060
30' WIDE POWER LINE R-O-W DISTURBANCE	±127.80'	±0.088
TOTAL SURFACE USE AREA	±318.20'	±3.571

NOTES:

- Fill quantity includes 5% for compaction.
- Calculations based on 12" of topsoil stripping.
- Topsoil should not be stripped below finished grade on substructure area.

ULTRA RESOURCES, INC.

THREE RIVERS #4-36T-820, #4-34-820 & #4-38T-820
SECTION 4, T8S, R20E, S.L.B.&M.
NW 1/4 SE 1/4



UELS, LLC
 Corporate Office * 85 South 200 East
 Vernal, UT 84078 * (435) 789-1017

DRAWN BY: H.W.	SCALE: AS SHOWN
DATE DRAWN: 04-30-14	REVISED: 00-00-00
TYPICAL CROSS SECTIONS	FIGURE #2

RECEIVED: May 13, 2014

RECEIVED: May 13, 2014

NW 1/4

NE 1/4

Sec. 4

1/4 Section Line

1/4 Section Line

1/16 Section Line

1/16 Section Line

SW 1/4

SE 1/4

Section Line

500°27'22"E - 2652.40' (Meas.)

SE Cor. Sec. 4
Alum. Cap

SW Cor. Sec. 4
2011 Alum. Cap
0.2' High

S89°29'04"W - 5279.27' (Meas.)

Section Line

BEGINNING OF ROAD STA. 0+00 BEARS
S30°55'34"W 1346.37' FROM THE NORTHEAST
CORNER OF THE NW 1/4 SE 1/4 OF SECTION
4, T8S, R20E, S.L.B.&M.

END OF ROAD STA. 1+03.77 BEARS
S34°34'46"W 1402.00' FROM THE NORTHEAST
CORNER OF THE NW 1/4 SE 1/4 OF THE NW
1/4 SW 1/4 OF SECTION 4, T8S, R20E,
S.L.B.&M.

Existing Underground
Pipeline

Proposed Three Rivers
#4-23-820 Well Pad
(3.280 Ac)

**SURFACE USE AREA
THREE RIVERS #4-36T-820,
#4-34-820 & #4-38T-820**
Contains 3.352 Acres

Proposed Access
Road for the Three
Rivers #4-23-820
Well Pad

**CLAY L &
ROSEANNA
BATTY**

Existing Three
Rivers #4-33-820
Well Pad

END OF PROPOSED
ROAD RIGHT-OF-WAY
STA. 1+03.77
(At Edge of Surface Use Area)

Existing
Fence

Existing
Power
Line

BEGINNING OF PROPOSED
ROAD RIGHT-OF-WAY
STA. 0+00
(At Proposed Access Road for the
Three Rivers #4-23-820 Wells Pad)

LINE TABLE		
LINE	DIRECTION	LENGTH
L1	N89°38'56"W	103.77'
L2	N89°43'04"W	29.33'
L3	N00°05'43"W	123.94'
L4	N53°43'06"E	34.91'
L5	N88°49'14"E	436.66'
L6	S00°41'42"E	280.74'
L7	S63°35'56"W	136.07'
L8	S89°20'22"W	135.26'
L9	N62°38'10"W	98.15'
L10	S89°04'48"W	123.38'
L11	N00°05'43"W	146.07'

SURFACE USE AREA DESCRIPTION

BEGINNING AT A POINT IN THE NW 1/4 SE 1/4 OF SECTION 4, T8S, R20E, S.L.B.&M., WHICH BEARS S34°34'46"W 1402.00' FROM THE NORTHEAST CORNER OF THE NW 1/4 SE 1/4 OF SAID SECTION 4, THENCE N89°43'04"W 29.33'; THENCE N00°05'43"W 123.94'; THENCE N53°43'06"E 34.91'; THENCE N88°49'14"E 436.66'; THENCE S00°41'42"E 280.74'; THENCE S63°35'56"W 136.07'; THENCE S89°20'22"W 135.26'; THENCE N62°38'10"W 98.15'; THENCE S89°04'48"W 123.38'; THENCE N00°05'43"W 146.07' TO THE POINT OF BEGINNING. BASIS OF BEARINGS IS A G.P.S. OBSERVATION. CONTAINS 3.352 ACRES MORE OR LESS.

ROAD RIGHT-OF-WAY DESCRIPTION ON CLAY L. & ROSEANNA BATTY LANDS

A 30' WIDE RIGHT-OF-WAY 15' ON EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE.

BEGINNING AT A POINT IN THE NW 1/4 SE 1/4 OF SECTION 4, T8S, R20E, S.L.B.&M., WHICH BEARS S30°55'34"W 1346.37' FROM THE NORTHEAST CORNER OF THE NW 1/4 SE 1/4 OF SAID SECTION 4, THENCE N89°38'56"W 103.77' TO A POINT IN THE NW 1/4 SE 1/4 OF SAID SECTION 4, WHICH BEARS S34°34'46"W 1402.00' FROM THE NORTHEAST CORNER OF THE NW 1/4 SE 1/4 OF SAID SECTION 4. THE SIDE LINES OF SAID DESCRIBED RIGHT-OF-WAY BEING SHORTENED OR ELONGATED TO MEET THE GRANTOR'S PROPERTY LINES. BASIS OF BEARINGS IS A G.P.S. OBSERVATION. CONTAINS 0.071 ACRES MORE OR LESS.


Proposed Three
Rivers #4-43-820
Well Pad
(Approx. ±4 Ac.)

Existing
Road

Alum.
Cap

S89°25'54"W - 1318.70' (Meas.)

E 1/4 Cor.
Sec. 4
Found Nail



ULTRA RESOURCES, INC.


LOCATION SURFACE USE AREA & ROAD RIGHT-OF-WAY ON FEE LANDS

(FOR THREE RIVERS #4-36T-820,
#4-34-820, & #4-38T-820)

LOCATED IN
SECTION 4, T8S, R20E, S.L.B.&M.
UINTAH COUNTY, UTAH

BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION



LEGEND:

P.I. = POINT OF INTERSECTION
P.O.P.L. = POINT ON PROPERTY LINE
▲ = SECTION CORNERS LOCATED.

RIGHT-OF-WAY LENGTHS

PROPERTY OWNER	FEET	ACRES	RODS
CLAY L. & ROSEANNA BATTY	103.77	0.071	6.29

NOTE: PROPERTY LINES SHOWN HAVE BEEN RE-ESTABLISHED FROM COUNTY RECORDS AND HAVE NOT BEEN SURVEYED BY UTAH ENGINEERING AND LAND SURVEY. UELS DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.

CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

REGISTERED LAND SURVEYOR
REGISTRATION NO. 16319
STATE OF UTAH



UELS, LLC
Corporate Office * 85 South 200 East
Vernal, UT 84078 * (435) 789-1017

SURVEYED BY: M.P. T.P.	SCALE: 1" = 300'	DRAWN BY: H.W.
DATE: 04-22-14	FILE: 56545	DATE: 05-01-14

ACCESS ROAD RIGHT-OF-WAY PLAT

RECEIVED: May 13, 2014

NW 1/4

NE 1/4

Sec. 4

BEGINNING OF PIPELINE STA. 0+00 BEARS S35°10'38"W 1381.25' FROM THE NORTHEAST CORNER OF THE NW 1/4 SE 1/4 OF SECTION 4, T8S, R20E, S.L.B.&M.

END OF PIPELINE STA. 0+86.63 BEARS S32°08'57"W 1332.62' FROM THE NORTHEAST CORNER OF THE NW 1/4 SE 1/4 OF THE NW 1/4 SW 1/4 OF SECTION 4, T8S, R20E, S.L.B.&M.

Existing Underground Pipeline

Proposed Three Rivers #4-23-820 Well Pad (3.280 Ac)

SURFACE USE AREA THREE RIVERS #4-36T-820, #4-34-820 & #4-38T-820

Existing Fence

Existing Power Line

Proposed Access Road for the Three Rivers #4-23-820 Well Pad

CLAY L & ROSEANNA BATTY

Proposed Pipeline for the Three Rivers #4-23-820 Well Pad

Existing Three Rivers #4-33-820 Well Pad

BEGINNING OF PROPOSED PIPELINE RIGHT-OF-WAY STA. 0+00 (At Edge of Surface Use Area)

END OF PROPOSED PIPELINE RIGHT-OF-WAY STA. 0+86.63 (At Proposed Pipeline for the Three Rivers #4-23-820 Well Pad)

Proposed Three Rivers #4-43-820 Well Pad (Approx. ±4 Ac.)

Existing Road

Alum. Cap

S89°25'54"W - 1318.70' (Meas.)

E 1/4 Cor. Sec. 4 Found Nail

Section Line

1/16 Section Line

SE 1/4

1/16 Section Line

S00°27'22"E - 2652.40' (Meas.)

S89°29'04"W - 5279.27' (Meas.)

Section Line

SW Cor. Sec. 4 2011 Alum. Cap 0.2' High


SE Cor. Sec. 4 Alum. Cap

ULTRA RESOURCES, INC.
PIPELINE RIGHT-OF-WAY
ON FEE LANDS

(FOR THREE RIVERS #4-36T-820, #4-34-820, & #4-38T-820)

LOCATED IN
SECTION 4, T8S, R20E, S.L.B.&M.
UINTAH COUNTY, UTAH

BASIS OF BEARINGS
BASIS OF BEARINGS IS A G.P.S. OBSERVATION



LEGEND:
P.I. = POINT OF INTERSECTION
P.O.P.L. = POINT ON PROPERTY LINE
▲ = SECTION CORNERS LOCATED.

RIGHT-OF-WAY LENGTHS

PROPERTY OWNER	FEET	ACRES	RODS
CLAY L. & ROSEANNA BATTY	86.63	0.060	5.25

NOTE: PROPERTY LINES SHOWN HAVE BEEN RE-ESTABLISHED FROM COUNTY RECORDS AND HAVE NOT BEEN SURVEYED BY UTAH ENGINEERING AND LAND SURVEY. UELS DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.

CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

REGISTERED LAND SURVEYOR
REGISTRATION NO. 16319
STATE OF UTAH



UELS, LLC
Corporate Office * 85 South 200 East
Vernal, UT 84078 * (435) 789-1017

SURVEYED BY: M.P. T.P.	SCALE: 1" = 300'	DRAWN BY: H.W.
DATE: 04-22-14	FILE: 5 6 5 4 7	DATE: 05-01-14

PIPELINE RIGHT-OF-WAY PLAT

RECEIVED: May 13, 2014

NW 1/4

NE 1/4

Sec. 4

BEGINNING OF POWER LINE STA. 0+00 BEARS S29°36'48"W 1351.66' FROM THE NORTHEAST CORNER OF THE NW 1/4 SE 1/4 OF SECTION 4, T8S, R20E, S.L.B.&M.

END OF POWER LINE STA. 1+27.79 BEARS S34°01'37"W 1421.90' FROM THE NORTHEAST CORNER OF THE NW 1/4 SE 1/4 OF THE NW 1/4 SW 1/4 OF SECTION 4, T8S, R20E, S.L.B.&M.

Existing Underground Pipeline

Proposed Three Rivers #4-23-820 Well Pad (3.280 Ac)

SURFACE USE AREA THREE RIVERS #4-36T-820, #4-34-820 & #4-38T-820

Existing Fence

Existing Power Line

BEGINNING OF PROPOSED POWER LINE RIGHT-OF-WAY STA. 0+00 (At Proposed Power Line for the Three Rivers #4-23-820 Well Pad)

END OF PROPOSED POWER LINE RIGHT-OF-WAY STA. 1+03.77 (At Edge of Surface Use Area)


Existing Three Rivers #4-33-820 Well Pad

Proposed Power Line for the Three Rivers #4-23-820 Well Pad

Proposed Access Road for the Three Rivers #4-23-820 Well Pad

CLAY L & ROSEANNA BATTY

LINE TABLE		
LINE	DIRECTION	LENGTH
L1	S88°30'38"W	127.79'
L2	S88°30'38"W	29.09'




ULTRA RESOURCES, INC.
POWER LINE RIGHT-OF-WAY
ON FEE LANDS

(FOR THREE RIVERS #4-36T-820, #4-34-820, & #4-38T-820)

LOCATED IN
SECTION 4, T8S, R20E, S.L.B.&M.
UINTAH COUNTY, UTAH

BASIS OF BEARINGS
BASIS OF BEARINGS IS A G.P.S. OBSERVATION



LEGEND:
P.I. = POINT OF INTERSECTION
P.O.P.L. = POINT ON PROPERTY LINE
▲ = SECTION CORNERS LOCATED.

RIGHT-OF-WAY LENGTHS

PROPERTY OWNER	FEET	ACRES	RODS
CLAY L. & ROSEANNA BATTY	127.79	0.088	7.74

NOTE: PROPERTY LINES SHOWN HAVE BEEN RE-ESTABLISHED FROM COUNTY RECORDS AND HAVE NOT BEEN SURVEYED BY UTAH ENGINEERING AND LAND SURVEY. UELS DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.

CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

REGISTERED LAND SURVEYOR
REGISTRATION NO. 151319
STATE OF UTAH

UELS, LLC
Corporate Office * 85 South 200 East
Vernal, UT 84078 * (435) 789-1017



SURVEYED BY: M.P. T.P.	SCALE: 1" = 300'	DRAWN BY: H.W.
DATE: 04-22-14	FILE: 56546	DATE: 05-01-14

POWER LINE RIGHT-OF-WAY PLAT

POWER LINE RIGHT-OF-WAY DESCRIPTION ON
CLAY L. & ROSEANNA BATTY LANDS

A 30' WIDE RIGHT-OF-WAY 15' ON EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE.

BEGINNING AT A POINT IN THE NW 1/4 SE 1/4 OF SECTION 4, T8S, R20E, S.L.B.&M., WHICH BEARS S29°36'48"W 1351.66' FROM THE NORTHEAST CORNER OF THE NW 1/4 SE 1/4 OF SAID SECTION 4, THENCE N88°30'38"W 127.79' TO A POINT IN THE NW 1/4 SE 1/4 OF SAID SECTION 4, WHICH BEARS S34°01'37"W 1421.90' FROM THE NORTHEAST CORNER OF THE NW 1/4 SE 1/4 OF SAID SECTION 4. THE SIDE LINES OF SAID DESCRIBED RIGHT-OF-WAY BEING SHORTENED OR ELONGATED TO MEET THE GRANTOR'S PROPERTY LINES. BASIS OF BEARINGS IS A G.P.S. OBSERVATION. CONTAINS 0.088 ACRES MORE OR LESS.

SW Cor. Sec. 4
2011 Alum. Cap
0.2' High

SE Cor. Sec. 4
Alum. Cap

S89°29'04"W - 5279.27' (Meas.)

Section Line

S00°27'22"E - 2652.40' (Meas.)

Section Line

1/16 Section Line

1/16 Section Line

SE 1/4

1/4 Section Line

1/4 Section Line

PROCEED IN A WESTERLY, THEN SOUTHWESTERLY DIRECTION FROM VERNAL, UTAH ALONG U.S. HIGHWAY 40 APPROXIMATELY 14.0 MILES TO THE JUNCTION OF THIS ROAD AND STATE HIGHWAY 88 TO THE SOUTH; EXIT LEFT AND PROCEED IN A SOUTHERLY, THEN SOUTHEASTERLY, THEN SOUTHERLY DIRECTION APPROXIMATELY 12.1 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE WEST; TURN RIGHT AND PROCEED IN A WESTERLY DIRECTION APPROXIMATELY 0.3 MILES TO THE BEGINNING OF THE PROPOSED ACCESS FOR THE THREE RIVERS #4-23-820 WELL PAD TO THE WEST; FOLLOW ROAD FLAGS IN A WESTERLY, THEN SOUTHERLY DIRECTION APPROXIMATELY 1,875' TO THE BEGINNING OF THE PROPOSED ACCESS ROAD TO THE WEST; FOLLOW ROAD FLAGS IN A WESTERLY DIRECTION APPROXIMATELY 133' TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM VERNAL, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 26.8 MILES.

ULTRA RESOURCES, INC.

THREE RIVERS #4-36T-820, #4-34-820 & #4-38T-820
SECTION 4, T8S, R20E, S.L.B&M.
NW 1/4 SE 1/4






UELS, LLC
Corporate Office * 85 South 200 East
Vernal, UT 84078 * (435) 789-1017

DRAWN BY: J.M.C.	DATE DRAWN: 05-06-14
	REV: 00-00-00
ROAD DESCRIPTION	

RECEIVED: May 13, 2014

Map Prepared: 5/15/2014
Map Produced by Diana Mason



Well Name	ULTRA RESOURCES INC Three Rivers 4-36T-820 43047544200000			
String	SURF	PROD		
Casing Size(")	8.625	5.500		
Setting Depth (TVD)	1000	6835		
Previous Shoe Setting Depth (TVD)	0	1000		
Max Mud Weight (ppg)	8.8	10.0		
BOPE Proposed (psi)	500	3000		
Casing Internal Yield (psi)	2950	5320		
Operators Max Anticipated Pressure (psi)	3500	9.8		

Calculations	SURF String	8.625	"
Max BHP (psi)	.052*Setting Depth*MW=	458	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	338	YES <input type="checkbox"/> diverter with rotating head
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	238	YES <input type="checkbox"/> OK
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	238	NO <input type="checkbox"/> OK
Required Casing/BOPE Test Pressure=		1000	psi
*Max Pressure Allowed @ Previous Casing Shoe=		0	psi *Assumes 1psi/ft frac gradient


Calculations	PROD String	5.500	"
Max BHP (psi)	.052*Setting Depth*MW=	3554	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	2734	YES <input type="checkbox"/> 3M BOP, dbl ram, annular with diverter and rotating
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	2050	YES <input type="checkbox"/> head
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	2270	NO <input type="checkbox"/> OK
Required Casing/BOPE Test Pressure=		3000	psi
*Max Pressure Allowed @ Previous Casing Shoe=		1000	psi *Assumes 1psi/ft frac gradient

Calculations	String		"
Max BHP (psi)	.052*Setting Depth*MW=		
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=		NO <input type="checkbox"/>
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=		NO <input type="checkbox"/>
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=		NO <input type="checkbox"/>
Required Casing/BOPE Test Pressure=			psi
*Max Pressure Allowed @ Previous Casing Shoe=			psi *Assumes 1psi/ft frac gradient

Calculations	String		"
Max BHP (psi)	.052*Setting Depth*MW=		
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=		NO <input type="checkbox"/>
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=		NO <input type="checkbox"/>
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=		NO <input type="checkbox"/>
Required Casing/BOPE Test Pressure=			psi
*Max Pressure Allowed @ Previous Casing Shoe=			psi *Assumes 1psi/ft frac gradient

43047544200000 Three Rivers 4-36T-820

Casing Schematic



CONFIDENTIAL

Stop cuts.

Well name:	43047544200000 Three Rivers 4-36T-820	
Operator:	ULTRA RESOURCES INC	
String type:	Surface	Project ID: 43-047-54420
Location:	UINTAH COUNTY	

Design parameters:**Collapse**

Mud weight: 8.800 ppg
Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Environment:

H2S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 88 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 100 ft

Burst:

Design factor 1.00

Cement top: 277 ft

Burst

Max anticipated surface pressure: 880 psi
Internal gradient: 0.120 psi/ft
Calculated BHP 1,000 psi

Annular backup: 1.50 ppg

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.70 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Non-directional string.

Tension is based on buoyed weight.
Neutral point: 868 ft

Re subsequent strings:

Next setting depth: 6,835 ft
Next mud weight: 10.000 ppg
Next setting BHP: 3,551 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 1,000 ft
Injection pressure: 1,000 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	1000	8.625	24.00	J-55	ST&C	1000	1000	7.972	5148
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	457	1370	2.997	922	2950	3.20	20.8	244	11.71 J

Prepared Helen Sadik-Macdonald
by: Div of Oil, Gas & Mining

Phone: 801 538-5357
FAX: 801-359-3940

Date: July 10, 2014
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 1000 ft, a mud weight of 8.8 ppg. The casing is considered to be evacuated for collapse purposes.
Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Well name:	43047544200000 Three Rivers 4-36T-820	
Operator:	ULTRA RESOURCES INC	
String type:	Production	Project ID: 43-047-54420
Location:	UINTAH COUNTY	

Design parameters:**Collapse**

Mud weight: 10.000 ppg
Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 170 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 1,000 ft

Cement top: 1,487 ft

Burst

Max anticipated surface pressure: 2,047 psi
Internal gradient: 0.220 psi/ft
Calculated BHP 3,550 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.60 (B)

Directional Info - Build & Drop

Kick-off point 1200 ft
Departure at shoe: 644 ft
Maximum dogleg: 2 °/100ft
Inclination at shoe: 0 °

Tension is based on buoyed weight.

Neutral point: 5,865 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	6902	5.5	17.00	J-55	LT&C	6835	6902	4.767	26739
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	3550	4910	1.383	3550	5320	1.50	98.6	247	2.51 J

Prepared Helen Sadik-Macdonald
by: Div of Oil, Gas & Mining

Phone: 801 538-5357
FAX: 801-359-3940

Date: July 10, 2014
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 6835 ft, a mud weight of 10 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

Engineering responsibility for use of this design will be that of the purchaser.

ON-SITE PREDRILL EVALUATION

Utah Division of Oil, Gas and Mining

Operator ULTRA RESOURCES INC
Well Name Three Rivers 4-36T-820
API Number 43047544200000 **APD No** 9698 **Field/Unit** THREE RIVERS
Location: 1/4,1/4 NWSE Sec 4 T w 8.0S Rng 20.0E 1529 FSL 2373 FEL
GPS Coord (UTM) 613076 4445093 **Surface Owner** UPL Three Rivers Holdings, LLC

Participants

John Busch (ULTRA), Jim Burns (permit contractor), Martin Pierce (surveyor), Richard Powell (UDOGM)

Regional/Local Setting & Topography

This proposed well site is in the farmland surrounding Pelican Lake. Pelican Lake sits at the bottom of a sort of large shallow bowl. Immediately around the lake lies mostly irrigated crop land. Most of the farm fields are watered with large circular pivot irrigation systems and the wells scattered throughout these farm fields are generally placed in the corners of these fields out of reach of the irrigation sprinklers on land that is usually abandoned from farming operations. Such is the case with this proposed 3 well site approximately 2.5 miles south of Pelican Lake and .5 mile west of Highway 88.

Surface Use Plan

Current Surface Use
Agricultural

New Road Miles	Well Pad Width Length	Src Const Material	Surface Formation
0.02	240 360	Offsite	UNTA

Ancillary Facilities N

Waste Management Plan Adequate? Y

Environmental Parameters

Affected Floodplains and/or Wetlands N

Flora / Fauna
kocia weed, corn stocks

Soil Type and Characteristics
Sandy loam

Erosion Issues N

Sedimentation Issues N

Site Stability Issues N

Drainage Diversion Required? N

Berm Required? Y

Permeable soil

Erosion Sedimentation Control Required? N**Paleo Survey Run? N Paleo Potential Observed? N Cultural Survey Run? N Cultural Resources? N****Reserve Pit****Site-Specific Factors****Site Ranking**

Distance to Groundwater (feet)	25 to 75	15
Distance to Surface Water (feet)	>1000	0
Dist. Nearest Municipal Well (ft)	>5280	0
Distance to Other Wells (feet)		20
Native Soil Type	High permeability	20
Fluid Type	Fresh Water	5
Drill Cuttings	Normal Rock	0
Annual Precipitation (inches)		0
Affected Populations		
Presence Nearby Utility Conduits	Not Present	0
Final Score		60 1 Sensitivity Level

Characteristics / Requirements

The reserve pit as proposed is 150ft x 60ft x 10ft deep and is to be placed in a cut stable location. This pit will require a 20 mil liner and felt subliner. The soil is very permeable and the pit will be used for three wells.

Closed Loop Mud Required? N Liner Required? Y Liner Thickness 20 Pit Underlayment Required? Y**Other Observations / Comments**

Richard Powell
Evaluator

7/1/2014
Date / Time

Application for Permit to Drill

Statement of Basis

Utah Division of Oil, Gas and Mining

APD No	API WellNo	Status	Well Type	Surf Owner	CBM
9698	43047544200000	LOCKED	OW	P	No
Operator	ULTRA RESOURCES INC		Surface Owner-APD	UPL Three Rivers Holdings, LLC	
Well Name	Three Rivers 4-36T-820		Unit		
Field	THREE RIVERS		Type of Work	DRILL	
Location	NWSE 4 8S 20E S 1529 FSL 2373 FEL GPS Coord (UTM) 613071E 4445094N				

Geologic Statement of Basis

Ultra proposes to set 1,000 feet of surface pipe, cemented to surface. The depth to the base of the moderately saline water at this location is estimated to be at approximately 1,000 feet. A search of Division of Water Rights records shows 6 water wells within a 10,000 foot radius of the center of Section 4. The wells range in depth from 70 to 150 feet with no depth being listed for 1 well. Listed uses are irrigation, domestic, stock watering and oil exploration. The surface formation at this site is the Uinta Formation and alluvium derived from the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be a significant source of useable ground water. The proposed casing and cement should adequately protect ground water in this area.

Brad Hill
APD Evaluator

7/8/2014
Date / Time

Surface Statement of Basis

This proposed three well pad is on fee surface with fee minerals. The surface owner is UPL Three Rivers Holdings which is also the operator of the proposed wells. John Busch acted as representative of both Ultra Resources and UPL Three Rivers Holdings at this onsite inspection. This proposed pad sits in a corner of a large irrigated farm field about 2.5 miles south of Pelican Lake. As placed the well site does not interfere with the irrigation system or current farming operations. The site is quite flat with a gentle east slope. The soil here is quite permeable and a berm will be required around the location. A reserve pit will be built and will require a minimum 20 mil liner and felt subliner. According to Mr. John Busch, Ultra uses a 20 mil liner for as general practice. This appears to be a good site for placement of this well.

Richard Powell
Onsite Evaluator

7/1/2014
Date / Time

Conditions of Approval / Application for Permit to Drill

Category	Condition
Pits	A synthetic liner with a minimum thickness of 20 mils with a felt subliner shall be properly installed and maintained in the reserve pit.
Surface	The well site shall be bermed to prevent fluids from entering or leaving the pad.
Surface	Measures (BMP's) shall be taken to protect steep slopes and topsoil pile from erosion, sedimentation and stability issues.
Surface	Drainages adjacent to the proposed pad shall be diverted around the location.

API Well Number: 43047544200000

Surface

The reserve pit shall be fenced upon completion of drilling operations.

CONFIDENTIAL

RECEIVED: July 17, 2014

WORKSHEET APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 5/13/2014

API NO. ASSIGNED: 43047544200000

WELL NAME: Three Rivers 4-36T-820

OPERATOR: ULTRA RESOURCES INC (N4045)

PHONE NUMBER: 303 645-9872

CONTACT: Katherine Skinner

PROPOSED LOCATION: NWSE 04 080S 200E

Permit Tech Review: ☒

SURFACE: 1529 FSL 2373 FEL

Engineering Review: ☒

BOTTOM: 1780 FSL 1780 FEL

Geology Review: ☒

COUNTY: UINTAH

LATITUDE: 40.14858

LONGITUDE: -109.67250

UTM SURF EASTINGS: 613071.00

NORTHINGS: 4445094.00

FIELD NAME: THREE RIVERS

LEASE TYPE: 4 - Fee

LEASE NUMBER: FEE

PROPOSED PRODUCING FORMATION(S): GREEN RIVER - LOWER

SURFACE OWNER: 4 - Fee

COALBED METHANE: NO

RECEIVED AND/OR REVIEWED:

- ☒ PLAT
- ☒ Bond: STATE - 022046398
- ☐ Potash
- ☐ Oil Shale 190-5
- ☐ Oil Shale 190-3
- ☐ Oil Shale 190-13
- ☒ Water Permit: 49-2262
- ☐ RDCC Review:
- ☒ Fee Surface Agreement
- ☐ Intent to Commingle

Commingle Approved

LOCATION AND SITING:

- ☐ R649-2-3.
- Unit:
- ☐ R649-3-2. General
- ☒ R649-3-3. Exception
- ☒ Drilling Unit
- Board Cause No: Cause 270-02
- Effective Date: 11/9/2013
- Siting: 2 Wells Per 40 Acres
- ☒ R649-3-11. Directional Drill

Comments: Presite Completed

Stipulations: 1 - Exception Location - bhill
5 - Statement of Basis - bhill
12 - Cement Volume (3) - hmacdonald
15 - Directional - dmason
25 - Surface Casing - ddoucet

RECEIVED: July 17, 2014



GARY R. HERBERT
Governor

SPENCER J. COX
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

Permit To Drill

Well Name: Three Rivers 4-36T-820

API Well Number: 43047544200000

Lease Number: FEE

Surface Owner: FEE (PRIVATE)

Approval Date: 7/17/2014

Issued to:

ULTRA RESOURCES INC, 304 Inverness Way South #295, Englewood, CO 80112

Authority:

Pursuant to Utah Code Ann. 40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 270-02. The expected producing formation or pool is the GREEN RIVER - LOWER Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

Exception Location:

Appropriate information has been submitted to DOGM and administrative approval of the requested exception location is hereby granted.

General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

Conditions of Approval:

In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis (copy attached).

Cement volume for the 5 1/2" production string shall be determined from actual hole diameter in order to place lead cement from the pipe setting depth back to 500' MD and tail cement to 4000' as indicated in the submitted drilling plan.

Surface casing shall be cemented to the surface. If water flows are encountered in the drilling of the surface casing or production casing the 11.5 ppg and 11.0 ppg cements will not be allowed. A cement of adequate density and strength will need to be pumped to ensure proper isolation.

Additional Approvals:

The operator is required to obtain approval from the Division of Oil, Gas and mining before performing any of the following actions during the drilling of this well:

- Any changes to the approved drilling plan - contact Dustin Doucet
- Significant plug back of the well - contact Dustin Doucet
- Plug and abandonment of the well - contact Dustin Doucet

Notification Requirements:

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well - contact Carol Daniels
OR
submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website
at <http://oilgas.ogm.utah.gov>
- 24 hours prior to testing blowout prevention equipment - contact Dan Jarvis
- 24 hours prior to cementing or testing casing - contact Dan Jarvis
- Within 24 hours of making any emergency changes to the approved drilling program
- contact Dustin Doucet
- 24 hours prior to commencing operations to plug and abandon the well - contact Dan Jarvis

Contact Information:

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voicemail message if the person is not available to take the call):

- Carol Daniels 801-538-5284 - office
- Dustin Doucet 801-538-5281 - office
801-733-0983 - after office hours
- Dan Jarvis 801-538-5338 - office
801-231-8956 - after office hours

Reporting Requirements:

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) - due within 5 days of spudding the well
- Monthly Status Report (Form 9) - due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) - due prior to implementation
- Written Notice of Emergency Changes (Form 9) - due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) - due prior to implementation
- Report of Water Encountered (Form 7) - due within 30 days after completion
- Well Completion Report (Form 8) - due within 30 days after completion or

plugging

Approved By:

A handwritten signature in black ink, appearing to read "J. Rogers", written over a horizontal line.

For John Rogers
Associate Director, Oil & Gas

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: FEE
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: ULTRA RESOURCES INC		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: 304 Inverness Way South #295, Englewood, CO, 80112		8. WELL NAME and NUMBER: Three Rivers 4-36T-820
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1529 FSL 2373 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWSE Section: 04 Township: 08.0S Range: 20.0E Meridian: S		9. API NUMBER: 43047544200000
PHONE NUMBER: 303 645-9810 Ext		9. FIELD and POOL or WILDCAT: THREE RIVERS
COUNTY: UINTAH		STATE: UTAH

11.

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"><input type="checkbox"/> ACIDIZE</div> <div style="width: 33%;"><input type="checkbox"/> ALTER CASING</div> <div style="width: 33%;"><input type="checkbox"/> CASING REPAIR</div> <div style="width: 33%;"><input type="checkbox"/> CHANGE TO PREVIOUS PLANS</div> <div style="width: 33%;"><input type="checkbox"/> CHANGE TUBING</div> <div style="width: 33%;"><input type="checkbox"/> CHANGE WELL NAME</div> <div style="width: 33%;"><input type="checkbox"/> CHANGE WELL STATUS</div> <div style="width: 33%;"><input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS</div> <div style="width: 33%;"><input type="checkbox"/> CONVERT WELL TYPE</div> <div style="width: 33%;"><input type="checkbox"/> DEEPEN</div> <div style="width: 33%;"><input type="checkbox"/> FRACTURE TREAT</div> <div style="width: 33%;"><input type="checkbox"/> NEW CONSTRUCTION</div> <div style="width: 33%;"><input type="checkbox"/> OPERATOR CHANGE</div> <div style="width: 33%;"><input type="checkbox"/> PLUG AND ABANDON</div> <div style="width: 33%;"><input type="checkbox"/> PLUG BACK</div> <div style="width: 33%;"><input type="checkbox"/> PRODUCTION START OR RESUME</div> <div style="width: 33%;"><input type="checkbox"/> RECLAMATION OF WELL SITE</div> <div style="width: 33%;"><input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION</div> <div style="width: 33%;"><input type="checkbox"/> REPERFORATE CURRENT FORMATION</div> <div style="width: 33%;"><input type="checkbox"/> SIDETRACK TO REPAIR WELL</div> <div style="width: 33%;"><input type="checkbox"/> TEMPORARY ABANDON</div> <div style="width: 33%;"><input type="checkbox"/> TUBING REPAIR</div> <div style="width: 33%;"><input type="checkbox"/> VENT OR FLARE</div> <div style="width: 33%;"><input type="checkbox"/> WATER DISPOSAL</div> <div style="width: 33%;"><input type="checkbox"/> WATER SHUTOFF</div> <div style="width: 33%;"><input type="checkbox"/> SI TA STATUS EXTENSION</div> <div style="width: 33%;"><input type="checkbox"/> WILDCAT WELL DETERMINATION</div> <div style="width: 33%;"><input type="checkbox"/> OTHER</div> </div>
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	
<input checked="" type="checkbox"/> SPUD REPORT Date of Spud: 8/19/2014	
<input type="checkbox"/> DRILLING REPORT Report Date:	
OTHER: <input style="width: 100px;" type="text"/>	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Ultra Resources will be moving ProPetro to spud the Three Rivers
 4-36T-820 (API #43-047-54420) on 8/19/2014.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY
 August 19, 2014

NAME (PLEASE PRINT) Jenna Anderson	PHONE NUMBER 303 645-9804	TITLE Permitting Assistant
SIGNATURE N/A	DATE 8/19/2014	

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: FEE
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: ULTRA RESOURCES INC		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: 304 Inverness Way South #295, Englewood, CO, 80112		8. WELL NAME and NUMBER: Three Rivers 4-36T-820
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1529 FSL 2373 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWSE Section: 04 Township: 08.0S Range: 20.0E Meridian: S		9. API NUMBER: 43047544200000
PHONE NUMBER: 303 645-9810 Ext		9. FIELD and POOL or WILDCAT: THREE RIVERS
COUNTY: UINTAH		STATE: UTAH

11.

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 8/27/2014 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE <input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION </div> </div> <div style="margin-top: 10px;"> OTHER: </div>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.


Ultra requests to change the BHL from 1780' FSL & 1780' FEL to 1344' FSL & 1980' FEL per attached plat dated 8-6-14. Ultra's Directional Drilling Letter is also attached.

Approved by the
August 28, 2014
Oil, Gas and Mining


Date: _____
By: *D. K. Duff*

NAME (PLEASE PRINT) Jenna Anderson	PHONE NUMBER 303 645-9804	TITLE Permitting Assistant
SIGNATURE N/A	DATE 8/13/2014	

RECEIVED: Aug. 13, 2014

T8S, R20E, S.L.B.&M.**LEGEND:**

- 90° SYMBOL
- PROPOSED WELLHEAD.
- TARGET BOTTOM HOLE.
- SECTION CORNERS LOCATED.
- SECTION CORNERS RE-ESTABLISHED. (Not Set on Ground.)



NAD 83 (TARGET BOTTOM HOLE)	NAD 83 (SURFACE LOCATION)
LATITUDE = 40°08'53.09" (40.148081)	LATITUDE = 40°08'54.88" (40.148578)
LONGITUDE = 109°40'16.32" (109.671200)	LONGITUDE = 109°40'21.40" (109.672611)

BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION

BASIS OF ELEVATION

BENCH MARK (38EAM) LOCATED IN THE SW 1/4 OF SECTION 9, T7S, R20E, S.L.B.&M. TAKEN FROM THE PELICAN LAKE, QUADRANGLE, UTAH, UTAH COUNTY, 7.5 MINUTE QUAD (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 4942 FEET.



UELS, LLC
Corporate Office * 85 South 200 East
Vernal, UT 84078 * (435) 789-1017

**ULTRA RESOURCES, INC.**

THREE RIVERS #4-36T-820
NW 1/4 SE 1/4, SECTION 4, T8S, R20E, S.L.B.&M.
UINTAH COUNTY, UTAH

SURVEYED BY: M.P. T.P.	SCALE: 1"=1000'	REVISED BY: H.W.
DATE: 04-22-14		DATE: 08-05-14

WELL LOCATION PLAT

RECEIVED: Aug. 13, 2014



Ultra Resources, Inc.

August 13, 2014

Mr. Dustin Doucet
Utah Division of Oil, Gas & Mining
1594 West North Temple
Salt Lake City, Utah 84116

RE: Directional Drilling – Docket No. 2014-026 / Cause No. 270-04
Three Rivers 4-36T-820
Surface Location: 1529' FSL & 2373' FEL, NWSE, Sec. 4, T8S, R20E
Target Location: 1344' FSL & 1980' FEL, NWSE, Sec. 4, T8S, R20E
SLB&M, Uintah County, Utah

Mr. Doucet:

Ultra Resources, Inc. ("Ultra") respectfully submits the below specifics concerning the proposed directional drilling of the subject well:

- The well is identified in Docket No. 2014-026 / Cause No. 270-04 ("270-04") as a "lease line" well.
- The well is located on or as close as reasonably feasible to the respective common lease line, and no closer than 460 feet to another well producing from the same formation or to a boundary with lands not subject to the 270-02 Order.
- Ultra is the sole owner of 100% of the leasehold rights with respect to all tracts within 460' around the full wellbore path of the proposed directional well.
- There are no unleased mineral interests with respect to all tracts within 460' around the full wellbore path of the proposed directional well.
- The anticipated points of intersection with the objective (spaced) formation and the anticipated productive interval are within the established setbacks.
- The bottom hole location is within the established setbacks.
- The directional drilling of the well is proposed to limit surface disturbance within the project and affected surface owners.

Therefore, based on the above stated information, Ultra requests the Sundry to change the bottom hole location be granted pursuant to the 270-04 Order.

Mr. Dustin Doucet

August 13, 2014

Page 2

Thank you in advance for your consideration. Please feel free to contact me at 303-645-9810 if you have any questions or comments.

Sincerely,

Debbie Ghani

Sr. Permitting Specialist

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: FEE
		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
		7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL Oil Well	8. WELL NAME and NUMBER: Three Rivers 4-36T-820	
2. NAME OF OPERATOR: ULTRA RESOURCES INC	9. API NUMBER: 43047544200000	
3. ADDRESS OF OPERATOR: 304 Inverness Way South #295, Englewood, CO, 80112	PHONE NUMBER: 303 645-9809 Ext	9. FIELD and POOL or WILDCAT: THREE RIVERS
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1529 FSL 2373 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWSE Section: 04 Township: 08.0S Range: 20.0E Meridian: S	COUNTY: UINTAH	
		STATE: UTAH

11.

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA


TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 9/17/2014 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> ACIDIZE <input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input type="text"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Ultra requests to change the SHL from 1529' FSL & 2373' FEL to 1530' FSL & 2373' FEL per attached As-Drilled plat dated 8-27-14.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY
 September 17, 2014

NAME (PLEASE PRINT) Jenna Anderson	PHONE NUMBER 303 645-9804	TITLE Permitting Assistant
SIGNATURE N/A		DATE 9/3/2014

T8S, R20E, S.L.B.&M.

NAD 83 (TARGET BOTTOM HOLE)	NAD 83 (AS-DRILLED SURFACE LOCATION)
LATITUDE = 40°08'53.09" (40.148081)	LATITUDE = 40°08'54.89" (40.148581)
LONGITUDE = 109°40'16.32" (109.671200)	LONGITUDE = 109°40'21.40" (109.672611)

BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION

BASIS OF ELEVATION

BENCH MARK (38EAM) LOCATED IN THE SW 1/4 OF SECTION 9, T7S, R20E, S.L.B.&M. TAKEN FROM THE PELICAN LAKE, QUADRANGLE, UTAH, UTAH COUNTY, 7.5 MINUTE QUAD (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 4942 FEET.



UELS, LLC
Corporate Office * 85 South 200 East
Vernal, UT 84078 * (435) 789-1017

**ULTRA RESOURCES, INC.**

(AS-DRILLED) THREE RIVERS #4-36T-820
NW 1/4 SE 1/4, SECTION 4, T8S, R20E, S.L.B.&M.
UINTAH COUNTY, UTAH

SURVEYED BY: M.P. D.L.	SCALE: 1"=1000'	DRAWN BY: H.W.
DATE: 08-22-14		DATE: 08-26-14

WELL LOCATION PLAT**CERTIFICATE**


THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM RECORDED NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION, AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



Ensign 122
 71-564-120

Company: Ultra Res
 Date: 9/11-9/12/2014

43 047 54420
 4 85 20E



RECEIVED

SEP 15 2014

DIV. OF OIL, GAS & MINING

DATE: 9-12-2014
WELL: TR V-36T-820

ACCUMULATOR FUNCTION TEST

TO CHECK THE USABLE FLUID STORED IN THE NITROGEN BOTTLES ON THE
ACCUMULATOR (OO #2 IIA.2.c.i. or ii or iii)

1. Make sure all runs and annular are open and if applicable HCR is closed
2. Ensure accumulator is pumped up to working pressure! (Shut off all pumps)
3. Open HCR valve. (if applicable)
4. Close annular.
5. Close all pipe runs.
6. Open one set of pipe runs to simulate closing the blind runs.
7. If you have a 3 Run stuck open the annular to achieve the 50 +/- % safety factor for 5M and greater systems.
8. Accumulator pressure should be 200 psi over precharge pressure
(Accumulator working pressure (1,500 psi = 750 desired psi)
(2,000 and 3,000 psi = 1,000 desired psi)).

9. RECORD THE REMAINING PRESSURE 1,450 PSI

If annular is closed, open it at this time and close HCR.

TO CHECK THE CAPACITY OF THE ACCUMULATOR PUMPS (OO #2 IIA.2.E.)

Shut the accumulator bottles or spherical (Isolate them from the pumps & manifold) open the bleed off valve to the tank (Manifold psi should go to zero psi) close bleed valve.

1. Open the HCR valve. (if applicable)
2. Close annular.
3. With pumps only, time how long it takes to re-gain manifold pressure to 200 psi over desired precharge pressure! (Accumulator working pressure (1,500 psi = 750 psi desired psi) (2,000 and 3,000 psi = 1,000 desired psi)).

4. RECORD ELAPSED TIME 1 min 9 sec PSI (2 minutes or less)

TO CHECK THE PRECHARGE ON THE BOTTLES OR SPHERICAL (OO #2 IIA.2.d.)

1. Open bottles back up to the manifold (pressure should be above the desired precharge pressure (1,500 psi = 750 psi desired psi) (2,000 and 3,000 psi = 1,000 desired psi) may need to use pumps to pressure back up.
2. With power to pumps shut off open bleed line to tank.
3. Watch and record where the pressure drops (Accumulator psi).

4. RECORD THE PRESSURE DROP 900 PSI

If pressure drops below MINIMUM precharge (Accumulator working pressure (1,500 psi = 700 psi minimum) (2,000 and 3,000 psi = 900 psi minimum)) each bottle shall be independently checked with a gauge.


RECEIVED

SEP 15 2014

DIV. OF OIL, GAS & MINING

DATE: 9/17/14		COMPANY: W. H. Res		WELL NAME: TR 4-36T-820
Time	Test No.		Result	
8:47 AM (PM)	1	Mud Saver	Pass (Fail)	
10:35 AM (PM)	2	Angular	Pass (Fail)	
11:02 AM (PM)	3	Pipe Ram, Inside Manual Kill & Choke Valves, TIV	Pass (Fail)	
11:32 AM (PM)	4	HCP, Check Valve, Dart	Pass (Fail)	
12:00 AM (PM)	5	Inside Manifold Valves, Riser	Pass (Fail)	
1:57 AM (PM)	6	Outside Manifold Valves	Pass (Fail)	
1:23 AM (PM)	7	Super Choke	Pass (Fail)	
1:46 AM (PM)	8	Blind Rams, Downstream Manifold Valves	Pass (Fail)	
2:25 AM (PM)	9	Casing	Pass (Fail)	
AM (PM)	10		Pass (Fail)	
AM (PM)	11		Pass (Fail)	
AM (PM)	12		Pass (Fail)	
AM (PM)	13		Pass (Fail)	
AM (PM)	14		Pass (Fail)	
AM (PM)	Retest		Pass (Fail)	
AM (PM)	Retest		Pass (Fail)	
AM (PM)	Retest		Pass (Fail)	
AM (PM)	Retest		Pass (Fail)	
AM (PM)	Retest		Pass (Fail)	
AM (PM)	Retest		Pass (Fail)	
AM (PM)	Retest		Pass (Fail)	
AM (PM)	Retest		Pass (Fail)	
Acc. Tank Size (Inches)		W	D	U ÷ 231 = gal

Rock Springs, WY (307) 382-3339
 BOP TESTING, CASING TESTING, LEAK OFF TESTING, &
 INTEGRITY TESTING
 NIPPLE UP CREWS, NITROGEN CHARGING SERVICE




RECEIVED

SEP 15 2014

DIV. OF OIL, GAS & MINING

Chart #2 on Reverse



682

WALKER INSPECTION,LLC.
REBEL TESTING • EAGER BEAVER TESTERS
 WYOMING • COLORADO • NORTH DAKOTA

Daily JSA/Observation Report

OPERATOR: Ultra Res
 LOCATION: TR 4-36T-830
 EMPLOYEE NAME: Dustin Redmond

DATE: 9-12-2014
 CONTRACTOR: Ensign 122

- ☒ **Factor:** High Pressure Testing
☒ **Factor:** Working Below Platform
☒ **Factor:** Requires PPE
☒ **Factor:** Overhead Work is Occurring
☐ **Fill in if:** Confined Spaces are Involved
☐ **Fill in if:** Set up of Containment
☒ **Factor:** Using Rig Hoist to Lift Tools
☐ **Fill in if:** Other: _____

COMMENTS: Safety excelsed.

SIGNATURE: [Signature]

DATE: 9-12-2014

WALKER INSPECTION, LLC. AND AFFILIATES

ATTENDANCE:

<u>[Signature]</u>		
<u>[Signature]</u>		
<u>[Signature]</u>		
<u>[Signature]</u>		
<u>[Signature]</u>		
<u>[Signature]</u>		
<u>[Signature]</u>		
<u>[Signature]</u>		

Observation Report

EMPLOYEE REPORTING: Dustin Redmond SIGNATURE: [Signature]

Was job set up and performed correctly and to best of companies ability? ☒ Y ☐ N

Was all safety equipment used correctly by all involved? ☒ Y ☐ N

Any incidents or near misses to report about WI? Y ☒ N

Any incidents or near misses to report in general? Y ☒ N

Any spills or environmental issues to report? Y ☒ N

Basic Comments: _____

RECEIVED

SEP 15 2014

DIV. OF OIL, GAS & MINING

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: FEE
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: ULTRA RESOURCES INC		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: 304 Inverness Way South #295, Englewood, CO, 80112		8. WELL NAME and NUMBER: Three Rivers 4-36T-820
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1529 FSL 2373 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWSE Section: 04 Township: 08.0S Range: 20.0E Meridian: S		9. API NUMBER: 43047544200000
PHONE NUMBER: 303 645-9809 Ext		9. FIELD and POOL or WILDCAT: THREE RIVERS
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input checked="" type="checkbox"/> DRILLING REPORT Report Date: 10/10/2014	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100%;" type="text"/> </div> </div>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Monthly status report of drilling and completion attached.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY October 14, 2014		
NAME (PLEASE PRINT) Jenna Anderson	PHONE NUMBER 303 645-9804	TITLE Permitting Assistant
SIGNATURE N/A	DATE 10/10/2014	

ULTRA RESOURCES, INC.
DAILY DRILLING REPORT DATE: 08/24/2014

WELL NAME

THREE RIVERS 4-36T-820

AFE#

140972

SPUD DATE

09/12/2014

WELL SITE CONSULTANT

JARED MEJORADO

PHONE#

713-948-9196

CONTRACTOR

Other

TD AT REPORT

1,052'

FOOTAGE

933'

PRATE

CUM. DRLG. HRS

DRLG DAYS SINCE SPUD

0

ANTICIPATED TD

6,769'

PRESENT OPS

Drilling at 1,052'

GEOLOGIC SECT.

DAILY MUD LOSS

SURF:

DH:

CUM. MUD LOSS

SURF:

DH:

MUD COMPANY:

MUD ENGINEER:

LAST BOP TEST

NEXT CASING SIZE

8 5/8

NEXT CASING DEPTH

1,032

SSE

SSED

AFE Days vs Depth:

AFE Cost Vs Depth:

DWOP Days vs Depth:

LL/BP Received Today:

FUEL AND WATER USAGE					
Fluid	Used	Received	Transferred	On Hand	Cum.Used
Fuel	1,500.0	1,500.0		0.0	1,500.0
Gas					
Fresh Well Water					
Nano Water					
Frac Water					
Reserve Pit Water					
Boiler Hours					
Air Heater Hours					
Urea				0.0	
Urea Sys 1 Hrs					
Urea Sys 2 Hrs					
Urea Sys 3 Hrs					

RECENT CASINGS RUN:	Date Set	Size	Grade	Weight	Depth	FIT Depth	FIT ppg
Surface	08/24/2014	8 5/8	J-55	24	1,032		
Conductor	08/19/2014	16	ARJ-55	45	119		

RECENT BITS:									
BIT	SIZE	MANUF	TYPE	SERIAL NO.	JETS	TFA	DEPTH IN	DEPTH OUT	I-O-D-L-B-G-O-R

BIT OPERATIONS:											
BIT	WOB	RPM	GPM	PRESS	HHP	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP

RECENT MUD MOTORS:											
#	SIZE	MANUF	TYPE	SERIAL NO.	LOBES	DEPTH IN	DEPTH OUT	DATE IN	DATE OUT		

MUD MOTOR OPERATIONS:											
#	WOB	REV/GAL	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP			

SURVEYS											
Date	TMD	Incl	Azimuth	TVD	VS	NS	EW	DLS	Tool Type		

DAILY COSTS	DAILY	CUM	AFE		DAILY	CUM	AFE
8100..100: Permits & Fees			4,500	8100..105: Insurance			2,000
8100..110: Staking & Surveying			1,500	8100..120: Surface Damages & R			
8100..200: Location Roads			50,000	8100..210: Reclamation			
8100..220: Secondary Reclamati				8100..230: Pit Solidification			5,000
8100..300: Water Well				8100..310: Water/Water Disposa			7,500
8100..320: Mud & Chemicals			45,000	8100..325: Oil Base Mud Diesel			
8100..400: Drilling Rig			127,000	8100..402: Drilling Rig Cleani			
8100..405: Rig Fuel			40,000	8100..410: Mob/Demob			17,000
8100..420: Bits & Reamers			15,500	8100..500: Roustabout Services			7,000
8100..510: Testing/Inspection/			5,000	8100..520: Trucking & Hauling			10,000
8100..530: Equipment Rental			25,000	8100..531: Down Hole Motor Ren			1,500
8100..532: Solids Control Equi			7,000	8100..535: Directional Drillin			76,000
8100..540: Fishing				8100..600: Surface Casing/Inte			20,000
8100..605: Cementing Work			25,000	8100..610: P & A			
8100..700: Logging - Openhole			15,000	8100..705: Logging - Mud			
8100..800: Supervision/Consult			25,000	8100..810: Engineering/Evaluat			
8100..900: Contingencies				8100..950: Administrative O/H			
8100..999: Non Operated IDC				8200..510: Testing/Inspection/			2,000
8200..520: Trucking & Hauling			7,000	8200..530: Equipment Rental			37,500
8200..605: Cementing Work			25,000	8210..600: Production Casing			94,000
8210..620: Wellhead/Casing Hea			20,000	Total Cost			717,000

ULTRA RESOURCES, INC.
DAILY DRILLING REPORT DATE: 08/25/2014

WELL NAME	THREE RIVERS 4-36T-820		AFE#	140972	SPUD DATE	09/12/2014	
WELL SITE CONSULTANT	JARED MEJORADO		PHONE#	713-948-9196	CONTRACTOR	Other	
TD AT REPORT	(no data)	FOOTAGE	PRATE	CUM. DRLG. HRS	9.5	DRLG DAYS SINCE SPUD	0
ANTICIPATED TD	6.769'	PRESENT OPS	(nothing recorded)		GEOLOGIC SECT.		
DAILY MUD LOSS	SURF:	DH:	CUM. MUD LOSS		SURF:	DH:	
MUD COMPANY:			MUD ENGINEER:				
LAST BOP TEST		NEXT CASING SIZE	NEXT CASING DEPTH		SSE	SSED	

TIME BREAKDOWN	
COND MUD & CIRCULATE	1.50
TRIPPING	1.00
DRILLING	9.50
RIG UP / TEAR DOWN	2.50

DETAILS			
Start	End	Hrs	
15:30	18:00	02:30	MOVE RIG ON LOCATION & RIG UP
18:00	03:30	09:30	DRILL FROM 119' TO 1052'
03:30	04:00	00:30	CIRCULATE HOLE CLEAN
04:00	05:00	01:00	WIPER TRIP
05:00	06:00	01:00	CIRCULATE HOLE CLEAN

AFE Days vs Depth:		AFE Cost Vs Depth:	
DWOP Days vs Depth:		# LL/BP Received Today:	

CASING EQUIPMENT
RUN 23JTS 8 5/8 24# J-55 CSG W/ SHOE + SHOE JT & FLOAT COLLAR THREAD LOCKED - CENTRALIZE FIRST FOUR JOINTS & THEN EVERY FOURTH TO SURFACE

CEMENT JOB SUMMARY
PRESSURE TEST LINES TO 3000PSI - PUMP 20BBLS FRESH WATER - PUMP 20BBLS WATER+GEL - PUMP 138.2BBLS 15.8 CEMENT 1.15 YIELD (675 SXS)5 GAL/SX MIX WATER - DISPLACE 61BBLS FRESH WATER - LAND PLUG W/ 420PSI+500 OVER FOR 1MIN - FLOATS HELD - BLEED BACK 1BBL TO TRUCK - GOOD RETURNS THROUGHOUT JOB - 30BBLS CEMENT TO SURFACE.

RECENT CASINGS RUN:		Date Set	Size	Grade	Weight	Depth	FIT Depth	FIT ppg	
Surface		08/24/2014	8 5/8	J-55	24	1,032			
Conductor		08/19/2014	16	ARJ-55	45	119			

RECENT BITS:										
BIT	SIZE	MANUF	TYPE	SERIAL NO.	JETS	TFA	DEPTH IN	DEPTH OUT	I-O-D-L-B-G-O-R	

BIT OPERATIONS:											
BIT	WOB	RPM	GPM	PRESS	HHP	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP

RECENT MUD MOTORS:											
#	SIZE	MANUF	TYPE	SERIAL NO.	LOBES	DEPTH IN	DEPTH OUT	DATE IN	DATE OUT		

MUD MOTOR OPERATIONS:									
#	WOB	REV/GAL	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP	

SURVEYS										
Date	TMD	Incl	Azimuth	TVD	VS	NS	EW	DLS	Tool Type	

DAILY COSTS	DAILY	CUM	AFE		DAILY	CUM	AFE
8100..100: Permits & Fees			4,500	8100..105: Insurance			2,000
8100..110: Staking & Surveying			1,500	8100..120: Surface Damages & R			
8100..200: Location Roads			50,000	8100..210: Reclamation			
8100..220: Secondary Reclamat				8100..230: Pit Solidification			5,000
8100..300: Water Well				8100..310: Water/Water Dispos			7,500
8100..320: Mud & Chemicals			45,000	8100..325: Oil Base Mud Diesel			
8100..400: Drilling Rig			127,000	8100..402: Drilling Rig Cleani			
8100..405: Rig Fuel			40,000	8100..410: Mob/Demob			17,000
8100..420: Bits & Reamers			15,500	8100..500: Roustabout Services			7,000
8100..510: Testing/Inspection/			5,000	8100..520: Trucking & Hauling			10,000
8100..530: Equipment Rental			25,000	8100..531: Down Hole Motor Ren			1,500
8100..532: Solids Control Equi			7,000	8100..535: Directional Drillin			76,000
8100..540: Fishing				8100..600: Surface Casing/Inte			20,000
8100..605: Cementing Work			25,000	8100..610: P & A			
8100..700: Logging - Openhole			15,000	8100..705: Logging - Mud			
8100..800: Supervision/Consult			25,000	8100..810: Engineering/Evaluat			
8100..900: Contingencies				8100..950: Administrative O/H			
8100..999: Non Operated IDC				8200..510: Testing/Inspection/			2,000
8200..520: Trucking & Hauling			7,000	8200..530: Equipment Rental			37,500
8200..605: Cementing Work			25,000	8210..600: Production Casing			94,000
8210..620: Wellhead/Casing Hea			20,000	Total Cost			717,000

ULTRA RESOURCES, INC.
DAILY DRILLING REPORT DATE: 08/27/2014

WELL NAME	THREE RIVERS 4-36T-820	AFE#	140972	SPUD DATE	09/12/2014
WELL SITE CONSULTANT	JARED MEJORADO	PHONE#	713-948-9196	CONTRACTOR	Other
TD AT REPORT	(no data)	FOOTAGE		PRATE	CUM. DRLG. HRS 9.5 DRLG DAYS SINCE SPUD 0
ANTICIPATED TD	6.769'	PRESENT OPS	(nothing recorded)	GEOLOGIC SECT.	
DAILY MUD LOSS	SURF:	DH:		CUM. MUD LOSS	SURF: DH:
MUD COMPANY:			MUD ENGINEER:		
LAST BOP TEST	NEXT CASING SIZE	NEXT CASING DEPTH	SSE	SSED	

AFE Days vs Depth:	AFE Cost Vs Depth:
DWOP Days vs Depth:	# LL/BP Received Today:

RECENT CASINGS RUN:	Date Set	Size	Grade	Weight	Depth	FIT Depth	FIT ppg
Surface	08/24/2014	8 5/8	J-55	24	1,032		
Conductor	08/19/2014	16	ARJ-55	45	119		

RECENT BITS:									
BIT	SIZE	MANUF	TYPE	SERIAL NO.	JETS	TFA	DEPTH IN	DEPTH OUT	I-O-D-L-B-G-O-R

BIT OPERATIONS:												
BIT	WOB	RPM	GPM	PRESS	HHP	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP	

RECENT MUD MOTORS:												
#	SIZE	MANUF	TYPE	SERIAL NO.	LOBES	DEPTH IN	DEPTH OUT	DATE IN	DATE OUT			

MUD MOTOR OPERATIONS:												
#	WOB	REV/GAL	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP				

SURVEYS										
Date	TMD	Incl	Azimuth	TVD	VS	NS	EW	DLS	Tool Type	

DAILY COSTS	DAILY	CUM	AFE		DAILY	CUM	AFE
8100..100: Permits & Fees			4,500	8100..105: Insurance			2,000
8100..110: Staking & Surveying			1,500	8100..120: Surface Damages & R			
8100..200: Location Roads	27,449	27,449	50,000	8100..210: Reclamation			
8100..220: Secondary Reclamati				8100..230: Pit Solidification			5,000
8100..300: Water Well				8100..310: Water/Water Disposa	863	863	7,500
8100..320: Mud & Chemicals			45,000	8100..325: Oil Base Mud Diesel			
8100..400: Drilling Rig	30,464	30,464	127,000	8100..402: Drilling Rig Cleani			
8100..405: Rig Fuel			40,000	8100..410: Mob/Demob			17,000
8100..420: Bits & Reamers			15,500	8100..500: Roustabout Services			7,000
8100..510: Testing/Inspection/	1,246	1,246	5,000	8100..520: Trucking & Hauling			10,000
8100..530: Equipment Rental			25,000	8100..531: Down Hole Motor Ren			1,500
8100..532: Solids Control Equi			7,000	8100..535: Directional Drillin			76,000
8100..540: Fishing				8100..600: Surface Casing/Inte	17,645	17,645	20,000
8100..605: Cementing Work	19,157	19,157	25,000	8100..610: P & A			
8100..700: Logging - Openhole			15,000	8100..705: Logging - Mud			
8100..800: Supervision/Consult			25,000	8100..810: Engineering/Evaluat			
8100..900: Contingencies	10,556	10,556		8100..950: Administrative O/H			
8100..999: Non Operated IDC				8200..510: Testing/Inspection/			2,000
8200..520: Trucking & Hauling			7,000	8200..530: Equipment Rental			37,500
8200..605: Cementing Work			25,000	8210..600: Production Casing			94,000
8210..620: Wellhead/Casing Hea			20,000	Total Cost	107,380	107,380	717,000

ULTRA RESOURCES, INC.
DAILY DRILLING REPORT DATE: 08/31/2014

WELL NAME	THREE RIVERS 4-36T-820		AFE#	140972		SPUD DATE	09/12/2014	
WELL SITE CONSULTANT	JARED MEJORADO		PHONE#	713-948-9196		CONTRACTOR	Other	
TD AT REPORT	(no data)	FOOTAGE	PRATE	CUM. DRLG. HRS	9.5	DRLG DAYS SINCE SPUD	0	
ANTICIPATED TD	6.769'	PRESENT OPS	(nothing recorded)		GEOLOGIC SECT.			
DAILY MUD LOSS	SURF:	DH:	CUM. MUD LOSS		SURF:	DH:		
MUD COMPANY:			MUD ENGINEER:					
LAST BOP TEST	NEXT CASING SIZE		NEXT CASING DEPTH		SSE	SSED		

AFE Days vs Depth:		AFE Cost Vs Depth:	
DWOP Days vs Depth:		# LL/BP Received Today:	

RECENT CASINGS RUN:		Date Set	Size	Grade	Weight	Depth	FIT Depth	FIT ppg	
Surface		08/24/2014	8 5/8	J-55	24	1,032			
Conductor		08/19/2014	16	ARJ-55	45	119			

RECENT BITS:		MANUF	TYPE	SERIAL NO.	JETS	TFA	DEPTH IN	DEPTH OUT	I-O-D-L-B-G-O-R	
BIT	SIZE									

BIT OPERATIONS:		RPM	GPM	PRESS	HHP	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP
BIT	WOB										

RECENT MUD MOTORS:		MANUF	TYPE	SERIAL NO.	LOBES	DEPTH IN	DEPTH OUT	DATE IN	DATE OUT	
#	SIZE									

MUD MOTOR OPERATIONS:		REV/GAL	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP	
#	WOB								

SURVEYS		TMD	Incl	Azimuth	TVD	VS	NS	EW	DLS	Tool Type	
Date											

DAILY COSTS	DAILY	CUM	AFE		DAILY	CUM	AFE
8100..100: Permits & Fees			4,500	8100..105: Insurance			2,000
8100..110: Staking & Surveying			1,500	8100..120: Surface Damages & R			
8100..200: Location Roads		27,449	50,000	8100..210: Reclamation			
8100..220: Secondary Reclamati				8100..230: Pit Solidification			5,000
8100..300: Water Well				8100..310: Water/Water Dispos	863		7,500
8100..320: Mud & Chemicals			45,000	8100..325: Oil Base Mud Diesel			
8100..400: Drilling Rig		30,464	127,000	8100..402: Drilling Rig Cleani			
8100..405: Rig Fuel			40,000	8100..410: Mob/Demob			17,000
8100..420: Bits & Reamers			15,500	8100..500: Roustabout Services			7,000
8100..510: Testing/Inspection/		1,246	5,000	8100..520: Trucking & Hauling			10,000
8100..530: Equipment Rental			25,000	8100..531: Down Hole Motor Ren			1,500
8100..532: Solids Control Equi			7,000	8100..535: Directional Drillin			76,000
8100..540: Fishing				8100..600: Surface Casing/Inte	17,645		20,000
8100..605: Cementing Work		19,157	25,000	8100..610: P & A			
8100..700: Logging - Openhole			15,000	8100..705: Logging - Mud			
8100..800: Supervision/Consult			25,000	8100..810: Engineering/Evaluat			
8100..900: Contingencies		10,556		8100..950: Administrative O/H			
8100..999: Non Operated IDC				8200..510: Testing/Inspection/			2,000
8200..520: Trucking & Hauling			7,000	8200..530: Equipment Rental			37,500
8200..605: Cementing Work			25,000	8210..600: Production Casing			94,000
8210..620: Wellhead/Casing Hea			20,000	Total Cost		107,380	717,000

ULTRA RESOURCES, INC.
DAILY DRILLING REPORT DATE: 09/01/2014

WELL NAME

THREE RIVERS 4-36T-820

AFE#

140972

SPUD DATE

09/12/2014

WELL SITE CONSULTANT

JARED MEJORADO

PHONE#

713-948-9196

CONTRACTOR

Other

TD AT REPORT

(no data)

FOOTAGE

PRATE

CUM. DRLG. HRS

9.5

DRLG DAYS SINCE SPUD

0

ANTICIPATED TD

6.769'

PRESENT OPS

(nothing recorded)

GEOLOGIC SECT.

DAILY MUD LOSS

SURF:

DH:

CUM. MUD LOSS

SURF:

DH:

MUD COMPANY:

MUD ENGINEER:

LAST BOP TEST

NEXT CASING SIZE

NEXT CASING DEPTH

SSE

SSED

AFE Days vs Depth:

AFE Cost Vs Depth:

DWOP Days vs Depth:

LL/BP Received Today:

RECENT CASINGS RUN:			Date Set		Size	Grade	Weight	Depth	FIT Depth		FIT ppg	
Surface			08/24/2014		8 5/8	J-55	24	1,032				
Conductor			08/19/2014		16	ARJ-55	45	119				
RECENT BITS:												
BIT	SIZE	MANUF	TYPE	SERIAL NO.	JETS		TFA	DEPTH IN	DEPTH OUT	I-O-D-L-B-G-O-R		
BIT OPERATIONS:												
BIT	WOB	RPM	GPM	PRESS	HHP	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP	
RECENT MUD MOTORS:												
#	SIZE	MANUF	TYPE		SERIAL NO.		LOBES	DEPTH IN	DEPTH OUT	DATE IN	DATE OUT	
MUD MOTOR OPERATIONS:												
#	WOB	REV/GAL	HRS		24hr DIST		24HR ROP	CUM HRS		CUM DIST	CUM ROP	
SURVEYS												
Date	TMD	Incl	Azimuth		TVD	VS	NS	EW	DLS	Tool Type		

DAILY COSTS	DAILY	CUM	AFE		DAILY	CUM	AFE
8100..100: Permits & Fees			4,500	8100..105: Insurance			2,000
8100..110: Staking & Surveying			1,500	8100..120: Surface Damages & R			
8100..200: Location Roads		27,449	50,000	8100..210: Reclamation			
8100..220: Secondary Reclamati				8100..230: Pit Solidification			5,000
8100..300: Water Well				8100..310: Water/Water Disposa	863	7,500	
8100..320: Mud & Chemicals	2,363	2,363	45,000	8100..325: Oil Base Mud Diesel			
8100..400: Drilling Rig		30,464	127,000	8100..402: Drilling Rig Cleani			
8100..405: Rig Fuel			40,000	8100..410: Mob/Demob		17,000	
8100..420: Bits & Reamers			15,500	8100..500: Roustabout Services		7,000	
8100..510: Testing/Inspection/		1,246	5,000	8100..520: Trucking & Hauling		10,000	
8100..530: Equipment Rental			25,000	8100..531: Down Hole Motor Ren		1,500	
8100..532: Solids Control Equi			7,000	8100..535: Directional Drillin		76,000	
8100..540: Fishing				8100..600: Surface Casing/Inte	17,645	20,000	
8100..605: Cementing Work		19,157	25,000	8100..610: P & A			
8100..700: Logging - Openhole			15,000	8100..705: Logging - Mud			
8100..800: Supervision/Consult			25,000	8100..810: Engineering/Evaluat			
8100..900: Contingencies	260	10,816		8100..950: Administrative O/H			
8100..999: Non Operated IDC				8200..510: Testing/Inspection/			2,000
8200..520: Trucking & Hauling			7,000	8200..530: Equipment Rental			37,500
8200..605: Cementing Work			25,000	8210..600: Production Casing			94,000
8210..620: Wellhead/Casing Hea			20,000	Total Cost	2,622	110,002	717,000

ULTRA RESOURCES, INC.
DAILY DRILLING REPORT DATE: 09/10/2014

WELL NAME	THREE RIVERS 4-36T-820			AFE#	140972	SPUD DATE	09/12/2014	
WELL SITE CONSULTANT	JARED MEJORADO			PHONE#	713-948-9196	CONTRACTOR	Other	
TD AT REPORT	1,045'	FOOTAGE	0'	PRATE	CUM. DRLG. HRS	9.5	DRLG DAYS SINCE SPUD	0
ANTICIPATED TD	6,769'	PRESENT OPS	(Nothing recorded) at 0' at 1,045'			GEOLOGIC SECT.		
DAILY MUD LOSS	SURF:	DH:		CUM. MUD LOSS	SURF:	DH:		
MUD COMPANY:				MUD ENGINEER:				
LAST BOP TEST	NEXT CASING SIZE		30	NEXT CASING DEPTH		SSE	SSD	

AFE Days vs Depth:

DWOP Days vs Depth:

AFE Cost Vs Depth:

LL/BP Received Today:

RECENT CASINGS RUN:			Date Set		Size	Grade	Weight	Depth	FIT Depth		FIT ppg	
Surface			08/24/2014		8 5/8	J-55	24	1,032				
Conductor			08/19/2014		16	ARJ-55	45	119				
RECENT BITS:												
BIT	SIZE	MANUF	TYPE	SERIAL NO.	JETS		TFA	DEPTH IN	DEPTH OUT	I-O-D-L-B-G-O-R		
BIT OPERATIONS:												
BIT	WOB	RPM	GPM	PRESS	HHP	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP	
RECENT MUD MOTORS:												
#	SIZE	MANUF	TYPE		SERIAL NO.		LOBES	DEPTH IN	DEPTH OUT	DATE IN	DATE OUT	
MUD MOTOR OPERATIONS:												
#	WOB	REV/GAL	HRS		24hr DIST		24HR ROP	CUM HRS		CUM DIST		CUM ROP
SURVEYS												
Date	TMD	Incl	Azimuth		TVD	VS	NS	EW	DLS	Tool Type		

DAILY COSTS	DAILY	CUM	AFE		DAILY	CUM	AFE
8100..100: Permits & Fees			4,500	8100..105: Insurance			2,000
8100..110: Staking & Surveying			1,500	8100..120: Surface Damages & R			
8100..200: Location Roads		27,449	50,000	8100..210: Reclamation			
8100..220: Secondary Reclamati				8100..230: Pit Solidification			5,000
8100..300: Water Well				8100..310: Water/Water Disposa		863	7,500
8100..320: Mud & Chemicals		2,363	45,000	8100..325: Oil Base Mud Diesel			
8100..400: Drilling Rig		30,464	127,000	8100..402: Drilling Rig Cleani			
8100..405: Rig Fuel			40,000	8100..410: Mob/Demob			17,000
8100..420: Bits & Reamers			15,500	8100..500: Roustabout Services			7,000
8100..510: Testing/Inspection/		1,246	5,000	8100..520: Trucking & Hauling			10,000
8100..530: Equipment Rental			25,000	8100..531: Down Hole Motor Ren			1,500
8100..532: Solids Control Equi			7,000	8100..535: Directional Drillin			76,000
8100..540: Fishing				8100..600: Surface Casing/Inte		17,645	20,000
8100..605: Cementing Work		19,157	25,000	8100..610: P & A			
8100..700: Logging - Openhole			15,000	8100..705: Logging - Mud			
8100..800: Supervision/Consult			25,000	8100..810: Engineering/Evaluat			
8100..900: Contingencies		10,816		8100..950: Administrative O/H			
8100..999: Non Operated IDC				8200..510: Testing/Inspection/			2,000
8200..520: Trucking & Hauling			7,000	8200..530: Equipment Rental			37,500
8200..605: Cementing Work			25,000	8210..600: Production Casing			94,000
8210..620: Wellhead/Casing Hea			20,000	Total Cost		110,002	717,000

ULTRA RESOURCES, INC.
DAILY DRILLING REPORT DATE: 09/11/2014

WELL NAME

THREE RIVERS 4-36T-820

AFE#

140972

SPUD DATE

09/12/2014

WELL SITE CONSULTANT

JOHN FREITAS/KING BROWN

PHONE#

713-948-9196

CONTRACTOR

Other

TD AT REPORT

1,045'

FOOTAGE

0'

PRATE

CUM. DRLG. HRS

9.5

DRLG DAYS SINCE SPUD

0

ANTICIPATED TD

6,769'

PRESENT OPS

(Nothing recorded) at 0' at 1,045'

GEOLOGIC SECT.

DAILY MUD LOSS

SURF:

DH:

CUM. MUD LOSS

SURF:

DH:

MUD COMPANY:

MUD ENGINEER:

LAST BOP TEST

NEXT CASING SIZE

30

NEXT CASING DEPTH

SSE

SSED

AFE Days vs Depth:

AFE Cost Vs Depth:

DWOP Days vs Depth:

LL/BP Received Today:

FUEL AND WATER USAGE

Fluid	Used	Received	Transferred	On Hand	Cum.Used
Fuel		1,780.0		1,780.0	1,500.0
Gas					
Fresh Well Water					
Nano Water					
Frac Water					
Reserve Pit Water					
Boiler Hours					
Air Heater Hours					
Urea				0.0	
Urea Sys 1 Hrs					
Urea Sys 2 Hrs					
Urea Sys 3 Hrs					

RECENT CASINGS RUN:

Date Set

08/24/2014

Size

8 5/8

Grade

J-55

Weight

24

Depth

1,032

FIT Depth

FIT ppg

Surface

08/19/2014

16

ARJ-55

45

119

Conductor

RECENT BITS:

BIT

SIZE

MANUF

TYPE

SERIAL NO.

JETS

TFA

DEPTH IN

DEPTH OUT

I-O-D-L-B-G-O-R

BIT OPERATIONS:

BIT

WOB

RPM

GPM

PRESS

HHP

HRS

24hr DIST

24HR ROP

CUM HRS

CUM DIST

CUM ROP

RECENT MUD MOTORS:

#

SIZE

MANUF

TYPE

SERIAL NO.

LOBES

DEPTH IN

DEPTH OUT

DATE IN

DATE OUT

MUD MOTOR OPERATIONS:

#

WOB

REV/GAL

HRS

24hr DIST

24HR ROP

CUM HRS

CUM DIST

CUM ROP

SURVEYS

Date

TMD

Incl

Azimuth

TVD

VS

NS

EW

DLS

Tool Type

DAILY COSTS	DAILY	CUM	AFE		DAILY	CUM	AFE
8100..100: Permits & Fees			4,500	8100..105: Insurance			2,000
8100..110: Staking & Surveying			1,500	8100..120: Surface Damages & R			
8100..200: Location Roads		27,449	50,000	8100..210: Reclamation			
8100..220: Secondary Reclamati				8100..230: Pit Solidification			5,000
8100..300: Water Well				8100..310: Water/Water Disposa	863	7,500	
8100..320: Mud & Chemicals		2,363	45,000	8100..325: Oil Base Mud Diesel			
8100..400: Drilling Rig		30,464	127,000	8100..402: Drilling Rig Cleani			
8100..405: Rig Fuel			40,000	8100..410: Mob/Demob		17,000	
8100..420: Bits & Reamers			15,500	8100..500: Roustabout Services		7,000	
8100..510: Testing/Inspection/		1,246	5,000	8100..520: Trucking & Hauling		10,000	
8100..530: Equipment Rental			25,000	8100..531: Down Hole Motor Ren		1,500	
8100..532: Solids Control Equi			7,000	8100..535: Directional Drillin		76,000	
8100..540: Fishing				8100..600: Surface Casing/Inte	17,645	20,000	
8100..605: Cementing Work		19,157	25,000	8100..610: P & A			
8100..700: Logging - Openhole			15,000	8100..705: Logging - Mud			
8100..800: Supervision/Consult			25,000	8100..810: Engineering/Evaluat			
8100..900: Contingencies		10,816		8100..950: Administrative O/H			
8100..999: Non Operated IDC				8200..510: Testing/Inspection/			2,000
8200..520: Trucking & Hauling			7,000	8200..530: Equipment Rental			37,500
8200..605: Cementing Work			25,000	8210..600: Production Casing			94,000
8210..620: Wellhead/Casing Hea			20,000	Total Cost		110,002	717,000

ULTRA RESOURCES, INC.
DAILY DRILLING REPORT DATE: 09/12/2014

WELL NAME	THREE RIVERS 4-36T-820			AFE#	140972	SPUD DATE	09/12/2014			
WELL SITE CONSULTANT	JOHN FREITAS/KING BROWN			PHONE#	713-948-9196	CONTRACTOR	Ensign 122			
TD AT REPORT	1,045'	FOOTAGE	0'	PRATE	CUM. DRLG. HRS		9.5	DRLG DAYS SINCE SPUD	0	
ANTICIPATED TD	6,769'	PRESENT OPS			Tripping in hole at 1,045'		GEOLOGIC SECT.			
DAILY MUD LOSS	SURF:	0	DH:	0	CUM. MUD LOSS		SURF:	0	DH:	0
MUD COMPANY:	ANCHOR			MUD ENGINEER:		SEAN LEHNEN				
LAST BOP TEST	09/12/2014	NEXT CASING SIZE	5 1/2	NEXT CASING DEPTH		6,769	SSE	0	SSED	0

TIME BREAKDOWN											
NIPPLE UP B.O.P.			3.00	OTHER			2.00	PRESSURE TEST B.O.P.			7.00
RIG UP / TEAR DOWN			10.50	WORK BHA			1.50				

DETAILS			
Start	End	Hrs	
06:00	16:30	10:30	MOVE RIG- MOVE IN RIG, MOVE IN CAMPS,RIG UP NEW CENTRAFUGE, SPOT PUMPS, MOVE IN DRILL PIPE TUBS, SET UP NEW DIR DRILLERS, STRAP TOOLS.
16:30	17:30	01:00	NIPPLE UP BOP.
17:30	18:30	01:00	HOLD A PRE SPUD MEETING WITH BOTH ENSIGN RIG CREWS, TOOL PUSHER, DIR DRILLERS, MUD ENGINEER, COMPANY REPS AND SUPERENTENDANT
18:30	20:30	02:00	NIPPLE UP BOP.
20:30	03:30	07:00	TEST BOP-(WALKER)PIPE RAMS, BLIND RAMS, CHOKE LINE & CHOKE VALVES, FOSV, INSIDE BOP, KILL LINE AND VALVES, CHOKE MANIFOLD, HCR & MANUAL VALVE ALL @ 10 MIN 250 PSI LOW 10 MIN 3000 PSI HIGH - ANNULAR @ 10 MIN 1500 PSI HIGH 10 MIN 250 PSI LOW - CASING @ 30 MIN 1500 PSI - ACCUMULATOR FUNCTION TEST, RIG DOWN TESTER.
03:30	05:00	01:30	P/U AND ORIENT BHA RIH W/SAME T/850,'
05:00	06:00	01:00	P/U ROTATING HEAD, ROLLED PUMPS AND SAW THAT THE PUMP STROKES WERE NOT WORKING PROPERLY, LOOKING AT THE SENSORS AND CABLES TO FIND THE PROBLEM.
05:55	05:55	00:00	SAFETY MEETING DAYS: PINCH POINTS, WORKING AROUND THIRD PARTY TRUCKS, FORKLIFT SAFETY. SAFETY MEETING NIGHTS: PINCH POINTS, WORKING AROUND THIRD PARTY TRUCKS. REGULATORY NOTICES: NONE. REGULATORY VISITS: NONE. INCIDENTS: NONE. SAFETY DRILLS: NONE.
NOTE:			
WE HAD A SAFETY MEETING WITH BOTH CREWS AND BRYAN COLTHARP.			

AFE Days vs Depth:		AFE Cost Vs Depth:	
DWOP Days vs Depth:		# LL/BP Received Today:	

FUEL AND WATER USAGE					
Fluid	Used	Received	Transferred	On Hand	Cum.Used
Fuel	311.0	3,641.0		5,110.0	1,811.0
Gas					
Fresh Well Water					
Nano Water					
Frac Water					
Reserve Pit Water					
Boiler Hours					
Air Heater Hours					
Urea				0.0	
Urea Sys 1 Hrs					
Urea Sys 2 Hrs					
Urea Sys 3 Hrs					

RECENT CASINGS RUN:	Date Set	Size	Grade	Weight	Depth	FIT Depth	FIT ppg				
Surface	08/24/2014	8 5/8	J-55	24	1,032						
Conductor	08/19/2014	16	ARJ-55	45	119						

RECENT BITS:											
BIT	SIZE	MANUF	TYPE	SERIAL NO.	JETS	TFA	DEPTH IN	DEPTH OUT	I-O-D-L-B-G-O-R		
1	7.875	HTC	T506	7152624	12/12/12/12/12/12	0.663	1,045		-----		

BIT OPERATIONS:											
BIT	WOB	RPM	GPM	PRESS	HHP	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP
1		65/128	440	1,500	2.03	0.00	0		0.00	0	

RECENT MUD MOTORS:											
#	SIZE	MANUF	TYPE	SERIAL NO.	LOBES	DEPTH IN	DEPTH OUT	DATE IN	DATE OUT		
1	6.500	HUNTING	ARROW	6236	7/8	1,045		09/12/2014			

MUD MOTOR OPERATIONS:											
#	WOB	REV/GAL	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP			
1	22	0.29	0.00	0		0.00	0				

SURVEYS											
Date	TMD	Incl	Azimuth	TVD	VS	NS	EW	DLS	Tool Type		
09/12/2014	3,147	11.2	102.95	3,134	170.6	-3.25	175.42	1.4	MWD Survey Tool		
09/12/2014	3,057	10.0	101.36	3,045	154.1	0.24	159.26	1.1	MWD Survey Tool		
09/12/2014	2,966	9.0	101.05	2,956	139.1	3.16	144.53	1.2	MWD Survey Tool		

MUD PROPERTIES											
Type	LSND	Mud Wt	9.2	Alk.		Sand %		XS Lime lb/bbl			
Temp.		Gels 10sec		Cl ppm		Solids %		Salt bbls			
Visc		Gels 10min		Ca ppm		LGS %		LCM ppb			
PV	10	pH		pF		Oil %		API WL cc			
YP	6	Filter Cake/32		Mf		Water %		HTHP WL cc			
O/W Ratio		ES		WPS							
Comments:	MEGA CIDE-4,PALLETS-11,TRAILER-1.										

Flaring:	Flare Foot-Minutes	0	Flared MCF	0.0	Cum. Flared MCF	0.0
----------	--------------------	---	------------	-----	-----------------	-----

SURFACE PUMP/BHA INFORMATION													
Pump 1 Liner	6.5	Stroke Len	9.0	SPM	125	PSI	_____	GPM	440	SPR	43	Slow PSI	_____
Pump 2 Liner	_____	Stroke Len	_____	SPM	_____	PSI	_____	GPM	_____	SPR	43	Slow PSI	_____
Pump 32 Liner	_____	Stroke Len	_____	SPM	_____	PSI	_____	GPM	_____	SPR	_____	Slow PSI	_____
BHA Makeup	STEARABLE												
Up Weight	_____	Dn Weight	_____	RT Weight	_____			Length	889.8			Hours on BHA	_____
	_____							Torque	_____			Hours on Motor	_____

BHA MAKEUP:

#	Component	OD	ID	Length	Weight (ft/lb)	Serial Number	Description
1	DRILL BIT	7.875		1.00		7152624	HUGHES T506
2	MUD MOTOR	7.000	3.250	34.92		6199	1.5 DEG FBH 7/8 6.7STG. .29 REV
3	NON MAG MONEL	6.500	3.250	31.53		ATM64-513	4.5 XH P x B
4	EM GAP SUB	6.400	3.250	3.80		GSB0398	4.5 XH P x B
5	NON MAG FLEX MONEL	6.500	2.813	29.61		9041	4.5 XH P x B
6	DRILL COLLAR	6.500	2.250	31.06		RIG	4.5 XH P x B
7	18JTS HWDP	4.500	2.313	545.39		RIG	4.5 XH P x B
8	DRILLING JARS	6.550	2.625	30.94		42986J	4.5 XH P x B(SMITH)HE JARS
9	6JTS HWDP	4.500	2.313	181.59		RIG	4.5 XH P x B

DAILY COSTS	DAILY	CUM	AFE		DAILY	CUM	AFE
8100..100: Permits & Fees			4,500	8100..105: Insurance			2,000
8100..110: Staking & Surveying			1,500	8100..120: Surface Damages & R			
8100..200: Location Roads		27,449	50,000	8100..210: Reclamation			
8100..220: Secondary Reclamati				8100..230: Pit Solidification			5,000
8100..300: Water Well				8100..310: Water/Water Disposa	2,363	3,226	7,500
8100..320: Mud & Chemicals	4,993	7,356	45,000	8100..325: Oil Base Mud Diesel			
8100..400: Drilling Rig	37,425	67,889	127,000	8100..402: Drilling Rig Cleani			
8100..405: Rig Fuel	11,740	11,740	40,000	8100..410: Mob/Demob	1,571	1,571	17,000
8100..420: Bits & Reamers			15,500	8100..500: Roustabout Services			7,000
8100..510: Testing/Inspection/		1,246	5,000	8100..520: Trucking & Hauling			10,000
8100..530: Equipment Rental	3,260	3,260	25,000	8100..531: Down Hole Motor Ren			1,500
8100..532: Solids Control Equi	425	425	7,000	8100..535: Directional Drillin	21,395	21,395	76,000
8100..540: Fishing				8100..600: Surface Casing/Inte	407	18,052	20,000
8100..605: Cementing Work		19,157	25,000	8100..610: P & A			
8100..700: Logging - Openhole			15,000	8100..705: Logging - Mud			
8100..800: Supervision/Consult	5,000	5,000	25,000	8100..810: Engineering/Evaluat			
8100..900: Contingencies	9,745	20,561		8100..950: Administrative O/H			
8100..999: Non Operated IDC				8200..510: Testing/Inspection/			2,000
8200..520: Trucking & Hauling			7,000	8200..530: Equipment Rental			37,500
8200..605: Cementing Work			25,000	8210..600: Production Casing			94,000
8210..620: Wellhead/Casing Hea			20,000	Total Cost	98,324	208,326	717,000

ULTRA RESOURCES, INC.
DAILY DRILLING REPORT DATE: 09/13/2014

WELL NAME	THREE RIVERS 4-36T-820			AFE#	140972		SPUD DATE	09/12/2014		
WELL SITE CONSULTANT	JOHN FREITAS/KING BROWN			PHONE#	713-948-9196		CONTRACTOR	Ensign 122		
TD AT REPORT	3,929'	FOOTAGE	2,884'	PRATE	128.2	CUM. DRLG. HRS	32.0	DRLG DAYS SINCE SPUD	1	
ANTICIPATED TD	6,769'	PRESNET OPS	Directional Drilling at 3,929'			GEOLOGIC SECT.				
DAILY MUD LOSS	SURF:	3	DH:	0	CUM. MUD LOSS	SURF:	3	DH:	0	
MUD COMPANY:	ANCHOR			MUD ENGINEER:			SEAN LEHNEN			
LAST BOP TEST	09/12/2014	NEXT CASING SIZE	5 1/2	NEXT CASING DEPTH		6,770	SSE	0	SSED	0

TIME BREAKDOWN											
COND MUD & CIRCULATE		0.50		DIRECTIONAL DRILLING		22.50		RIG SERVICE		1.00	

DETAILS			
Start	End	Hrs	
06:00	08:00	02:00	TAG CEMENT AT 932', DRILL OUT CEMENT, FLOAT AT 995', DRILL OUT CEMENT AND SHOE.
08:00	13:30	05:30	DIR DRILL F/ 1045' T/ 2023' 978' @ 177.8 FT/HR - W/ 4-15K WT ON BIT - 440GPM - 65-75RPM - 400-600 DIFF - 5-9K TORQUE - 1550 PSI SPP.
13:30	14:00	00:30	RIG SERVICE- LUBRICATE RIG (GREASE PIPEARMS, ROUGHNECK, WASH PIPE AND SHOCK SUB)TIGHTEN MUD SAVER SERVICE AND INSPECT PUMP # 1 PUMP #2 AND HPU MOTORS.
14:00	19:00	05:00	DIR DRILL F/ 2023' T/2840' 817' @ 163.4 FT/HR - W/ 4-15K WT ON BIT - 440GPM - 65-75RPM - 300-500 DIFF - 5-9K TORQUE - 1550 PSI SPP.
19:00	19:30	00:30	CIRC GAS AND OIL OUT. 5200 UNITS W/2' FLARE. INCREASE MUD WEIGHT T/ 9.5 PPG.
19:30	00:00	04:30	DIR DRILL F/ 2840' T/3342' 502' @ 111.5 FT/HR - W/15-20K WT ON BIT - 440GPM - 62RPM - 300-400 DIFF - 7-10300K TORQUE - 2129 PSI SPP.
00:00	00:30	00:30	RIG SERV. LUBE RIG.
00:30	06:00	05:30	DIR DRILL F/3342' T/3929' 587' @ 106.7 FT/HR - W/15-20K WT ON BIT - 440GPM - 62RPM - 300-400 DIFF - 7-10200K TORQUE - 2229 PSI SPP.ON BOTTOM ROP 194.86
05:55	05:55	00:00	SAFETY MEETING DAYS: DRILLING AND FORK LIFT SAFETY.
			SAFETY MEETING NIGHTS: DRILLING AND MAKING CONNECTIONS.
			REGULATORY NOTICES: NONE.
			REGULATORY VISITS: NONE.
			INCIDENTS: NONE.
			SAFETY DRILLS: BOP DRILL DAY AND NIGHT CREW..

AFE Days vs Depth:		AFE Cost Vs Depth:	
DWOP Days vs Depth:		# LL/BP Received Today:	

FUEL AND WATER USAGE	Used	Received	Transferred	On Hand	Cum.Used				
Fluid									
Fuel	1,360.0			3,750.0	3,171.0				
Gas									
Fresh Well Water									
Nano Water									
Frac Water									
Reserve Pit Water									
Boiler Hours									
Air Heater Hours									
Urea				0.0					
Urea Sys 1 Hrs									
Urea Sys 2 Hrs									
Urea Sys 3 Hrs									

RECENT CASINGS RUN:	Date Set	Size	Grade	Weight	Depth	FIT Depth	FIT ppg		
Surface	08/24/2014	8 5/8	J-55	24	1,032				
Conductor	08/19/2014	16	ARJ-55	45	119				

RECENT BITS:	SIZE	MANUF	TYPE	SERIAL NO.	JETS	TFA	DEPTH IN	DEPTH OUT	I-O-D-L-B-G-O-R
BIT									
1	7.875	HTC	T506	7152624	12/12/12/12/12/12	0.663	1,045		-----

BIT OPERATIONS:	WOB	RPM	GPM	PRESS	HHP	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP
BIT											
1		65/128	440	2,100	2.10	22.50	2,884	128.18	22.50	2,884	128.18

RECENT MUD MOTORS:	SIZE	MANUF	TYPE	SERIAL NO.	LOBES	DEPTH IN	DEPTH OUT	DATE IN	DATE OUT
#									
1	6.500	HUNTING	ARROW	6236	7/8	1,045		09/12/2014	

MUD MOTOR OPERATIONS:	WOB	REV/GAL	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP
#								
1	25	0.29	22.50	2,884	128.18	22.50	2,884	128.18

SURVEYS	Date	TMD	Incl	Azimuth	TVD	VS	NS	EW	DLS	Tool Type
	09/13/2014	4,959	1.8	178.26	4,929	386.1	-81.10	377.86	0.4	MWD Survey Tool
	09/13/2014	4,868	1.8	166.76	4,838	385.1	-78.26	377.48	0.7	MWD Survey Tool
	09/13/2014	4,778	2.0	147.28	4,748	383.2	-75.57	376.31	0.6	MWD Survey Tool

MUD PROPERTIES	Type	LSND	Mud Wt	9.5	Alk.	0.0	Sand %	0.0	XS Lime lb/bbl	
	Temp.	92	Gels 10sec	1	Cl ppm	1,600	Solids %	8.0	Salt bbls	
	Visc	38	Gels 10min	4	Ca ppm	20	LGS %	8.0	LCM ppb	
	PV	8	pH	10.2	pF	0.0	Oil %	0.0	API WL cc	8.0
	YP	4	Filter Cake/32	1	Mf	0.0	Water %	92.0	HTHP WL cc	
O/W Ratio	ES									
Comments:	CEDER FIBER-5,DRISPAK-2,GEL-14,LIGNITE-3,MICA-6,PHPA-5,FLOWZAN-2,SODIUM BICARB-5,WALNUT-1,MEGA CIDE-4,ECOSEAL-8,TRAILER-1.									

Flaring:	Flare Foot-Minutes	0	Flared MCF	0.0	Cum. Flared MCF	0.0			
----------	--------------------	---	------------	-----	-----------------	-----	--	--	--

SURFACE PUMP/BHA INFORMATION	Pump 1 Liner	6.5	Stroke Len	9.0	SPM	125	PSI		GPM	440	SPR	43	Slow PSI	350
	Pump 2 Liner		Stroke Len		SPM		PSI		GPM		SPR		Slow PSI	
	Pump 32 Liner		Stroke Len		SPM		PSI		GPM		SPR		Slow PSI	
BHA Makeup	STEARABLE													
Up Weight	109,000	Dn Weight	87,000	RT Weight	96,000			Length	889.8			Hours on BHA	23	
								Torque	9,700			Hours on Motor	23	

BHA MAKEUP:

#	Component	OD	ID	Length	Weight (ft/lb)	Serial Number	Description
1	DRILL BIT	7.875		1.00		7152624	HUGHES T506
2	MUD MOTOR	7.000	3.250	34.92		6199	1.5 DEG FBH 7/8 6.7STG. .29 REV
3	NON MAG MONEL	6.500	3.250	31.53		ATM64-513	4.5 XH P x B
4	EM GAP SUB	6.400	3.250	3.80		GSB0398	4.5 XH P x B
5	NON MAG FLEX MONEL	6.500	2.813	29.61		9041	4.5 XH P x B
6	DRILL COLLAR	6.500	2.250	31.06		RIG	4.5 XH P x B
7	18JTS HWDP	4.500	2.313	545.39		RIG	4.5 XH P x B
8	DRILLING JARS	6.550	2.625	30.94		42986J	4.5 XH P x B(SMITH)HE JARS
9	6JTS HWDP	4.500	2.313	181.59		RIG	4.5 XH P x B

DAILY COSTS	DAILY	CUM	AFE		DAILY	CUM	AFE
8100..100: Permits & Fees			4,500	8100..105: Insurance			2,000
8100..110: Staking & Surveying			1,500	8100..120: Surface Damages & R			
8100..200: Location Roads		27,449	50,000	8100..210: Reclamation			
8100..220: Secondary Reclamati				8100..230: Pit Solidification			5,000
8100..300: Water Well				8100..310: Water/Water Disposa	190	3,416	7,500
8100..320: Mud & Chemicals	3,373	10,729	45,000	8100..325: Oil Base Mud Diesel			
8100..400: Drilling Rig	19,425	87,314	127,000	8100..402: Drilling Rig Cleani			
8100..405: Rig Fuel		11,740	40,000	8100..410: Mob/Demob		1,571	17,000
8100..420: Bits & Reamers			15,500	8100..500: Roustabout Services	500	500	7,000
8100..510: Testing/Inspection/	3,735	4,981	5,000	8100..520: Trucking & Hauling			10,000
8100..530: Equipment Rental	4,760	8,020	25,000	8100..531: Down Hole Motor Ren			1,500
8100..532: Solids Control Equi	425	850	7,000	8100..535: Directional Drillin		21,395	76,000
8100..540: Fishing				8100..600: Surface Casing/Inte		18,052	20,000
8100..605: Cementing Work		19,157	25,000	8100..610: P & A			
8100..700: Logging - Openhole			15,000	8100..705: Logging - Mud			
8100..800: Supervision/Consult	5,000	10,000	25,000	8100..810: Engineering/Evaluat			
8100..900: Contingencies	4,378	24,939		8100..950: Administrative O/H			
8100..999: Non Operated IDC				8200..510: Testing/Inspection/			2,000
8200..520: Trucking & Hauling			7,000	8200..530: Equipment Rental			37,500
8200..605: Cementing Work			25,000	8210..600: Production Casing	82,652	82,652	94,000
8210..620: Wellhead/Casing Hea			20,000	Total Cost	124,438	332,764	717,000

ULTRA RESOURCES, INC.
DAILY DRILLING REPORT DATE: 09/14/2014

WELL NAME	THREE RIVERS 4-36T-820			AFE#	140972		SPUD DATE	09/12/2014		
WELL SITE CONSULTANT	JOHN FREITAS/KING BROWN			PHONE#	713-948-9196		CONTRACTOR	Ensign 122		
TD AT REPORT	6.385'	FOOTAGE	2.456'	PRATE	106.8	CUM. DRLG. HRS	55.0	DRLG DAYS SINCE SPUD	2	
ANTICIPATED TD	6.769'	PRESENT OPS			Directional Drilling at 6.385'		GEOLOGIC SECT.			
DAILY MUD LOSS	SURF:	5	DH:	350	CUM. MUD LOSS	SURF:	8	DH:	350	
MUD COMPANY:	ANCHOR			MUD ENGINEER:			SEAN LEHNEN			
LAST BOP TEST	09/12/2014	NEXT CASING SIZE	5 1/2	NEXT CASING DEPTH		6,747	SSE	0	SSED	0

TIME BREAKDOWN			
DIRECTIONAL DRILLING	23.00	RIG SERVICE	1.00

DETAILS				
Start	End	Hrs		
06:00	12:00	06:00	DIR DRILL F/3929' T/4605' 676' @ 112.6 FT/HR - W/18-26K WT ON BIT - 440GPM - 65-70RPM - 350-450 DIFF - 7-10200K TORQUE - 2350 PSI SPP.	
12:00	12:30	00:30	RIG SERVICE- LUBRICATE RIG (GREASE PIPEARMS, ROUGHNECK, WASH PIPE AND SHOCK SUB)SERVICE AND INSPECT PUMP # 1 PUMP #2 AND HPU MOTORS.	
12:30	00:00	11:30	DIR DRILL F/4605' T/5826' 1221' @ 106.2FT/HR - W/18-26K WT ON BIT - 440GPM - 63 RPM - 450 DIFF - 7-10200K TORQUE - 2450 PSI SPP.	
00:00	00:30	00:30	RIG SERV. LUBE RIG.	
00:30	06:00	05:30	DIR DRILL F/5826' T/6385' 559' @ 101.6FT/HR - W/18-26K WT ON BIT - 440GPM - 63 RPM - 450 DIFF - 7-10200K TORQUE - 2450 PSI SPP.	
05:55	05:55	00:00	SAFETY MEETING DAYS: PPE & MIXING CHEMICALS.	
			SAFETY MEETING NIGHTS: PPE & MIXING CHEMICALS	
			REGULATORY NOTICES: INTENT TO RUN PRODUCTION CASING WAS GIVEN TO STATE.	
			REGULATORY VISITS: NONE.	
			INCIDENTS: NONE.	
			SAFETY DRILLS: NONE.	

AFE Days vs Depth:		AFE Cost Vs Depth:	
DWOP Days vs Depth:		# LL/BP Received Today:	

FUEL AND WATER USAGE					
Fluid	Used	Received	Transferred	On Hand	Cum.Used
Fuel	1,720.0	2,660.0		4,690.0	4,891.0
Gas					
Fresh Well Water					
Nano Water					
Frac Water					
Reserve Pit Water					
Boiler Hours					
Air Heater Hours					
Urea				0.0	
Urea Sys 1 Hrs					
Urea Sys 2 Hrs					
Urea Sys 3 Hrs					

CASING EQUIPMENT	
154 JOINTS OF 5.5" 17# PRODUCTION CASING, 2 MARKERS SET AT 5901' AND 5032'. 41 CENTRALIZERS.	

CEMENT JOB SUMMARY	
R/U HES TO FLOOR-CHECK HEAD: LOAD PLUG WITNESED BY CO-MAN. R/U HEAD & IRON.PUMP 3bbls WTR & TEST LINES T/5,000psi. PUMP 50bbl TUNED SPACER III. MIX & PUMP 148bbls LEAD CMT@11.0ppg/YIELD OF 3.541ft3/SK/21.31gal WTR/SK(235SKS),MIX & PUMP 103bbls TAIL CMT@14.0ppg/1.35ft3/SK/5.82gal/SK (430SKS). WASH UP. DROP PLUG & DISP/157.0bbls WTR.BUMP PLUG/2173=500psi OVER FCP OF 1615psi. BLEED BACK 1.0bbls T/TRUCK. FLOATS HELD.***RETURNS SLOWED AT 130 BBLs OF DISPLACEMENT***NO CEMENT TO SURFACE***	

RECENT CASINGS RUN:	Date Set	Size	Grade	Weight	Depth	FIT Depth	FIT ppg
Production	09/14/2014	5 1/2	J-55	17	6,747		
Surface	08/24/2014	8 5/8	J-55	24	1,032		
Conductor	08/19/2014	16	ARJ-55	45	119		

RECENT BITS:										
BIT	SIZE	MANUF	TYPE	SERIAL NO.	JETS	TFA	DEPTH IN	DEPTH OUT	I-O-D-L-B-G-O-R	
1	7.875	HTC	T506	7152624	12/12/12/12/12/12	0.663	1,045		-----	

BIT OPERATIONS:											
BIT	WOB	RPM	GPM	PRESS	HHP	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP
1		60/128	440	2,400	2.16	23.00	2,456	106.78	45.50	5,340	117.36

RECENT MUD MOTORS:											
#	SIZE	MANUF	TYPE	SERIAL NO.	LOBES	DEPTH IN	DEPTH OUT	DATE IN	DATE OUT		
1	6.500	HUNTING	ARROW	6236	7/8	1,045		09/12/2014			

MUD MOTOR OPERATIONS:										
#	WOB	REV/GAL	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP		
1	25	0.29	23.00	2,456	106.78	45.50	5,340	117.36		

SURVEYS										
Date	TMD	Incl	Azimuth	TVD	VS	NS	EW	DLS	Tool Type	
09/14/2014	6,760	1.9	182.98	6,729	406.3	-138.69	383.83	0.0	Projected Survey Station	
09/14/2014	6,708	1.9	182.98	6,677	406.0	-136.96	383.92	0.8	MWD Survey Tool	
09/14/2014	6,680	1.8	188.88	6,649	405.9	-136.06	384.01	0.8	MWD Survey Tool	

MUD PROPERTIES										
Type	LSND	Mud Wt	9.8	Alk.	0.0	Sand %	0.0	XS Lime lb/bbl		
Temp.	102	Gels 10sec	4	Cl ppm	2,400	Solids %	8.0	Salt bbls		
Visc	40	Gels 10min	12	Ca ppm	30	LGS %	5.0	LCM ppb		
PV	9	pH	9.8	pF	0.0	Oil %	0.0	API WL cc	7.8	
YP	9	Filter Cake/32	1	Mf	0.0	Water %	92.0	HTHP WL cc		
O/W Ratio		ES		WPS						
Comments:	ALUMINUM STEARATE-1,ANCO BAR-138,CEDER FIBER-3,POLY SWELL-1,DRISPAK-9,GEL-39,LIGNITE-5,LIME-18,PHPA-7,SAWDUCT-125,FLOWZAN-4,WALNUT-2,MEGA CIDE-4,ECOSEAL-35,DRISPAC LOW VIS-3,TRAILER-1,ENGINEERING-1.									

Flaring:	Flare Foot-Minutes	0	Flared MCF	0.0	Cum. Flared MCF	0.0
----------	--------------------	---	------------	-----	-----------------	-----

SURFACE PUMP/BHA INFORMATION

Pump 1 Liner	<u>6.5</u>	Stroke Len	<u>9.0</u>	SPM	<u>125</u>	PSI	<u> </u>	GPM	<u>440</u>	SPR	<u>43</u>	Slow PSI	<u>350</u>
Pump 2 Liner	<u> </u>	Stroke Len	<u> </u>	SPM	<u> </u>	PSI	<u> </u>	GPM	<u> </u>	SPR	<u>43</u>	Slow PSI	<u>383</u>
Pump 32 Liner	<u> </u>	Stroke Len	<u> </u>	SPM	<u> </u>	PSI	<u> </u>	GPM	<u> </u>	SPR	<u> </u>	Slow PSI	<u> </u>
BHA Makeup	STEARABLE											Hours on BHA	<u>46</u>
Up Weight	<u>155,000</u>	Dn Weight	<u>115,000</u>	RT Weight	<u>134,000</u>			Length	<u>889.8</u>			Hours on Motor	<u>46</u>
								Torque	<u>10,200</u>				

BHA MAKEUP:

#	Component	OD	ID	Length	Weight (ft/lb)	Serial Number	Description
1	DRILL BIT	7.875		1.00		7152624	HUGHES T506 6X12
2	MUD MOTOR	7.000	3.250	34.92		6199	1.5 DEG FBH 7/8 6.7STG. .29 REV
3	NON MAG MONEL	6.500	3.250	31.53		ATM64-513	4.5 XH P x B
4	EM GAP SUB	6.400	3.250	3.80		GSB0398	4.5 XH P x B
5	NON MAG FLEX MONEL	6.500	2.813	29.61		9041	4.5 XH P x B
6	DRILL COLLAR	6.500	2.250	31.06		RIG	4.5 XH P x B
7	18JTS HWDP	4.500	2.313	545.39		RIG	4.5 XH P x B
8	DRILLING JARS	6.550	2.625	30.94		42986J	4.5 XH P x B(SMITH)HE JARS
9	6JTS HWDP	4.500	2.313	181.59		RIG	4.5 XH P x B

DAILY COSTS

	DAILY	CUM	AFE		DAILY	CUM	AFE
8100..100: Permits & Fees			4,500	8100..105: Insurance			2,000
8100..110: Staking & Surveying			1,500	8100..120: Surface Damages & R			
8100..200: Location Roads		27,449	50,000	8100..210: Reclamation			
8100..220: Secondary Reclamati				8100..230: Pit Solidification			5,000
8100..300: Water Well				8100..310: Water/Water Disposa	473	3,889	7,500
8100..320: Mud & Chemicals	9,634	20,363	45,000	8100..325: Oil Base Mud Diesel			
8100..400: Drilling Rig	19,425	106,739	127,000	8100..402: Drilling Rig Cleani			
8100..405: Rig Fuel	9,503	21,243	40,000	8100..410: Mob/Demob		1,571	17,000
8100..420: Bits & Reamers			15,500	8100..500: Roustabout Services		500	7,000
8100..510: Testing/Inspection/		4,981	5,000	8100..520: Trucking & Hauling			10,000
8100..530: Equipment Rental	3,260	11,280	25,000	8100..531: Down Hole Motor Ren			1,500
8100..532: Solids Control Equi	425	1,275	7,000	8100..535: Directional Drillin	8,150	29,545	76,000
8100..540: Fishing				8100..600: Surface Casing/Inte		18,052	20,000
8100..605: Cementing Work		19,157	25,000	8100..610: P & A			
8100..700: Logging - Openhole			15,000	8100..705: Logging - Mud			
8100..800: Supervision/Consult	5,000	15,000	25,000	8100..810: Engineering/Evaluat			
8100..900: Contingencies	7,121	32,060		8100..950: Administrative O/H			
8100..999: Non Operated IDC				8200..510: Testing/Inspection/			2,000
8200..520: Trucking & Hauling			7,000	8200..530: Equipment Rental			37,500
8200..605: Cementing Work			25,000	8210..600: Production Casing	1,719	84,371	94,000
8210..620: Wellhead/Casing Hea	7,146	7,146	20,000	Total Cost	71,856	404,620	717,000

ULTRA RESOURCES, INC.
DAILY DRILLING REPORT DATE: 09/15/2014

WELL NAME	THREE RIVERS 4-36T-820			AFE#	140972	SPUD DATE	09/12/2014		
WELL SITE CONSULTANT	JOHN FREITAS/KING BROWN			PHONE#	713-948-9196	CONTRACTOR	Ensign 122		
TD AT REPORT	6,760'	FOOTAGE	375'	PRATE	62.5	CUM. DRLG. HRS	61.0	DRLG DAYS SINCE SPUD	3
ANTICIPATED TD	6,769'	PRESNET OPS	Circulate at 6,760'			GEOLOGIC SECT.			
DAILY MUD LOSS	SURF: 5	DH:	200	CUM. MUD LOSS	SURF: 13			DH:	550
MUD COMPANY:	ANCHOR			MUD ENGINEER:	SEAN LEHNEN				
LAST BOP TEST	09/12/2014	NEXT CASING SIZE	5 1/2	NEXT CASING DEPTH	6,745	SSE	0	SSED	0

TIME BREAKDOWN	CASING & CEMENT	5.00	COND MUD & CIRCULATE	3.00	DIRECTIONAL DRILLING	5.00
	DRILLING	1.00	TRIPPING	6.50	WIRELINE	4.50

DETAILS	Start	End	Hrs	
	06:00	11:00	05:00	DIR DRILL F/6385' T/6760'(TD) 375' @ 75 FT/HR - W/18-26K WT ON BIT - 440GPM - 63 RPM - 450 DIFF - 7-13000 K TORQUE - 2540 PSI SPP.ON BOTTOM ROP 153.21.
	11:00	12:00	01:00	CONDITION AND CIRC, CLEAN HOLE, ONE BOTTOMS UP.FLOW CHECK, NO FLOW WELL IS STATIC.
	12:00	13:00	01:00	SHORT TRIP UP TO 6188, PULLED FREE DIDN'T SEE ANY TIGHT SPOTS COMING OUT OR GOING BACK IN THE HOLE.
	13:00	14:00	01:00	CONDITION AND CIRC, CLEAN HOLE, ONE BOTTOMS UP.FLOW CHECK, NO FLOW WELL IS STATIC.
	14:00	19:30	05:30	POOH WITH NO PUMP OR ROTARY,PULLED FREE THROUGH THE CASTLE PEAK SO WE FLOW CHECKED, PUMP SLUG,POOH IT PULLED TIGHT AT 4800-4700', POOH FOR LOGS.
	19:30	00:00	04:30	FUNCTION TEST PIPE RAMS.
				RIG UP AND HOLD SAFETY MEETING W/ HALIBURTON WIRELINE CREW. RIH T/ 6758'(DRILLERS DEPTH 6760') W/LOGGING TOOLS AND LOG WELL. RIG DOWN AND PREPAIR TO RUN CASING.
	00:00	05:00	05:00	SAFETY MEETING W/ CREW AND RUN 154 JOINTS 5 1/2" PRODUCTION CASING & 2 MARKER JOINTS &MANDREL HANGER. SET @ 6744'
	01:00	02:00	01:00	SKID RIG, RIG RELEASE AT 14:00 HRS.
	05:00	06:00	01:00	CIRC AND COND WELL F/ CEMENT.WAIT ON HALLIBURTON CEMENTERS, THEY WERE GIVEN A 7 HR NOTICE. THEY EXPECT TO BE HERE ON SITE AT 08:30.
	05:55	05:55	00:00	SAFETY MEETING DAYS:TRIPPING AND LOGGING.
				SAFETY MEETING NIGHTS: PPE, RUNNING CASING AND LOGGING. LAST DAY.
				REGULATORY NOTICES: INTENT TO TEST BOP WAS GIVEN TO THE STATE.
				REGULATORY VISITS: NONE.
				INCIDENTS: NONE.
				SAFETY DRILLS: NONE.

AFE Days vs Depth:		AFE Cost Vs Depth:	
DWOP Days vs Depth:		# LL/BP Received Today:	

FUEL AND WATER USAGE	Used	Received	Transferred	On Hand	Cum.Used
Fluid					
Fuel	1,050.0			3,640.0	5,941.0
Gas					
Fresh Well Water					
Nano Water					
Frac Water					
Reserve Pit Water					
Boiler Hours					
Air Heater Hours					
Urea				0.0	
Urea Sys 1 Hrs					
Urea Sys 2 Hrs					
Urea Sys 3 Hrs					

CEMENT JOB SUMMARY	R/U HES TO FLOOR-CHECK HEAD: LOAD PLUG WITNESED BY CO-MAN. R/U HEAD & IRON.PUMP 3bbbls WTR & TEST LINES T/5,000psi. PUMP 50bbbl TUNED SPACER III. MIX & PUMP 148bbbls LEAD CMT@ 11.0ppg/YIELD OF 3.541ft3/SK/21.31gal WTR/SK(235SKS),MIX & PUMP 103bbbls TAIL CMT@ 14.0ppg/1.35ft3/SK/5.82gal/SK (430SKS). WASH UP. DROP PLUG & DISP/157.0bbbls WTR.BUMP PLUG/2173=500psi OVER FCP OF 1615psi. BLEED BACK 1.0bbbls T/TRUCK. FLOATS HELD.***RETURNS SLOWED AT 130 BBLS OF DISPLACEMENT***NO CEMENT TO SURFACE***									
--------------------	-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	--	--	--	--	--	--	--	--	--

RECENT CASINGS RUN:	Date Set	Size	Grade	Weight	Depth	FIT Depth	FIT ppg
Production	09/14/2014	5 1/2	J-55	17	6,747		
Surface	08/24/2014	8 5/8	J-55	24	1,032		
Conductor	08/19/2014	16	ARJ-55	45	119		

RECENT BITS:	BIT	SIZE	MANUF	TYPE	SERIAL NO.	JETS	TFA	DEPTH IN	DEPTH OUT	I-O-D-L-B-G-O-R
	1	7.875	HTC	T506	7152624	12/12/12/12/12	0.663	1,045	6,760	1-5-WT-S-X-X-CT-TD

BIT OPERATIONS:	BIT	WOB	RPM	GPM	PRESS	HHP	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP
	1		60/128	440	2,400	2.16	5.00	375	75.00	50.50	5,715	113.17

RECENT MUD MOTORS:	#	SIZE	MANUF	TYPE	SERIAL NO.	LOBES	DEPTH IN	DEPTH OUT	DATE IN	DATE OUT
	1	6.500	HUNTING	ARROW	6236	7/8	1,045	6,760	09/12/2014	09/14/2014

MUD MOTOR OPERATIONS:	#	WOB	REV/GAL	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP
	1	25	0.29	5.00	375	75.00	50.50	5,715	113.17

SURVEYS	Date	TMD	Incl	Azimuth	TVD	VS	NS	EW	DLS	Tool Type
	09/14/2014	6,760	1.9	182.98	6,729	406.3	-138.69	383.83	0.0	Projected Survey Station
	09/14/2014	6,708	1.9	182.98	6,677	406.0	-136.96	383.92	0.8	MWD Survey Tool
	09/14/2014	6,680	1.8	188.88	6,649	405.9	-136.06	384.01	0.8	MWD Survey Tool

MUD PROPERTIES	Type	LSND	Mud Wt	10.0	Alk.	0.0	Sand %	0.0	XS Lime lb/bbl	
	Temp.	104	Gels 10sec	2	Cl ppm	2,300	Solids %	8.0	Salt bbls	
	Visc	40	Gels 10min	8	Ca ppm	40	LGS %	4.0	LCM ppb	
	PV	13	pH	9.7	pF	0.0	Oil %	0.0	API WL cc	6.0
	YP	9	Filter Cake/32	1	Mf	0.0	Water %	90.0	HTHP WL cc	
	O/W Ratio		ES		WPS					
Comments:	ANCO BAR-151,ANCO-DD 1,CEDER FIBER-15,DRISPAK-5,GEL-6,LIGNITE-6,LIME-10,PHPA-9,SAWDUST-200,FLOWZAN-3,SOLTEX-36,WALNUT-29,MEGA CIDE-3,ECOSEAL-10,DRISPAC LOW VIS-8,TRAILER-1,ENGINEERING-1.									

Flaring:	Flare Foot-Minutes	0	Flared MCF	0.0	Cum. Flared MCF	0.0
----------	--------------------	---	------------	-----	-----------------	-----

SURFACE PUMP/BHA INFORMATION

Pump 1 Liner	<u>6.5</u>	Stroke Len	<u>9.0</u>	SPM	<u>125</u>	PSI	<u> </u>	GPM	<u>440</u>	SPR	<u>43</u>	Slow PSI	<u>350</u>	
Pump 2 Liner	<u> </u>	Stroke Len	<u> </u>	SPM	<u> </u>	PSI	<u> </u>	GPM	<u> </u>	SPR	<u>43</u>	Slow PSI	<u>383</u>	
Pump 32 Liner	<u> </u>	Stroke Len	<u> </u>	SPM	<u> </u>	PSI	<u> </u>	GPM	<u> </u>	SPR	<u> </u>	Slow PSI	<u> </u>	
BHA Makeup	STEARABLE								Length	<u>889.8</u>	Hours on BHA			<u>51</u>
Up Weight	<u>170,000</u>	Dn Weight	<u>125,000</u>	RT Weight	<u>145,000</u>	Torque			<u>15,000</u>	Hours on Motor			<u>51</u>	

BHA MAKEUP:

#	Component	OD	ID	Length	Weight (ft/lb)	Serial Number	Description
1	DRILL BIT	7.875		1.00		7152624	HUGHES T506 6X12
2	MUD MOTOR	7.000	3.250	34.92		6199	1.5 DEG FBH 7/8 6.7STG.
							.29 REV
3	NON MAG MONEL	6.500	3.250	31.53		ATM64-513	4.5 XH P x B
4	EM GAP SUB	6.400	3.250	3.80		GSB0398	4.5 XH P x B
5	NON MAG FLEX MONEL	6.500	2.813	29.61		9041	4.5 XH P x B
6	DRILL COLLAR	6.500	2.250	31.06		RIG	4.5 XH P x B
7	18JTS HWDP	4.500	2.313	545.39		RIG	4.5 XH P x B
8	DRILLING JARS	6.550	2.625	30.94		42986J	4.5 XH P x B(SMITH)HE JARS
9	6JTS HWDP	4.500	2.313	181.59		RIG	4.5 XH P x B

DAILY COSTS

	DAILY	CUM	AFE		DAILY	CUM	AFE
8100..100: Permits & Fees			4,500	8100..105: Insurance			2,000
8100..110: Staking & Surveying			1,500	8100..120: Surface Damages & R			
8100..200: Location Roads		27,449	50,000	8100..210: Reclamation			
8100..220: Secondary Reclamati				8100..230: Pit Solidification			5,000
8100..300: Water Well				8100..310: Water/Water Disposa	472	4,361	7,500
8100..320: Mud & Chemicals	13,661	34,024	45,000	8100..325: Oil Base Mud Diesel			
8100..400: Drilling Rig	19,425	126,164	127,000	8100..402: Drilling Rig Cleani			
8100..405: Rig Fuel		21,243	40,000	8100..410: Mob/Demob		1,571	17,000
8100..420: Bits & Reamers			15,500	8100..500: Roustabout Services		500	7,000
8100..510: Testing/Inspection/		4,981	5,000	8100..520: Trucking & Hauling			10,000
8100..530: Equipment Rental	3,260	14,540	25,000	8100..531: Down Hole Motor Ren			1,500
8100..532: Solids Control Equi	425	1,700	7,000	8100..535: Directional Drillin	8,150	37,695	76,000
8100..540: Fishing				8100..600: Surface Casing/Inte		18,052	20,000
8100..605: Cementing Work		19,157	25,000	8100..610: P & A			
8100..700: Logging - Openhole	12,693	12,693	15,000	8100..705: Logging - Mud			
8100..800: Supervision/Consult	5,000	20,000	25,000	8100..810: Engineering/Evaluat			
8100..900: Contingencies	6,940	39,000		8100..950: Administrative O/H			
8100..999: Non Operated IDC				8200..510: Testing/Inspection/			2,000
8200..520: Trucking & Hauling			7,000	8200..530: Equipment Rental			37,500
8200..605: Cementing Work			25,000	8210..600: Production Casing		84,371	94,000
8210..620: Wellhead/Casing Hea		7,146	20,000	Total Cost	70,026	474,646	717,000

ULTRA RESOURCES, INC.
DAILY DRILLING REPORT DATE: 09/16/2014

WELL NAME	THREE RIVERS 4-36T-820			AFE#	140972	SPUD DATE	09/12/2014		
WELL SITE CONSULTANT	JOHN FREITAS/KING BROWN			PHONE#	713-948-9196	CONTRACTOR	Ensign 122		
TD AT REPORT	6,760'	FOOTAGE	0'	PRATE		CUM. DRLG. HRS	61.0	DRLG DAYS SINCE SPUD	3
ANTICIPATED TD	6,769'	PRESSENT OPS	Move rig on location at 6,760'			GEOLOGIC SECT.			
DAILY MUD LOSS	SURF: 5	DH:	200	CUM. MUD LOSS		SURF: 18	DH:	750	
MUD COMPANY:	ANCHOR			MUD ENGINEER:	SEAN LEHNEN				
LAST BOP TEST	09/12/2014	NEXT CASING SIZE	5 1/2	NEXT CASING DEPTH	6,746	SSE	0	SSED	0

TIME BREAKDOWN									
	CASING & CEMENT	6.00		RIG MOVE	1.00		RIG UP / TEAR DOWN	1.00	

DETAILS				
Start	End	Hrs		
06:00	09:30	03:30	WAIT ON HALLIBURTON CEMENTERS. WE HAD ONE TRUCK ON LOCATION AT 06:00,ONE MORE TRUCKS ARRIVED AT 06:30, THE RST OF THE TRUCKS ARRIVED AT 08:20, THEY STARTED PUTTING TOGETHER ALL THIER EQUIPMENT.	
09:30	12:00	02:30	R/U HES TO FLOOR-CHECK HEAD: LOAD PLUG WITNESED BY CO-MAN. R/U HEAD & IRON.PUMP 3bbls WTR & TEST LINES T/5,000psi. PUMP 50bbl TUNED SPACER III. MIX & PUMP 148bbls LEAD CMT@11.0ppg/YIELD OF 3.541ft3/SK/21.31gal WTR/SK(235SKS),MIX & PUMP 103bbls TAIL CMT@14.0ppg/1.35ft3/SK/5.82gal/SK (430SKS). WASH UP. DROP PLUG & DISP/157.0bbls WTR.BUMP PLUG/2173=500psi OVER FCP OF 1615psi. BLED BACK 1.0bbls T/TRUCK. FLOATS HELD.***RETURNS SLOWED AT 130 BBLS OF DISPLACEMENT***NO CEMENT TO SURFACE***	
12:00	13:00	01:00	RIG DOWN TO SKID THE RIG.	
13:00	14:00	01:00	SKID RIG, RIG RELEASE AT 14:00 HRS.	

AFE Days vs Depth:		AFE Cost Vs Depth:	
DWOP Days vs Depth:		# LL/BP Received Today:	

FUEL AND WATER USAGE									
Fluid		Used	Received	Transferred	On Hand	Cum.Used			
Fuel		500.0		3,140.0	0.0	6,441.0			
Gas									
Fresh Well Water									
Nano Water									
Frac Water									
Reserve Pit Water									
Boiler Hours									
Air Heater Hours									
Urea					0.0				
Urea Sys 1 Hrs									
Urea Sys 2 Hrs									
Urea Sys 3 Hrs									

RECENT CASINGS RUN:	Date Set	Size	Grade	Weight	Depth	FIT Depth	FIT ppg		
Production	09/14/2014	5 1/2	J-55	17	6,747				
Surface	08/24/2014	8 5/8	J-55	24	1,032				
Conductor	08/19/2014	16	ARJ-55	45	119				

RECENT BITS:											
BIT	SIZE	MANUF	TYPE	SERIAL NO.	JETS	TFA	DEPTH IN	DEPTH OUT	I-O-D-L-B-G-O-R		
1	7.875	HTC	T506	7152624	12/12/12/12/12/12	0.663	1,045	6,760	1-5-WT-S-X-X-CT-TD		

BIT OPERATIONS:											
BIT	WOB	RPM	GPM	PRESS	HHP	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP
1		60/128	440	2,400	2.16	5.00	375	75.00	50.50	5,715	113.17

RECENT MUD MOTORS:											
#	SIZE	MANUF	TYPE	SERIAL NO.	LOBES	DEPTH IN	DEPTH OUT	DATE IN	DATE OUT		
1	6.500	HUNTING	ARROW	6236	7/8	1,045	6,760	09/12/2014	09/14/2014		

MUD MOTOR OPERATIONS:										
#	WOB	REV/GAL	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP		
1	25	0.29	5.00	375	75.00	50.50	5,715	113.17		

SURVEYS											
Date	TMD	Incl	Azimuth	TVD	VS	NS	EW	DLS	Tool Type		
09/14/2014	6,760	1.9	182.98	6,729	406.3	-138.69	383.83	0.0	Projected Survey Station		
09/14/2014	6,708	1.9	182.98	6,677	406.0	-136.96	383.92	0.8	MWD Survey Tool		
09/14/2014	6,680	1.8	188.88	6,649	405.9	-136.06	384.01	0.8	MWD Survey Tool		

MUD PROPERTIES											
Type	LSND	Mud Wt	10.0	Alk.	0.0	Sand %	0.0	XS Lime lb/bbl			
Temp.	104	Gels 10sec	2	Cl ppm	2,300	Solids %	8.0	Salt bbls			
Visc	40	Gels 10min	8	Ca ppm	40	LGS %	4.0	LCM ppb			
PV	13	pH	9.7	pF	0.0	Oil %	0.0	API WL cc	6.0		
YP	9	Filter Cake/32	1	Mf	0.0	Water %	90.0	HTHP WL cc			
O/W Ratio		ES		WPS							
Comments:	ANCO BAR-151,ANCO-DD 1,CEDER FIBER-15,DRISPAK-5,GEL-6,LIGNITE-6,LIME-10,PHPA-9,SAWDUST-200,FLOWZAN-3,SOLTEX-36,WALNUT-29,MEGA CIDE-3,ECOSEAL-10,DRISPAC LOW VIS-8,TRAILER-1,ENGINEERING-1.										

Flaring:	Flare Foot-Minutes	0	Flared MCF	0.0	Cum. Flared MCF	0.0
----------	--------------------	---	------------	-----	-----------------	-----

SURFACE PUMP/BHA INFORMATION													
Pump 1 Liner	<u>6.5</u>	Stroke Len	<u>9.0</u>	SPM	<u>125</u>	PSI	<u> </u>	GPM	<u>440</u>	SPR	<u>43</u>	Slow PSI	<u>350</u>
Pump 2 Liner	<u> </u>	Stroke Len	<u> </u>	SPM	<u> </u>	PSI	<u> </u>	GPM	<u> </u>	SPR	<u>43</u>	Slow PSI	<u>383</u>
Pump 32 Liner	<u> </u>	Stroke Len	<u> </u>	SPM	<u> </u>	PSI	<u> </u>	GPM	<u> </u>	SPR	<u> </u>	Slow PSI	<u> </u>
BHA Makeup	STEARABLE												
Up Weight	170.000	Dn Weight	125.000	RT Weight	145.000			Length	889.8			Hours on BHA	51
								Torque	15.000			Hours on Motor	51

BHA MAKEUP:

#	Component	OD	ID	Length	Weight (ft/lb)	Serial Number	Description
1	DRILL BIT	7.875		1.00		7152624	HUGHES T506 6X12
2	MUD MOTOR	7.000	3.250	34.92		6199	1.5 DEG FBH 7/8 6.7STG. .29 REV
3	NON MAG MONEL	6.500	3.250	31.53		ATM64-513	4.5 XH P x B
4	EM GAP SUB	6.400	3.250	3.80		GSB0398	4.5 XH P x B
5	NON MAG FLEX MONEL	6.500	2.813	29.61		9041	4.5 XH P x B
6	DRILL COLLAR	6.500	2.250	31.06		RIG	4.5 XH P x B
7	18JTS HWDP	4.500	2.313	545.39		RIG	4.5 XH P x B
8	DRILLING JARS	6.550	2.625	30.94		42986J	4.5 XH P x B(SMITH)HE JARS
9	6JTS HWDP	4.500	2.313	181.59		RIG	4.5 XH P x B

DAILY COSTS	DAILY	CUM	AFE		DAILY	CUM	AFE
8100..100: Permits & Fees			4,500	8100..105: Insurance			2,000
8100..110: Staking & Surveying			1,500	8100..120: Surface Damages & R			
8100..200: Location Roads		27,449	50,000	8100..210: Reclamation			
8100..220: Secondary Reclamati				8100..230: Pit Solidification			5,000
8100..300: Water Well				8100..310: Water/Water Disposa		4,361	7,500
8100..320: Mud & Chemicals	1,143	35,167	45,000	8100..325: Oil Base Mud Diesel			
8100..400: Drilling Rig	6,475	132,639	127,000	8100..402: Drilling Rig Cleani			
8100..405: Rig Fuel		21,243	40,000	8100..410: Mob/Demob		1,571	17,000
8100..420: Bits & Reamers	14,288	14,288	15,500	8100..500: Roustabout Services		500	7,000
8100..510: Testing/Inspection/	542	5,523	5,000	8100..520: Trucking & Hauling	2,640	2,640	10,000
8100..530: Equipment Rental	1,090	15,630	25,000	8100..531: Down Hole Motor Ren			1,500
8100..532: Solids Control Equi	142	1,842	7,000	8100..535: Directional Drillin		37,695	76,000
8100..540: Fishing				8100..600: Surface Casing/Inte	3,957	22,009	20,000
8100..605: Cementing Work		19,157	25,000	8100..610: P & A			
8100..700: Logging - Openhole		12,693	15,000	8100..705: Logging - Mud			
8100..800: Supervision/Consult	1,667	21,667	25,000	8100..810: Engineering/Evaluat			
8100..900: Contingencies	7,529	46,529		8100..950: Administrative O/H			
8100..999: Non Operated IDC				8200..510: Testing/Inspection/			2,000
8200..520: Trucking & Hauling			7,000	8200..530: Equipment Rental			37,500
8200..605: Cementing Work	43,632	43,632	25,000	8210..600: Production Casing		84,371	94,000
8210..620: Wellhead/Casing Hea		7,146	20,000	Total Cost	83,105	557,751	717,000

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: FEE
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: ULTRA RESOURCES INC		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: 304 Inverness Way South #295, Englewood, CO, 80112		8. WELL NAME and NUMBER: Three Rivers 4-36T-820
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1529 FSL 2373 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWSE Section: 04 Township: 08.0S Range: 20.0E Meridian: S		9. API NUMBER: 43047544200000
PHONE NUMBER: 303 645-9809 Ext		9. FIELD and POOL or WILDCAT: THREE RIVERS
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 10/11/2014	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> CONVERT WELL TYPE	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PLUG BACK	
	<input checked="" type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. First Production occurred on the TR4-36T-820 on 10/11/2014.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY October 17, 2014		
NAME (PLEASE PRINT) Jenna Anderson	PHONE NUMBER 303 645-9804	TITLE Permitting Assistant
SIGNATURE N/A	DATE 10/13/2014	

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

AMENDED REPORT ☐ FORM 8
(highlight changes)

5. LEASE DESIGNATION AND SERIAL NUMBER:
UT001

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. TYPE OF WELL: OIL WELL ☒ GAS WELL ☐ DRY ☐ OTHER _____

b. TYPE OF WORK: NEW WELL ☒ HORIZ. LATS. ☐ DEEP-EN ☐ RE-ENTRY ☐ DIFF. RESVR. ☐ OTHER _____

2. NAME OF OPERATOR:
Ultra Resources, Inc.

3. ADDRESS OF OPERATOR:
304 Inverness Way So. CITY Englewood STATE CO ZIP 80112 PHONE NUMBER: **(303) 645-9804**

4. LOCATION OF WELL (FOOTAGES)
AT SURFACE: **1530 FSL 2373 FEL 40.148581 109.672611**
AT TOP PRODUCING INTERVAL REPORTED BELOW: **1446 FSL 1997 FEL 40.148363 109.671260**
AT TOTAL DEPTH: **1387 FSL 1991 FEL 40.1482 109.671238**

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT or CA AGREEMENT NAME

8. WELL NAME and NUMBER:
THREE RIVERS 4-36T-820

9. API NUMBER:
4304754420

10 FIELD AND POOL, OR WILDCAT
THREE RIVERS

11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:
NWSE 4 8S 20E S

12. COUNTY
Uintah

13. STATE
UTAH

14. DATE SPURRED:
8/19/2014

15. DATE T.D. REACHED:
9/14/2014

16. DATE COMPLETED:
10/11/2014

ABANDONED ☐

READY TO PRODUCE ☒

17. ELEVATIONS (DF, RKB, RT, GL):
GL 4752.4

18. TOTAL DEPTH: MD **6,760**
TVD **6,729**

19. PLUG BACK T.D.: MD **6,744**
TVD **6,713**

20. IF MULTIPLE COMPLETIONS, HOW MANY? *

21. DEPTH BRIDGE MD
PLUG SET: TVD

22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each)

Triple Combo, CBL

23. WAS WELL CORED? NO ☒ YES ☐

(Submit analysis)

WAS DST RUN? NO ☒ YES ☐

(Submit report)

DIRECTIONAL SURVEY? NO ☐ YES ☒

(Submit copy)

24. CASING AND LINER RECORD (Report all strings set in well)

HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED
24	16 arj55	45	0	119				0	
12 1/4	8 5/8 J-55	24	0	1,032		675		0	
7 7/8	5 1/2 J-55	17	0	6,747		665		200	

25. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
2 7/8	4,910							

26. PRODUCING INTERVALS

FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)
(A) Lower GR	4,900	6,635		
(B)				
(C)				
(D)				

27. PERFORATION RECORD

INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS
4,900 6,635		264	Open <input checked="" type="checkbox"/> Squeezed <input type="checkbox"/>
			Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
			Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
			Open <input type="checkbox"/> Squeezed <input type="checkbox"/>

28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.

WAS WELL HYDRAULICALLY FRACTURED? YES ☒ NO ☐ IF YES - DATE FRACTURED: **10/6/2014**

DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL
4900 to 6635	Fracture/ Stimulate 7 Stages

29. ENCLOSED ATTACHMENTS:

☒ ELECTRICAL/MECHANICAL LOGS

☐ SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION

☐ GEOLOGIC REPORT

☐ CORE ANALYSIS

☐ DST REPORT

☒ OTHER: _____

☒ DIRECTIONAL SURVEY

30. WELL STATUS:

POW

31. INITIAL PRODUCTION

INTERVAL A (As shown in Item #26)

DATE FIRST PRODUCED: 10/11/2014	TEST DATE: 10/22/2014	HOURS TESTED: 24	TEST PRODUCTION RATES: →	OIL – BBL: 207	GAS – MCF: 100	WATER – BBL: 144	PROD. METHOD: Gas Pumping
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS:

INTERVAL B (As shown in Item #26)

DATE FIRST PRODUCED:	TEST DATE:	HOURS TESTED:	TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS:

INTERVAL C (As shown in Item #26)

DATE FIRST PRODUCED:	TEST DATE:	HOURS TESTED:	TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS:

INTERVAL D (As shown in Item #26)

DATE FIRST PRODUCED:	TEST DATE:	HOURS TESTED:	TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS:

32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)

Used on lease

33. SUMMARY OF POROUS ZONES (Include Aquifers):

Show all important zones of porosity and contents thereof. Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

34. FORMATION (Log) MARKERS:

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)
				Upper Green River	2,780
				Mahogany	4,124
				Lower Green River	4,883
				Wasatch	6,648

35. ADDITIONAL REMARKS (Include plugging procedure)

Frac material used: 7000 gal HCl Acid, 971413 gal FR-66 Water, 235677 gal DeltaFrac Fluid, 969177 lbs White Sand

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

NAME (PLEASE PRINT) Jenna Anderson

TITLE Permitting Specialist

SIGNATURE 

DATE 11/6/2014

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

** ITEM 24: Cement Top – Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
Box 145801
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

☐ Proposed
☒ As Is

THREE RIVERS 4-36T-820 **GL: 4,752.4, KB: 4,764.9**
Sec 4, 8S, 20E **Uintah County, Utah**


	Size	Weight	Grade	Depth	Sks/Cmt
Conductor	16	45	ARJ-55	119	
Surface	8 5/8	24	J-55	1032	675
Production	5 1/2	17	J-55	6747	665
Cement Top				200	

STAGE	ZONE 1	ZONE 2	ZONE 3	ZONE 4	ZONE 5	ZONE 6	ZONE 7
1	6633-6635	6624-6625	6580-6581	6569-6570	6556-6557	6549-6550	6533-6534
2	6439-6441	6429-6430	6421-6422	6411-6412	6404-6405	6392-6393	6382-6383
3	6330-6331	6317-6318	6298-6299	6284-6285	6265-6266	6252-6253	6218-6219
4	6084-6085	6059-6060	6048-6049	6040-6041	6007-6008	5990-5991	5978-5979
5	5831-5833	5816-5817	5775-5776	5751-5752	5733-5734	5713-5714	5693-5694
6	5360-5362	5352-5353	5346-5347	5339-5340	5269-5270	5221-5222	5202-5203
7	5042-5043	5033-5034	5022-5023	5013-5014	4989-4990	4982-4983	4970-4971

Stage	Date	Av. Rate	Av. Press	Proppant	Clean Fluid	Tracer	Screenout
1	10/06/2014	49.0	2,272	108,195	3,573		N
2	10/06/2014	50.0	2,766	112,920	3,723		N
3	10/06/2014	50.0	2,498	171,147	5,289		N
4	10/06/2014	49.0	2,987	170,184	4,602		N
5	10/06/2014	47.0	2,987	186,252	4,967		N
6	10/06/2014	43.0	2,827	98,775	2,763		N
7	10/07/2014	44.0	2,122	121,704	3,989		N
Totals:				969,177	28,906		

Actual Formation or Depth	Top	Sand Type	Amount
		Gross Sand Drilled	
		Gross Sand Logged	
		Net Sand	
		Net Pay	

Move In	Spud Date	TD Date	Rig Release	1st Prod	Full Sales
08/24/2014	09/12/2014	09/14/2014	09/15/2014	10/11/2014	





ULTRA RESOURCES, INC

Location: Three Rivers Slot: Three Rivers 4-36T-820 (1530' FSL & 2373' FEL)

Field: UINTAH COUNTY Well: Three Rivers 4-36T-820

Facility: Sec.04-T8S-R20E Wellbore: Three Rivers 4-36T-820 PWB

Plot reference wellpath is Three Rivers 4-36T-820 PWP

True vertical depths are referenced to Rig on Three Rivers 4-36T-820 (1529' FSL & 2373' FWL) (RT)

Grid System: NAD83 / Lambert Utah SP, Central Zone (4302), US feet

Measured depths are referenced to Rig on Three Rivers 4-36T-820 (1529' FSL & 2373' FWL) (RT)

North Reference: True north

Rig on Three Rivers 4-36T-820 (1529' FSL & 2373' FWL) (RT) to Mean Sea Level: 4765.4 feet



Scale: True distance

Mean Sea Level to Mud line (At Slot: Three Rivers 4-36T-820 (1530' FSL & 2373' FEL)): 0 feet

Depths are in feet

Coordinates are in feet referenced to Slot

Created by: welliams on 11/4/2014





Actual Wellpath Report

Three Rivers 4-36T-820 AWP

Page 1 of 5



REFERENCE WELLPATH IDENTIFICATION

Operator	ULTRA RESOURCES, INC	Slot	Three Rivers 4-36T-820 (1530' FSL & 2373' FEL)
Area	Three Rivers	Well	Three Rivers 4-36T-820
Field	UINTAH COUNTY	Wellbore	Three Rivers 4-36T-820 AWB
Facility	Sec.04-T8S-R20E		

REPORT SETUP INFORMATION

Projection System	NAD83 / Lambert Utah SP, Central Zone (4302), US feet	Software System	WellArchitect® 3.0.0
North Reference	True	User	EWilliams
Scale	0.999914	Report Generated	11/4/2014 at 2:15:22 PM
Convergence at slot	1.17° East	Database/Source file	WellArchitectDB/Three_Rivers_4-36T-820_AWB.xml

WELLPATH LOCATION

	Local coordinates		Grid coordinates		Geographic coordinates	
	North[ft]	East[ft]	Easting[US ft]	Northing[US ft]	Latitude	Longitude
Slot Location	-2552.02	-1987.95	2151192.49	7228063.11	40°08'54.890"N	109°40'21.400"W
Facility Reference Pt			2153127.51	7230655.14	40°09'20.110"N	109°39'55.800"W
Field Reference Pt			2156630.96	7236613.42	40°10'18.270"N	109°39'09.100"W

WELLPATH DATUM

Calculation method	Minimum curvature	Rig on Three Rivers 4-36T-820 (1529' FSL & 2373' FWL) (RT) to Facility Vertical Datum
Horizontal Reference Pt	Slot	Rig on Three Rivers 4-36T-820 (1529' FSL & 2373' FWL) (RT) to Mean Sea Level
Vertical Reference Pt	Rig on Three Rivers 4-36T-820 (1529' FSL & 2373' FWL) (RT)	Rig on Three Rivers 4-36T-820 (1529' FSL & 2373' FWL) (RT) to Mud Line at Slot (Three Rivers 4-36T-820 (1530' FSL & 2373' FEL))
MD Reference Pt	Rig on Three Rivers 4-36T-820 (1529' FSL & 2373' FWL) (RT)	Section Origin
Field Vertical Reference	Mean Sea Level	Section Azimuth



Actual Wellpath Report

Three Rivers 4-36T-820 AWP

Page 2 of 5



REFERENCE WELLPATH IDENTIFICATION

Operator	ULTRA RESOURCES, INC	Slot	Three Rivers 4-36T-820 (1530' FSL & 2373' FEL)
Area	Three Rivers	Well	Three Rivers 4-36T-820
Field	UINTAH COUNTY	Wellbore	Three Rivers 4-36T-820 AWB
Facility	Sec.04-T8S-R20E		

WELLPATH DATA (74 stations) † = interpolated/extrapolated station

MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Vert Sect [ft]	North [ft]	East [ft]	Latitude	Longitude	DLS [°/100ft]	Comments
0.00†	0.000	25.650	0.00	0.00	0.00	0.00	40°08'54.890"N	109°40'21.400"W	0.00	
13.00	0.000	25.650	13.00	0.00	0.00	0.00	40°08'54.890"N	109°40'21.400"W	0.00	
119.00	0.000	0.000	119.00	0.00	0.00	0.00	40°08'54.890"N	109°40'21.400"W	0.00	
1032.00	0.000	0.000	1032.00	0.00	0.00	0.00	40°08'54.890"N	109°40'21.400"W	0.00	
1064.00	0.310	25.650	1064.00	0.02	0.08	0.04	40°08'54.891"N	109°40'21.400"W	0.97	
1154.00	0.310	70.650	1154.00	0.27	0.38	0.37	40°08'54.894"N	109°40'21.395"W	0.26	
1245.00	0.310	75.140	1245.00	0.68	0.52	0.84	40°08'54.895"N	109°40'21.389"W	0.03	
1336.00	0.310	51.960	1336.00	1.05	0.74	1.27	40°08'54.897"N	109°40'21.384"W	0.14	
1426.00	0.400	60.860	1425.99	1.42	1.04	1.74	40°08'54.900"N	109°40'21.378"W	0.12	
1517.00	0.400	49.760	1516.99	1.84	1.40	2.26	40°08'54.904"N	109°40'21.371"W	0.09	
1607.00	0.400	73.250	1606.99	2.29	1.69	2.80	40°08'54.907"N	109°40'21.364"W	0.18	
1698.00	0.400	94.580	1697.99	2.87	1.76	3.42	40°08'54.907"N	109°40'21.356"W	0.16	
1789.00	0.490	98.280	1788.99	3.57	1.68	4.12	40°08'54.907"N	109°40'21.347"W	0.10	
1879.00	0.490	123.260	1878.98	4.32	1.41	4.83	40°08'54.904"N	109°40'21.338"W	0.24	
1970.00	2.210	90.570	1969.95	6.39	1.18	6.91	40°08'54.902"N	109°40'21.311"W	2.00	
2060.00	3.800	91.670	2059.83	10.98	1.08	11.62	40°08'54.901"N	109°40'21.250"W	1.77	
2151.00	6.010	87.880	2150.49	18.49	1.17	19.40	40°08'54.902"N	109°40'21.150"W	2.45	
2241.00	8.310	84.260	2239.78	29.11	1.99	30.58	40°08'54.910"N	109°40'21.006"W	2.60	
2332.00	9.990	85.670	2329.62	42.75	3.24	44.99	40°08'54.922"N	109°40'20.821"W	1.86	
2422.00	9.280	85.850	2418.35	57.01	4.36	60.02	40°08'54.933"N	109°40'20.627"W	0.79	
2513.00	9.720	86.860	2508.10	71.28	5.31	75.01	40°08'54.942"N	109°40'20.434"W	0.52	
2604.00	9.400	89.550	2597.84	85.78	5.79	90.11	40°08'54.947"N	109°40'20.240"W	0.60	
2694.00	8.710	88.270	2686.72	99.43	6.05	104.27	40°08'54.950"N	109°40'20.057"W	0.80	
2780.00†	8.132	92.882	2771.79	111.64	5.94	116.85	40°08'54.949"N	109°40'19.895"W	1.03	Top Green River
2785.00	8.100	93.170	2776.74	112.33	5.91	117.56	40°08'54.948"N	109°40'19.886"W	1.03	
2875.00	8.700	94.270	2865.77	125.24	5.05	130.68	40°08'54.940"N	109°40'19.717"W	0.69	
2966.00	9.010	101.050	2955.69	139.13	3.17	144.53	40°08'54.921"N	109°40'19.539"W	1.20	
3057.00	9.990	101.360	3045.44	154.12	0.25	159.26	40°08'54.892"N	109°40'19.349"W	1.08	
3147.00	11.180	102.950	3133.91	170.64	-3.24	175.42	40°08'54.858"N	109°40'19.141"W	1.36	
3238.00	11.400	103.100	3223.15	188.45	-7.26	192.78	40°08'54.818"N	109°40'18.917"W	0.24	
3328.00	11.090	106.740	3311.42	205.99	-11.77	209.73	40°08'54.774"N	109°40'18.699"W	0.86	
3419.00	10.210	103.260	3400.85	222.80	-16.14	225.96	40°08'54.731"N	109°40'18.490"W	1.20	
3509.00	11.300	109.250	3489.28	239.56	-20.87	242.05	40°08'54.684"N	109°40'18.283"W	1.73	
3600.00	11.000	109.000	3578.56	257.10	-26.64	258.68	40°08'54.627"N	109°40'18.069"W	0.33	
3691.00	9.500	107.400	3668.10	273.26	-31.71	274.05	40°08'54.577"N	109°40'17.871"W	1.68	
3781.00	8.800	108.150	3756.96	287.55	-36.08	287.68	40°08'54.533"N	109°40'17.695"W	0.79	
3872.00	9.410	109.250	3846.81	301.91	-40.70	301.32	40°08'54.488"N	109°40'17.520"W	0.70	
3962.00	8.710	113.570	3935.69	315.97	-45.85	314.51	40°08'54.437"N	109°40'17.350"W	1.08	
4053.00	8.480	116.740	4025.67	329.33	-51.62	326.82	40°08'54.380"N	109°40'17.191"W	0.58	
4124.00†	8.172	115.264	4095.92	339.41	-56.13	336.06	40°08'54.335"N	109°40'17.072"W	0.53	Mahogany
4143.00	8.090	114.850	4114.73	342.05	-57.27	338.49	40°08'54.324"N	109°40'17.041"W	0.53	
4234.00	5.610	114.050	4205.07	352.74	-61.78	348.37	40°08'54.279"N	109°40'16.914"W	2.73	
4325.00	4.200	113.970	4295.73	360.41	-64.94	355.48	40°08'54.248"N	109°40'16.822"W	1.55	
4415.00	3.800	107.270	4385.52	366.64	-67.17	361.33	40°08'54.226"N	109°40'16.747"W	0.68	
4506.00	3.400	110.750	4476.34	372.33	-69.02	366.74	40°08'54.208"N	109°40'16.677"W	0.50	



Actual Wellpath Report

Three Rivers 4-36T-820 AWP

Page 3 of 5



REFERENCE WELLPATH IDENTIFICATION

Operator	ULTRA RESOURCES, INC	Slot	Three Rivers 4-36T-820 (1530' FSL & 2373' FEL)
Area	Three Rivers	Well	Three Rivers 4-36T-820
Field	UINTAH COUNTY	Wellbore	Three Rivers 4-36T-820 AWB
Facility	Sec.04-T8S-R20E		

WELLPATH DATA (74 stations) † = interpolated/extrapolated station

MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Vert Sect [ft]	North [ft]	East [ft]	Latitude	Longitude	DLS [°/100ft]	Comments
4596.00	2.610	116.740	4566.21	376.99	-70.89	371.06	40°08'54.189"N	109°40'16.622"W	0.94	
4687.00	2.210	133.360	4657.13	380.55	-73.02	374.19	40°08'54.168"N	109°40'16.581"W	0.88	
4778.00	1.990	147.280	4748.07	383.25	-75.56	376.32	40°08'54.143"N	109°40'16.554"W	0.61	
4868.00	1.810	166.760	4838.02	385.06	-78.26	377.49	40°08'54.117"N	109°40'16.539"W	0.74	
4883.00†	1.805	168.648	4853.02	385.27	-78.72	377.59	40°08'54.112"N	109°40'16.538"W	0.40	Lower Green River
4900.00†	1.802	170.799	4870.01	385.49	-79.24	377.69	40°08'54.107"N	109°40'16.536"W	0.40	Top of Production
4959.00	1.810	178.260	4928.98	386.13	-81.09	377.86	40°08'54.089"N	109°40'16.534"W	0.40	
5049.00	1.990	182.580	5018.93	386.85	-84.07	377.83	40°08'54.059"N	109°40'16.534"W	0.26	
5140.00	1.990	184.870	5109.87	387.44	-87.23	377.63	40°08'54.028"N	109°40'16.537"W	0.09	
5230.00	2.500	184.170	5199.80	388.05	-90.74	377.35	40°08'53.993"N	109°40'16.541"W	0.57	
5321.00	2.200	184.560	5290.73	388.71	-94.46	377.07	40°08'53.957"N	109°40'16.544"W	0.33	
5412.00	1.680	188.440	5381.68	389.15	-97.52	376.74	40°08'53.926"N	109°40'16.549"W	0.59	
5502.00	1.590	188.970	5471.64	389.41	-100.06	376.35	40°08'53.901"N	109°40'16.554"W	0.10	
5593.00	1.900	108.860	5562.61	391.04	-101.79	377.58	40°08'53.884"N	109°40'16.538"W	2.48	
5683.00	1.810	179.760	5652.57	392.89	-103.70	379.00	40°08'53.865"N	109°40'16.519"W	2.39	
5774.00	1.900	183.150	5743.52	393.55	-106.64	378.92	40°08'53.836"N	109°40'16.520"W	0.16	
5864.00	1.990	186.060	5833.47	394.08	-109.69	378.67	40°08'53.806"N	109°40'16.524"W	0.15	
5955.00	1.990	180.550	5924.42	394.69	-112.84	378.49	40°08'53.775"N	109°40'16.526"W	0.21	
6046.00	1.990	177.640	6015.36	395.53	-115.99	378.54	40°08'53.744"N	109°40'16.525"W	0.11	
6136.00	1.900	169.270	6105.31	396.62	-119.02	378.88	40°08'53.714"N	109°40'16.521"W	0.33	
6227.00	1.900	164.560	6196.26	398.01	-121.96	379.57	40°08'53.685"N	109°40'16.512"W	0.17	
6317.00	1.990	150.850	6286.21	399.84	-124.76	380.72	40°08'53.657"N	109°40'16.497"W	0.53	
6408.00	1.990	155.870	6377.15	401.91	-127.58	382.14	40°08'53.629"N	109°40'16.479"W	0.19	
6499.00	1.990	165.480	6468.10	403.67	-130.55	383.18	40°08'53.600"N	109°40'16.466"W	0.37	
6589.00	1.680	165.480	6558.05	405.07	-133.34	383.90	40°08'53.572"N	109°40'16.456"W	0.34	
6648.00†	1.732	181.093	6617.03	405.69	-135.07	384.10	40°08'53.555"N	109°40'16.454"W	0.79	Wasatch
6680.00	1.810	188.880	6649.01	405.85	-136.06	384.02	40°08'53.545"N	109°40'16.455"W	0.79	
6708.00	1.900	182.980	6677.00	405.99	-136.96	383.92	40°08'53.537"N	109°40'16.456"W	0.75	End of Surveys
6760.00	1.900	182.980	6728.97	406.34	-138.68	383.83	40°08'53.520"N	109°40'16.457"W	0.00	TD



Actual Wellpath Report

Three Rivers 4-36T-820 AWP

Page 4 of 5



REFERENCE WELLPATH IDENTIFICATION

Operator	ULTRA RESOURCES, INC	Slot	Three Rivers 4-36T-820 (1530' FSL & 2373' FEL)
Area	Three Rivers	Well	Three Rivers 4-36T-820
Field	UINTAH COUNTY	Wellbore	Three Rivers 4-36T-820 AWB
Facility	Sec.04-T8S-R20E		

TARGETS

Name	MD [ft]	TVD [ft]	North [ft]	East [ft]	Grid East [US ft]	Grid North [US ft]	Latitude	Longitude	Shape
Three Rivers 4-36T-820 1344' FSL & 1980' FEL		4690.00	-182.14	394.49	2151590.58	7227889.08	40°08'53.090"N	109°40'16.320"W	point
Three Rivers 4-36T-820 Driller's Target Radius: 5' 1374' FSL & 1980' FEL		4690.00	-104.14	402.49	2151596.99	7227967.22	40°08'53.861"N	109°40'16.217"W	circle
Three Rivers 4-36T-820 Geo Target Radius: 50' 1374' FSL & 1980' FEL		4690.00	-152.14	394.49	2151589.97	7227919.07	40°08'53.386"N	109°40'16.320"W	circle
Hardline: 50' South of Center of Geo Target		4860.00	-152.14	394.49	2151589.97	7227919.07	40°08'53.387"N	109°40'16.320"W	point

WELLPATH COMPOSITION - Ref Wellbore: Three Rivers 4-36T-820 AWB Ref Wellpath: Three Rivers 4-36T-820 AWP

Start MD [ft]	End MD [ft]	Positional Uncertainty Model	Log Name/Comment	Wellbore
13.00	119.00	Unknown Tool (Standard)	Conductor	Three Rivers 4-36T-820 AWB
119.00	1032.00	Unknown Tool (Standard)	Surface	Three Rivers 4-36T-820 AWB
1032.00	6708.00	MTC (Collar, post-2000) (Standard)	MWD	Three Rivers 4-36T-820 AWB
6708.00	6760.00	Blind Drilling (std)	Projection to bit	Three Rivers 4-36T-820 AWB



Actual Wellpath Report

Three Rivers 4-36T-820 AWP

Page 5 of 5



REFERENCE WELLPATH IDENTIFICATION

Operator	ULTRA RESOURCES, INC	Slot	Three Rivers 4-36T-820 (1530' FSL & 2373' FEL)
Area	Three Rivers	Well	Three Rivers 4-36T-820
Field	UINTAH COUNTY	Wellbore	Three Rivers 4-36T-820 AWB
Facility	Sec.04-T8S-R20E		

WELLPATH COMMENTS

MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Comment
2780.00	8.132	92.882	2771.79	Top Green River
4124.00	8.172	115.264	4095.92	Mahogany
4883.00	1.805	168.648	4853.02	Lower Green River
4900.00	1.802	170.799	4870.01	Top of Production
6648.00	1.732	181.093	6617.03	Wasatch
6708.00	1.900	182.980	6677.00	End of Surveys
6760.00	1.900	182.980	6728.97	TD

ULTRA RESOURCES, INC.
DAILY COMPLETION REPORT FOR 09/29/2014 TO 10/16/2014

Well Name	THREE RIVERS 4-36T-820	Frac Planned	7
Location:	UINTAH County, UTAH(NWSE 4 8S 20E)	AFE#	140972
Total Depth Date:	09/14/2014 TD 6,760	Formation:	(Missing)
Production Casing:	Size 5 1/2 Wt 17 Grade J-55 Set At 6,747	GL:	KB: 4,765

Date: 09/29/2014			
Supervisor:		Duncan	
Work Objective:		Logging	
Contractors:		CHS	
Completion Rig:		Casedhole Sol	Supervisor Phone: 435-828-1472
Upcoming Activity:		Prep for frac work	
Activities			
1030-1330		MIRU CHS WLU, run 4.65" gauge ring fr/surface to 6638'. POH w/gauge ring. Run CBL/GR/CCL fr/6626' to surface. TOC @ 1694'. RDMO WLU.	
Costs (\$):	Daily:	5,138	Cum: 5,138 AFE: 1,298,141

Date: 09/30/2014			
Supervisor:		Duncan	
Work Objective:		Nipple up BOP	
Contractors:		Knight	
Completion Rig:		(Missing)	Supervisor Phone: 435-828-1472
Upcoming Activity:		Prep for frac work	
Activities			
0900-1000		MINU Knight 5K BOP. Set flow back tanks.	
Costs (\$):	Daily: 2,272	Cum: 7,410	AFE: 1,298,141

Date: 10/01/2014			
Supervisor:		Duncan	
Work Objective:		Prep for frac work	
Contractors:		Knight	
Completion Rig:		(Missing)	Supervisor Phone: 435-828-1472
Upcoming Activity:		Prep for frac work	
Activities			
0800-0801		MI set frac tanks. Install flow back iron. Fill 10K, and 500 bbl tanks	
Costs (\$):	Daily:	1,350	Cum: 8,760 AFE: 1,298,141

Date: 10/02/2014			
Supervisor:		Duncan	
Work Objective:		Testing	
Contractors:		MBT, Rhetts, R&R, Target, Sunrise	
Completion Rig:		(Missing)	Supervisor Phone: 435-828-1472
Upcoming Activity:		Prep for frac work	
Activities			
0900-1000		MIRU RBS Test Unit, and test csg, WH, Flow back lines, and BOP to 4,250 psig, good test. RDMO Testers.	
Costs (\$):	Daily:	6,562	Cum: 15,322 AFE: 1,298,141

Date: 10/03/2014			
Supervisor:		Duncan	
Work Objective:		Perforating	
Contractors:		CHS	
Completion Rig:		Casedhole Sol	Supervisor Phone: 435-828-1472
Upcoming Activity:		Prep for frac work	
Activities			
0800-1000		Perforate stage 1 (6606'-6480').	
Costs (\$):	Daily:	6,000	Cum: 21,322
			AFE: 1,298,141

Date: 10/06/2014			
Supervisor:		Stringham/Duncan	
Work Objective:		Perf, Frac, and Flowback	
Contractors:		HES, R&R, Rhett's, Target, Sunrise	
Completion Rig:		Hal, HAL RED T4	Supervisor Phone: 435-790-2326/435-828-1472
Upcoming Activity:		Perf, Frac, and Flowback	
Activities			
0500-0645		Prime up and pressure test frac lines.	
0645-0720		Safety meeting with Vendors. WH, WL perforating, & crane operations, PPE, chemical handling, location conditions, stepping, handling & lifting, slips, trips & falls, pinch points, traffic control, backing, land guides, incident reporting , spill containment , JSA's and Muster area.	
0720-0835		Frac stage 1.	
0835-0955		Perforate stage 2 (6365'-6441'). Set 5.5" FTFP @ 6466'.	
0955-1145		Frac stage 2.	
1145-1215		Perforate stage 3 (6141'-6331'). Set 5.5" FTFP @ 6348'.	
1215-1355		Frac stage 3.	
1355-1545		Perforate stage 4 (5859'-6085'). Set 5.5" FTFP @ 6102'.	
1545-1620		Frac stage 4.	
1620-1725		Perforate Stage 5 (5588'-5833'). Set 5.5" FTFP @ 5853'.	
1725-1908		Frac Stage 5	
1908-2020		Perforate Stage 6 (5075'-5362'). Set 5.5" FTFP @ 5382'.	
2020-2121		Frac Stage 6	
2121-2225		Perforate Stage 7 (4900'-5043'). Set 5.5" FTFP @ 5063'.	
2225-2320		Change Out Chemical & HCL Trailers	
2320-0030		Frac Stage 7 Shutdown On X-Link Pad No Gel And Lost Suction C-Pump On Blender	
Costs (\$):	Daily:	46,978	Cum: 68,300 AFE: 1,298,141

Date: 10/07/2014			
Supervisor:		Stringham/Duncan	
Work Objective:		W/O CTU	
Contractors:		(Missing)	
Completion Rig:		(Missing)	Supervisor Phone: 435-790-2326/435-828-1472
Upcoming Activity:		Drill out plug	
Activities			
2320-0030		Frac Stage 7 Shutdown On X-Link Pad No Gel And Lost Suction C-Pump On Blender	
0030-0300		Working On Growler For Gel And Suction Pump On Blender. Went To Start Blender Had Hydraulic Hose Come Off, Shutdown again To Fix.	
0300-0327		Resume Frac Stage 7 SICP (1423) PSI	
W/O CTU			
Costs (\$):	Daily:	0	Cum: 68,300 AFE: 1,298,141

Date: 10/08/2014			
Supervisor:		(Missing)	
Work Objective:		(Nothing Recorded)	
Contractors:		(Missing)	
Completion Rig:		(Missing)	Supervisor Phone: (Missing)
Upcoming Activity:			
Costs (\$):	Daily:	19,924	Cum: 88,224 AFE: 1,298,141

Date: 10/09/2014			
Supervisor:		Stringham/Duncan	
Work Objective:		Drill out plug	SSE: 2
Contractors:		IPS,R&R,ETS,Rhetts	
Completion Rig:		IPS CT 2"	Supervisor Phone: 435-790-2326/435-828-1472
Upcoming Activity:		Flow test well	
Activities			
1300-1400		MIRU IPS 2" CTU fr/TR4-38T-820. Spot in and RU crane & coil tubing unit. NU stack, and flow lines. Pick up injector head and NU lub. Run the same connector fr/TR_4-38T-820.	
1400-1445		Make up New ETS BHA as follows: Coil Connector, Bi-Directional jar, MHA Dual Check Valves, 3/4" Ball Seat (back pressure valve) Hydraulic Disconnect, Dual Circ Sub, 5/8" Ball Seat, 8K Burst Disc, motor and 5 blade 4.625" mill. Connect lubricator. Function test motor, 1.5 BPM @ 1800 PSI.Pressure test to 3500 psi. Open rams, 250 psi well pressure.	
1445-1525		RIH with mill and motor to plug @ 5063'. (Coil depth 5068').	
1525-1535		Drill plug @ 5068' (175) PSI.	
1535-1540		Pump a 10 bbl gel sweep. RIH with mill and motor to plug @ 5382'. (Coil depth 5383').	
1540-1605		Drill plug @ 5382' (160) PSI.	
1605-1615		Pump a 10 bbl gel sweep. RIH with mill and motor to plug @ 5853'. (Coil depth 5855').	
1615-1630		Drill plug @ 5853' (250) PSI.	
1630-1645		Pump a 10 bbl gel sweep. RIH with mill and motor to plug @ 6102'. (Coil depth 6110').	
1645-1700		Drill Plug @ 6102' (250) PSI.	
1700-1705		Pump a 10 bbl gel sweep. RIH with mill and motor to plug @ 6348'. (Coil depth 6355').	
1705-1720		Drill Plug @ 6348' (330) PSI.	
1720-1730		Pump a 10 bbl gel sweep. RIH with mill and motor to plug @ 6466'. (Coil depth 6474').	
1730-1745		Drill Plug @ 6466' (300) PSI.	
1745-2105		RIH to PBTD @ 6744'. Pump 20 bbl gel sweep, 10 bbl water spacer & 20 bbl gel sweep. Coil PBTD @ 6740'. Make 500' short trip and retag PBTD. POOH @ 50 ft/min for 30 min and then continue POOH. Close Bottom ram, SICP 400 PSI.	
2105-2205		RDMO CTU	
2205-2206		Turn well over to flow testers, open well on 18/64 choke. IP (460) PSI.	
Costs (\$):	Daily:	421,297	Cum: 509,521 AFE: 1,298,141

Date: 10/10/2014			
Supervisor:		Stringham/Duncan	
Work Objective:		Flow test well	SSE: 2
Contractors:		R&R, Rhetts	
Completion Rig:		(Missing)	Supervisor Phone: 435-790-2326/435-828-1472
Upcoming Activity:		Turned over to Production Dept	
Costs (\$):	Daily:	13,999	Cum: 523,519
			AFE: 1,298,141

Date: 10/11/2014			
Supervisor:		Duncan	
Work Objective:		Flow test well	
Contractors:		R&R, Rhett's	
Completion Rig:		(Missing)	Supervisor Phone: 435-828-1472
Upcoming Activity:		Turned over to Production Dept	
Costs (\$):	Daily: 0	Cum: 523,519	AFE: 1,298,141

Date: 10/12/2014			
Supervisor:		Fletcher	
Work Objective:		Turned over to Production Dept	
Contractors:		(Missing)	
Completion Rig:		(Missing)	Supervisor Phone: 3036459812
Upcoming Activity:			
Costs (\$):	Daily: 0	Cum: 523,519	AFE: 1,298,141

Date: 10/13/2014						
Supervisor: (Missing)						
Work Objective: (Nothing Recorded)						
Contractors: (Missing)						
Completion Rig: (Missing)			Supervisor Phone: (Missing)			
Upcoming Activity:						
Costs (\$):	Daily:	5,983	Cum:	529,502	AFE:	1,298,141

Date: 10/14/2014						
Supervisor: (Missing)						
Work Objective: (Nothing Recorded)						
Contractors: (Missing)						
Completion Rig: (Missing)			Supervisor Phone: (Missing)			
Upcoming Activity:						
Costs (\$):	Daily:	4,744	Cum:	534,246	AFE:	1,298,141

Date: 10/15/2014			
Supervisor: (Missing)			
Work Objective: (Nothing Recorded)			
Contractors: (Missing)			
Completion Rig: (Missing)			Supervisor Phone: (Missing)
Upcoming Activity:			
Costs (\$):	Daily: 33,730	Cum: 567,976	AFE: 1,298,141

Date: 10/16/2014				
Supervisor:		Jim Burns		
Work Objective:		TIH w/ Rods		
Contractors:		Stone, Willies		
Completion Rig:		Stone #7	Supervisor Phone: 435-299-2974	
Upcoming Activity:		Pressure test		
Activities				
0600-0700		Crew Travel		
0700-1900		TBG RIH w/ rods plunger hung up in barrel worked it through screwed onto standing valve. POOH called for cellar to be suck out hot oiler pumped 2 bbls of chemical and flushed with 40 bls RIH w/ rods tag space out p.u. Polish Rod fill w/ 10 bbls stroke test form 500-1000 psi in 1 stroke hand horse head hang off well rig down.		
1900-2000		Crew Travel		
Costs (\$):	Daily:	1,700	Cum: 569,676	AFE: 1,298,141

ULTRA RESOURCES, INC.
PERFORATION AND FRAC SUMMARY FOR THREE RIVERS 4-36T-820

Well Name: THREE RIVERS 4-36T-820			Fracs Planned: 7		
Location: UINTAH County, UTAH (NWSE 004 8S 20E)					
Stage 1		Frac Date: 10/06/2014	Avg Rate: 49.0 BPM	Avg Pressure: 2,272 PSI	
Initial Completion		Proppant: 108,195 lbs total	Max Rate: 61.0 BPM	Max Pressure: 3,819 PSI	
108195 lbs Ottawa					
Initial Annulus Pressure: 0		Final Annulus Pressure: 0	Pump Down Volume:		
PreFrac SICP:		ISIP: 1,714 PSI	Base BBLS to Recover: 3,573 BBLs		
Pseudo Frac Gradient: 0.691 PSI/FT		Pseudo Frac Gradient: 13.291 LB/GAL			
		Net Pressure: 236 psi	Total BBLS to Recover: 3,573 BBLs		
Breakdown Pressure: 2135		Breakdown Rate: 3.8	Perfs Open:		
ScreenOut: No		Tracer: (None)			
Zones:	Perf Date	SPF	Perf Interval:	From	To
11	10/06/2014	3		6,480	6,481
10	10/06/2014	3		6,490	6,491
9	10/06/2014	3		6,500	6,501
8	10/06/2014	3		6,525	6,526
7	10/06/2014	3		6,533	6,534
6	10/06/2014	3		6,549	6,550
5	10/06/2014	3		6,556	6,557
4	10/06/2014	3		6,569	6,570
3	10/06/2014	3		6,580	6,581
2	10/06/2014	3		6,624	6,625
1	10/06/2014	3		6,633	6,635
Stage 2		Frac Date: 10/06/2014	Avg Rate: 50.0 BPM	Avg Pressure: 2,766 PSI	
Initial Completion		Proppant: 112,920 lbs total	Max Rate: 61.0 BPM	Max Pressure: 3,882 PSI	
112920 lbs Ottawa					
Initial Annulus Pressure: 0		Final Annulus Pressure: 0	Pump Down Volume:		
PreFrac SICP:		ISIP: 1,710 PSI	Base BBLS to Recover: 3,723 BBLs		
Pseudo Frac Gradient: 0.698 PSI/FT		Pseudo Frac Gradient: 13.428 LB/GAL			
		Net Pressure: -450 psi	Total BBLS to Recover: 3,723 BBLs		
Breakdown Pressure: 1464		Breakdown Rate: 6.3	Perfs Open:		
ScreenOut: No		Tracer: (None)			
Zones:	Perf Date	SPF	Perf Interval:	From	To
10	10/06/2014	3		6,365	6,366
9	10/06/2014	3		6,372	6,373
8	10/06/2014	3		6,377	6,378
7	10/06/2014	3		6,382	6,383
6	10/06/2014	3		6,392	6,393
5	10/06/2014	3		6,404	6,405
4	10/06/2014	3		6,411	6,412
3	10/06/2014	3		6,421	6,422
2	10/06/2014	3		6,429	6,430
1	10/06/2014	3		6,439	6,441
Stage 3		Frac Date: 10/06/2014	Avg Rate: 50.0 BPM	Avg Pressure: 2,498 PSI	
Initial Completion		Proppant: 171,147 lbs total	Max Rate: 61.0 BPM	Max Pressure: 3,841 PSI	
171147 lbs Ottawa					
Initial Annulus Pressure: 0		Final Annulus Pressure: 0	Pump Down Volume:		
PreFrac SICP:		ISIP: 1,487 PSI	Base BBLS to Recover: 5,289 BBLs		
Pseudo Frac Gradient: 0.668 PSI/FT		Pseudo Frac Gradient: 12.840 LB/GAL			
		Net Pressure: -305 psi	Total BBLS to Recover: 5,289 BBLs		
Breakdown Pressure: 2259		Breakdown Rate: 10.3	Perfs Open:		
ScreenOut: No		Tracer: (None)			
Zones:	Perf Date	SPF	Perf Interval:	From	To
13	10/06/2014	3		6,141	6,142
12	10/06/2014	3		6,151	6,152
11	10/06/2014	3		6,159	6,160
10	10/06/2014	3		6,186	6,187
9	10/06/2014	3		6,193	6,194
8	10/06/2014	3		6,210	6,211
7	10/06/2014	3		6,218	6,219
6	10/06/2014	3		6,252	6,253
5	10/06/2014	3		6,265	6,266
4	10/06/2014	3		6,284	6,285
3	10/06/2014	3		6,298	6,299
2	10/06/2014	3		6,317	6,318
1	10/06/2014	3		6,330	6,331

Stage 4	Frac Date: 10/06/2014	Avg Rate: 49.0 BPM	Avg Pressure: 2,987 PSI
Initial Completion	Proppant: 170,184 lbs total	Max Rate: 61.0 BPM	Max Pressure: 3,869 PSI
	170184 lbs Ottawa		
	Initial Annulus Pressure: 0	Final Annulus Pressure: 0	Pump Down Volume:
	PreFrac SICP:	ISIP: 1,613 PSI	Base BBLS to Recover: 4,602 BBLs
	Pseudo Frac Gradient: 0.698 PSI/FT	Pseudo Frac Gradient: 13.421 LB/GAL	
		Net Pressure: -283 psi	Total BBLS to Recover: 4,602 BBLs
	Breakdown Pressure: 2658	Breakdown Rate: 6.7	Perfs Open:
	ScreenOut: No	Tracer: (None)	
Zones:	Perf Date	SPF	Perf Interval: From To
13	10/06/2014	3	5,859 5,860
12	10/06/2014	3	5,873 5,874
11	10/06/2014	3	5,889 5,890
10	10/06/2014	3	5,938 5,939
9	10/06/2014	3	5,949 5,950
8	10/06/2014	3	5,968 5,969
7	10/06/2014	3	5,978 5,979
6	10/06/2014	3	5,990 5,991
5	10/06/2014	3	6,007 6,008
4	10/06/2014	3	6,040 6,041
3	10/06/2014	3	6,048 6,049
2	10/06/2014	3	6,059 6,060
1	10/06/2014	3	6,084 6,085
Stage 5	Frac Date: 10/06/2014	Avg Rate: 47.0 BPM	Avg Pressure: 2,987 PSI
Initial Completion	Proppant: 186,252 lbs total	Max Rate: 64.0 BPM	Max Pressure: 4,098 PSI
	186252 lbs Ottawa		
	Initial Annulus Pressure: 0	Final Annulus Pressure: 0	Pump Down Volume:
	PreFrac SICP:	ISIP: 2,025 PSI	Base BBLS to Recover: 4,967 BBLs
	Pseudo Frac Gradient: 0.780 PSI/FT	Pseudo Frac Gradient: 14.999 LB/GAL	
		Net Pressure: 37 psi	Total BBLS to Recover: 4,967 BBLs
	Breakdown Pressure: 3836	Breakdown Rate: 4.3	Perfs Open:
	ScreenOut: No	Tracer: (None)	
Zones:	Perf Date	SPF	Perf Interval: From To
12	10/06/2014	3	5,588 5,589
11	10/06/2014	3	5,619 5,620
10	10/06/2014	3	5,644 5,645
9	10/06/2014	3	5,669 5,670
8	10/06/2014	3	5,679 5,680
7	10/06/2014	3	5,693 5,694
6	10/06/2014	3	5,713 5,714
5	10/06/2014	3	5,733 5,734
4	10/06/2014	3	5,751 5,752
3	10/06/2014	3	5,775 5,776
2	10/06/2014	3	5,816 5,817
1	10/06/2014	3	5,831 5,833
Stage 6	Frac Date: 10/06/2014	Avg Rate: 43.0 BPM	Avg Pressure: 2,827 PSI
Initial Completion	Proppant: 98,775 lbs total	Max Rate: 64.0 BPM	Max Pressure: 4,022 PSI
	98775 lbs Ottawa		
	Initial Annulus Pressure: 0	Final Annulus Pressure: 0	Pump Down Volume:
	PreFrac SICP:	ISIP: 1,613 PSI	Base BBLS to Recover: 2,763 BBLs
	Pseudo Frac Gradient: 0.734 PSI/FT	Pseudo Frac Gradient: 14.108 LB/GAL	
		Net Pressure: -378 psi	Total BBLS to Recover: 2,763 BBLs
	Breakdown Pressure: 4022	Breakdown Rate: 9.4	Perfs Open:
	ScreenOut: No	Tracer: (None)	
Zones:	Perf Date	SPF	Perf Interval: From To
12	10/06/2014	3	5,075 5,076
11	10/06/2014	3	5,109 5,110
10	10/06/2014	3	5,132 5,133
9	10/06/2014	3	5,144 5,145
8	10/06/2014	3	5,175 5,176
7	10/06/2014	3	5,202 5,203
6	10/06/2014	3	5,221 5,222
5	10/06/2014	3	5,269 5,270
4	10/06/2014	3	5,339 5,340
3	10/06/2014	3	5,346 5,347
2	10/06/2014	3	5,352 5,353
1	10/06/2014	3	5,360 5,362

Stage 7	Frac Date: 10/07/2014	Avg Rate: 44.0 BPM	Avg Pressure: 2,122 PSI
Initial Completion	Proppant: 121,704 lbs total	Max Rate: 62.0 BPM	Max Pressure: 3,745 PSI
	121704 lbs Ottawa		
	Initial Annulus Pressure: 0	Final Annulus Pressure: 0	Pump Down Volume:
	PreFrac SICP:	ISIP: 1,423 PSI	Base BBLS to Recover: 3,989 BBLS
	Pseudo Frac Gradient: 0.715 PSI/FT	Pseudo Frac Gradient: 13.749 LB/GAL	
		Net Pressure: -294 psi	Total BBLS to Recover: 3,989 BBLS
	Breakdown Pressure: 2126	Breakdown Rate: 9.8	Perfs Open:
	ScreenOut: No	Tracer: (None)	
Zones:	Perf Date	SPF	Perf Interval: From To
13	10/06/2014	3	4,900 4,901
12	10/06/2014	3	4,909 4,910
11	10/06/2014	3	4,915 4,916
10	10/06/2014	3	4,926 4,927
9	10/06/2014	3	4,944 4,945
8	10/06/2014	3	4,963 4,964
7	10/06/2014	3	4,970 4,971
6	10/06/2014	3	4,982 4,983
5	10/06/2014	3	4,989 4,990
4	10/06/2014	3	5,013 5,014
3	10/06/2014	3	5,022 5,023
2	10/06/2014	3	5,033 5,034
1	10/06/2014	3	5,042 5,043

Hydraulic Fracturing Fluid Product Component Information Disclosure

Job Start Date:	10/6/2014
Job End Date:	10/7/2014
State:	Utah
County:	Uintah
API Number:	43-047-54420-00-00
Operator Name:	Ultra Resources
Well Name and Number:	Three Rivers Federal 4-36T-820
Longitude:	-109.67261100
Latitude:	40.14858100
Datum:	NAD27
Federal/Tribal Well:	NO
True Vertical Depth:	7,500
Total Base Water Volume (gal):	1,212,306
Total Base Non Water Volume:	0



Hydraulic Fracturing Fluid Composition:

Trade Name	Supplier	Purpose	Ingredients	Chemical Abstract Service Number (CAS #)	Maximum Ingredient Concentration in Additive (% by mass)**	Maximum Ingredient Concentration in HF Fluid (% by mass)**	Comments
Fresh Water	Operator	Base Fluid					
			Fresh Water	7732-18-5	100.00000	90.36617	Density = 8.330
SAND - PREMIUM WHITE	Halliburton	Proppant					
			Crystalline silica, quartz	14808-60-7	100.00000	8.64847	
HYDROCHLORIC ACID 10-30%	Halliburton	Solvent					
			Hydrochloric acid	7647-01-0	30.00000	0.19221	
LoSurf-300D	Halliburton	Non-ionic Surfactant					
			Ethanol	64-17-5	60.00000	0.04643	
			Heavy aromatic petroleum naphtha	64742-94-5	30.00000	0.02322	
			Poly(oxy-1,2-ethanediyl), alpha-(4-nonylphenyl)-omega-hydroxy-, branched	127087-87-0	5.00000	0.00387	
			Naphthalene	91-20-3	5.00000	0.00387	
			1,2,4 Trimethylbenzene	95-63-6	1.00000	0.00077	
WG-35 GELLING AGENT	Halliburton	Gelling Agent					
			Guar gum	9000-30-0	100.00000	0.04212	
BC-140	Halliburton	Crosslinker					
			Monoethanolamine borate	26038-87-9	60.00000	0.02303	

			Ethylene glycol	107-21-1	30.00000	0.01152	
Cla-Web™	Halliburton	Additive					
			Ammonium salt	Confidential	60.00000	0.02931	Denise Tuck, Halliburton 3000 N. Sam Houston Pkwy E., Houston, TX 77032 281-871-6226
MC MX 2-2822	Multi-Chem	Scale Inhibitor					
			Methyl Alcohol	67-56-1	30.00000	0.01291	Density = 8.76
			Phosphonate of a Diamine, Sodium Salt	Proprietary	30.00000	0.01291	
SandWedge® NT	Halliburton	Conductivity Enhancer					
			Dipropylene glycol monomethyl ether	34590-94-8	60.00000	0.01951	
			Heavy aromatic petroleum naphtha	64742-94-5	10.00000	0.00325	
FE-1A ACIDIZING COMPOSITION	Halliburton	Additive					
			Acetic anhydride	108-24-7	100.00000	0.00642	
			Acetic acid	64-19-7	60.00000	0.00385	
FR-66	Halliburton	Friction Reducer					
			Hydrotreated light petroleum distillate	64742-47-8	30.00000	0.00979	
MC B-8614	Multi-Chem	Biocide					
			Glutaraldehyde	111-30-8	30.00000	0.00552	
			Alkyl (C12-16) dimethylbenzylammonium chloride	68424-85-1	5.00000	0.00092	
OPTIFLO-HTE	Halliburton	Breaker					
			Walnut hulls	Mixture	100.00000	0.00221	
			Crystalline silica, quartz	14808-60-7	30.00000	0.00066	
SP BREAKER	Halliburton	Breaker					
			Sodium persulfate	7775-27-1	100.00000	0.00170	
HAI-404M™	Halliburton	Corrosion Inhibitor					
			Aldehyde	Confidential	30.00000	0.00035	
			Isopropanol	67-63-0	30.00000	0.00035	
			Methanol	67-56-1	30.00000	0.00035	
			Quaternary ammonium salt	Confidential	10.00000	0.00012	
			1-(Benzyl)quinolinium chloride	15619-48-4	10.00000	0.00012	
Ingredients shown above are subject to 29 CFR 1910.1200(i) and appear on Material Safety Data Sheets (MSDS). Ingredients shown below are Non-MSDS.							
		Other Ingredient(s)					
			Water	7732-18-5		0.75406	
		Other Ingredient(s)					
			Oxyalkylated phenolic resin	Confidential		0.02322	
		Other Ingredient(s)					
			Polyacrylamide copolymer	Confidential		0.00979	
		Other Ingredient(s)					
			Oxyalkylated phenolic resin	Confidential		0.00774	

		Other Ingredient(s)					
			Sodium chloride	7647-14-5		0.00407	
		Other Ingredient(s)					
			Quaternary ammonium compound	Confidential		0.00325	
		Other Ingredient(s)					
			Quaternary amine	Confidential		0.00244	
		Other Ingredient(s)					
			Modified bentonite	Confidential		0.00211	
		Other Ingredient(s)					
			Alcohols, C12-16, ethoxylated	68551-12-2		0.00175	
		Other Ingredient(s)					
			Fatty acid tall oil amide	Confidential		0.00163	
		Other Ingredient(s)					
			Ammonium chloride	12125-02-9		0.00163	
		Other Ingredient(s)					
			Cured acrylic resin	Confidential		0.00066	
		Other Ingredient(s)					
			Quaternary amine	Confidential		0.00049	
		Other Ingredient(s)					
			Silica, amorphous - fumed	7631-86-9		0.00042	
		Other Ingredient(s)					
			Ethoxylated nonylphenol	Confidential		0.00042	
		Other Ingredient(s)					
			Naphthenic acid ethoxylate	68410-62-8		0.00035	
		Other Ingredient(s)					
			Methanol	67-56-1		0.00035	
		Other Ingredient(s)					
			Sorbitan monooleate polyoxyethylene derivative	9005-65-6		0.00033	
		Other Ingredient(s)					
			Sorbitan, mono-9-octadecenoate, (Z)	1338-43-8		0.00033	
		Other Ingredient(s)					
			Polyethoxylated fatty amine salt	61791-26-2		0.00012	
		Other Ingredient(s)					
			Fatty acids, tall oil	Confidential		0.00012	
		Other Ingredient(s)					
			Enzyme	Confidential		0.00011	
		Other Ingredient(s)					
			Ethoxylated amine	Confidential		0.00006	
		Other Ingredient(s)					
			Quaternary amine	Confidential		0.00005	
		Other Ingredient(s)					
			Amine salts	Confidential		0.00005	
		Other Ingredient(s)					
			Amine salts	Confidential		0.00005	

		Other Ingredient(s)					
			Crystalline silica, quartz	14808-60-7		0.00004	
		Other Ingredient(s)					
			C.I. Pigment Red 5	6410-41-9		0.00002	
		Other Ingredient(s)					
			Cured acrylic resin	Confidential		0.00002	
		Other Ingredient(s)					
			Ammonium phosphate	7722-76-1		0.00001	
		Other Ingredient(s)					
			Sodium iodide	7681-82-5		0.00001	
		Other Ingredient(s)					
			Naphthalene	91-20-3		0.00000	
		Other Ingredient(s)					
			Phosphoric Acid	7664-38-2		0.00000	
		Other Ingredient(s)					
			Sodium sulfate	7757-82-6		0.00000	

* Total Water Volume sources may include fresh water, produced water, and/or recycled water

** Information is based on the maximum potential for concentration and thus the total may be over 100%

Note: For Field Development Products (products that begin with FDP), MSDS level only information has been provided.

Ingredient information for chemicals subject to 29 CFR 1910.1200(i) and Appendix D are obtained from suppliers Material Safety Data Sheets (MSDS)

Well Name: Three Rivers 4-36T-820 1 Green River

Date, Time & SO: 10/06/14 7:11 AM 901724450
Top & Bottom Perfs: 6480 TO 6625.0
Mid-Perf: 6558

BHST: 160 °F

HALLIBURTON

Stage	Stage Name	Slurry Vol	Pump Time	Fluid Name	Fluid Volume	Proppant	Slurry	Max Slurry	Pressure	Pressure	Pressure	Prop Conc	Prop Conc	Liquid Additives				Liquid Additives				SP	FR-76	MC B-8614			
														WG-35 9000-30-0 (Gel)	BC 140 590-29-4 (Xlinker)	Sandwedge N 1310-58-3 (Xlinker)	BA-20 631-61-8 (Buffer)	LoSurf-300D	CLA-Web (Clay Cont.)	MC MX 2-2822 (Conduct. Enh.)	Optiflo HTE 7727-54-0 (Breaker)						
		(bbl)			(gal)	Mass (lb)	Rate (bpm)	Rate (bpm)	Ave (psi)	Max (psi)	Min (psi)	Avg (PPG)	Max (PPG)														
1	Pre-Pad	8	0:00:49	FR Water	340	0	3.0	3.8	1500	2135	65	0.00	0.00					1.00	0.50			0.50	0.20				
2	0 PPG	24	0:02:23	15 % HCL Acid	1000	0	10.4	16.2	1813	1975	1581	0.00	0.00														
3	0 PPG	1004	0:16:44	FR Water	42153	0	55.3	60.6	2664	3819	1827	0.00	0.00					1.00	0.50	0.60		0.50	0.20				
4	0.35 PPG White Sand	1382	0:23:02	FR Water	57075	19,406	60.2	60.4	2413	2465	2369	0.34	0.36					1.00	0.50	0.60		0.50	0.20				
5	0.35 PPG White Sand	121	0:02:01	FR Water	5014	1,705	60.3	60.3	2444	2464	2427	0.34	0.35					1.00	0.50	2.00		0.50	0.20				
6	0.35 PPG White Sand	122	0:02:02	FR Water	5018	1,430	59.3	60.5	2440	2486	2226	0.29	0.35					1.00	0.50	0.25		0.50	0.20				
7	0 PPG	138	0:02:18	18# Delta 140	5792	0	54.5	60.5	2376	2630	1826	0.00	0.00	18.00	1.50			1.00	0.50	0.25	0.80	0.25	0.20				
8	2 PPG White Sand	338	0:05:38	18# Delta 140	12917	24,284	60.1	60.5	2532	2675	12917	1.88	2.11	18.00	1.80			1.00	0.50	0.25	1.00	0.50	0.20				
9	4 PPG White Sand	209	0:03:29	18# Delta 140	7352	27,298	60.0	60.6	2364	2554	7352	3.71	4.06	18.00	1.80			1.00	0.50	0.25	1.00	0.50	0.20				
10	6 PPG White Sand	218	0:03:38	18# Delta 140	7089	35,161	60.3	60.3	2277	2358	2232	4.96	6.07	18.00	1.80	1.80		1.00	0.50		1.00	0.50	0.20				
						0																					
						0																					
						0																					
						0																					
						0																					
11	Flush	150	0:02:30	FR Water	6309	0	60.3	61.0	2173	2691	1523	0.00	0.00					1.00	0.50			0.50	0.20				
						0																					
	Growler @ Flush	57			4000	0																0.00					
Calculated Amt														796.70	57.93	63.29	0.00	149.06	74.53	77.80	31.99	15.13	57.95	29.81			
Actual Amt														835.00	56.70	58.90		150.20	79.60	78.20	31.60	15.30	57.80	29.90			
Percent Variance														4.8%	-2.1%	-6.9%	0.0%	0.8%	6.8%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%		
Strap Amt														835.00	58.00	60.00		152.00	81.00	79.00	32.00	16.00	58.00	30.00			
Percent Variance														4.8%	0.0%	-5.2%	0.0%	2.0%	8.7%	1.5%	0.0%	0.0%	0.0%	0.0%			
Slurry (bbl)		3714																									

Percent Variance is reported as 0% if variance is within 1 gallon.

Slurry (bbl) 3714
Pump Time (Min) 1:04:34
Clean Fluid (gal) 150059
Proppant (lb) 121263

Avg Rate 49.4 BPM
Avg Corrected Rate 54.1 BPM
Max Rate 61.0 BPM
Average Prop Con 1.3
Average Pressure 2272.4 PSI
Maximum Pressure 3819.0 PSI

BREAKDOWN INFORMATION:

Base Fluid: 8.40 PPG
Wellhead Pressure: 65 PSI
Broke Back: 2135 PSI
Pressure (Prop at Perfs) 2401 PSI
Initial ISIP: 2135 PSI
ISDP: 1714 PSI

@ 3.8 BPM
@ 60.0 BPM
@ 0.698 PSI/FT

(Use weight slips for below amounts)				Variance		COMMENTS:			
TOTAL PROPPANT PUMPED: 107,916 Lbs				0.0%		HES Engineer: Greg Carr			
						Co. Rep: Joe Duncan			
						Crew: Red C			
% of Job	Prop	Mesh	Quantity	Units	MB Vari	SS Vari	Dens Vari	SC Vari	
0%	None	20/40		Lbs	1.3%	3.7%	0.3%	3.5%	Equipment running well
0%	TLC	20/40		Lbs					Xlink samples look good
100%	White Sand	20/40	107,916	Lbs					Good job by Crew
Initial Annulus Pressure 0.0 PSI				Average Annulus Pressure 0.0 PSI		3bbl overflush per Co Rep			
Final Annulus Pressure 0.0 PSI				Change in Annulus Pressure 0.0 PSI		Had to drop rate in stage 7 because blender was losing its tub because the ADP Blender started mixing.			

CLEAN STREAM:		
UV1 HRs	UV2 HRs	Transm.%
520	520	71.7

Well Name: Three Rivers 4-36T-820 2 Green River

Date, Time & SO: 10/06/14 9:59 AM 901724450
Top & Bottom Perfs: 6365 TO 6441.0
Mid-Perf: 6403

BHST: 157 °F

HALLIBURTON

Stage	Stage Name	Slurry Vol (bbl)	Pump Time	Fluid Name	Fluid Volume (gal)	Proppant Mass (lb)	Slurry Rate (bpm)	Max Slurry Rate (bpm)	Pressure Ave (psi)	Pressure Max (psi)	Pressure Min (psi)	Prop Conc Avg (PPG)	Prop Conc Max (PPG)	Liquid Additives				Liquid Additives							
														WG-35 9000-30-0 (Gel) (ppt)	BC 140 590-29-4 (Xlinker) (gpt)	Sandwedge NT 1310-58-3 (Xlinker) (gpt)	BA-20 631-61-8 (Buffer) (gpt)	LoSurf-300D	CLA-Web (Clay Cont.) (gpt)	MC MX 2-2822 (Conduct. Enh.) (gpt)	Optiflo HTE 7727-54-0 (Breaker) (ppt)	SP 7775-27-1 (Breaker) (ppt)	FR-66 (Fric Red) (gpt)	MC B-8614 7681-52-9 (Bactericide) (gpt)	
1	Pre-Pad	12	0:01:11	FR Water	500	0	4.1	7.2	1284	1485	977	0.00	0.00					1.00	0.50					0.50	0.20
2	0 PPG	22	0:02:11	15 % HCL Acid	918	0	9.3	10.6	1735	1873	1484	0.00	0.00												
3	PPG	1042	0:17:22	FR Water	43761	0	53.6	60.7	3212	3882	1839	0.00	0.00					1.00	0.50	0.58			0.50	0.20	
4	0.35 PPG White Sand	1445	0:24:05	FR Water	59683	22.441	60.6	60.8	3063	3283	2965	0.38	0.46					1.00	0.50	0.58			0.50	0.20	
5	0.35 PPG White Sand	121	0:02:01	FR Water	5011	1.754	60.7	60.7	3155	3166	3142	0.35	0.36					1.00	0.50	2.00			0.50	0.20	
6	0.35 PPG White Sand	122	0:02:02	FR Water	5026	1.809	60.8	61.0	3169	3185	3138	0.36	0.38	18.00	0.90			1.00	0.50	0.25	0.50		0.50	0.20	
7	0 PPG	133	0:02:13	18# Delta 140	5580	0	61.1	61.2	3111	3158	3069	0.00	0.00	18.00	1.80			1.00	0.50	0.25	1.00	0.50		0.20	
8	2 PPG White Sand	351	0:05:51	18# Delta 140	13430	25.114	60.7	61.1	3098	3224	3013	1.87	2.03	18.00	1.80			1.00	0.50	0.25	1.00	0.50		0.20	
9	4 PPG White Sand	217	0:03:37	18# Delta 140	7625	19.520	60.5	60.7	2966	3017	2901	2.56	4.25	18.00	1.80			1.00	0.50	0.25	1.00	0.50		0.20	
10	6 PPG White Sand	266	0:04:26	18# Delta 140	8645	43.398	60.4	60.7	2820	3014	2543	5.02	6.04	18.00	1.80	1.80		1.00	0.50		1.00	0.50		0.20	
						0																			
						0																			
						0																			
						0																			
						0																			
11	Flush	147	0:02:27	FR Water	6178	0	56.3	61.0	2817	3125	2652	0.00	0.00					1.00	0.50				0.50	0.20	
						0																			
	Growler @ Flush	57			2400	0												0.00						0.00	
Calculated Amt														725.51	68.03	78.12	0.00	155.44	77.72	77.94	37.79	17.64	60.08	31.09	
Actual Amt														755.00	66.70	73.30		155.00	77.20	77.80	37.10	18.60	60.70	31.20	
Percent Variance														4.1%	-2.0%	-6.2%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	
Strap Amt														755.00	68.00	79.00		155.00	78.00	78.00	38.00	19.00	61.00	32.00	
Percent Variance														4.1%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	7.7%	0.0%	0.0%	
Slurry (bbl)	3879																								

Percent Variance is reported as 0% if variance is within 1 gallon.

Slurry (bbl) 3879
Pump Time (Min) 1:07:27
Clean Fluid (gal) 156357
Proppant (lb) 133632

Avg Rate 49.8 BPM
Avg Corrected Rate 54.4 BPM
Max Rate 61.2 BPM
Average Prop Con 1.2
Average Pressure 2766.4 PSI
Maximum Pressure 3882.0 PSI

BREAKDOWN INFORMATION:

Base Fluid: 8.36 PPG
Wellhead Pressure: 977 PSI
Broke Back: 1464 PSI
Pressure (Prop at Perfs) 3062 PSI
Initial ISIP: 1464 PSI
ISDP: 1710 PSI

@ 6.3 BPM
@ 60.6 BPM
@ 0.702 PSI/FT

(Use weight slips for below amounts)			
TOTAL PROPPANT PUMPED: 112,148 Lbs			
% of Job	Prop	Mesh	Quantity
0%	None	20/40	
0%	TLC	20/40	
100%	White Sand	20/40	112,148
Initial Annulus Pressure 0.0 PSI			
Final Annulus Pressure 0.0 PSI			

Variance			
0.0%			
MB Vari	SS Vari	Dens Vari	SC Vari
1.7%	3.2%	0.7%	4.5%
Average Annulus Pressure 0.0 PSI			
Change in Annulus Pressure 0.0 PSI			

CLEAN STREAM:		
UV1 HRs	UV2 HRs	Transm.%
521	521	72.5

HES Engineer: Greg Carr
Co. Rep: Joe Duncan
Crew: Red C
Equipment running well
Xlink samples look good
Good job by Crew
3bbl overflush per Co Rep
Bin swap in stage 9, prop conc dropped off then the drop caused the sand screw to bind up.

Well Name: Three Rivers 4-36T-820 3 Green River

Date, Time & SO: 10/06/14 12:12 PM 901724450
Top & Bottom Perfs: 6141 TO 6285.0
Mid-Perf: 6236

BHST: 155 °F

HALLIBURTON

Stage	Stage Name	Slurry Vol (bbl)	Pump Time	Fluid Name	Fluid Volume (gal)	Proppant Mass (lb)	Slurry Rate (bpm)	Max Slurry Rate (bpm)	Pressure Ave (psi)	Pressure Max (psi)	Pressure Min (psi)	Prop Conc Avg (PPG)	Prop Conc Max (PPG)	Liquid Additives				Liquid Additives						
														WG-35 9000-30-0 (Gel) (ppt)	BC 140 590-29-4 (Xlinker) (gpt)	Sandwedge N 1310-58-3 (Xlinker) (gpt)	BA-20 631-61-8 (Buffer) (gpt)	LoSurf-300D	CLA-Web (Clay Cont.) (gpt)	MC MX 2-2822 (Conduct. Enh.) (gpt)	Optiflo HTE 7727-54-0 (Breaker) (ppt)	SP 7775-27-1 (Breaker) (ppt)	FR-66 (Fric Red) (gpt)	MC B-8614 7681-52-9 (Bactericide) (gpt)
1	Pre-Pad	11	0:01:07	FR Water	470	0	6.5	7.7	1824	2820	923	0.00	0.00					1.00	0.50				0.30	0.20
2	0 PPG	24	0:02:23	15 % HCL Acid	1000	0	9.4	13.4	2140	2307	1743	0.00	0.00											
3	PPG	1568	0:26:08	FR Water	65869	0	56.2	61.0	2797	3841	1744	0.00	0.00					1.00	0.50	0.37			0.30	0.20
4	0.35 PPG White Sand	2337	0:38:57	FR Water	96496	35,704	60.8	60.9	2710	2923	2611	0.37	0.44					1.00	0.50	0.37			0.30	0.20
5	0.35 PPG White Sand	122	0:02:02	FR Water	5043	1,866	60.7	60.8	2916	2925	2910	0.37	0.39					1.00	0.50	2.00			0.30	0.20
6	0.35 PPG White Sand	120	0:02:00	FR Water	4964	1,936	60.9	61.0	2928	2947	2912	0.39	0.42	8.00	0.50			1.00	0.50	0.25	0.20		0.30	0.20
7	0 PPG	0	0:00:00	18# Delta 140	1	0								18.00	1.80			1.00	0.50	0.25	1.00	0.50		0.20
8	2 PPG White Sand	537	0:08:57	18# Delta 140	20542	39,441	60.7	61.0	2638	2954	2553	1.92	2.02	18.00	1.80			1.00	0.50	0.25	1.00	0.50		0.20
9	4 PPG White Sand	332	0:05:32	18# Delta 140	11664	44,137	60.3	60.8	2447	2564	2336	3.78	4.00	18.00	1.80			1.00	0.50	0.25	1.00	0.50		0.20
10	6 PPG White Sand	311	0:05:11	18# Delta 140	10091	51,060	60.5	61.0	2232	2345	2023	5.06	6.01	18.00	1.80	1.80		1.00	0.50		1.00	0.50		0.20
						0																		
						0																		
						0																		
						0																		
11	Flush	143	0:02:23	FR Water	5986	0	61.0	61.3	2344	2499	2227	0.00	0.00					1.00	0.50				0.50	0.20
						0																		
	Growler @ Flush	57			2400	0								50.00				0.00					0.00	
Calculated Amt														921.08	78.62	91.91	0.00	221.13	110.56	79.38	43.29	21.15	54.85	44.23
Actual Amt														896.00	77.80	88.00		220.50	110.20	79.30	43.40	21.70	54.80	44.10
Percent Variance														-2.7%	0.0%	-4.3%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
Strap Amt														896.00	78.00	90.00		221.00	111.00	80.00	45.00	22.00	55.00	45.00
Percent Variance														-2.7%	0.0%	-2.1%	0.0%	0.0%	0.0%	0.0%	3.9%	0.0%	0.0%	0.0%
Slurry (bbl)		5505																						

Percent Variance is reported as 0% if variance is within 1 gallon.

Slurry (bbl) 5505
Pump Time (Min) 1:34:40
Clean Fluid (gal) 222126
Proppant (lb) 185562

Avg Rate 49.7 BPM
Avg Corrected Rate 54.5 BPM
Max Rate 61.3 BPM
Average Prop Con 1.5
Average Pressure 2497.6 PSI
Maximum Pressure 3841.0 PSI

BREAKDOWN INFORMATION:

Base Fluid: 8.34 PPG
Wellhead Pressure: 943 PSI
Broke Back: 2259 PSI
Pressure (Prop at Perfs) 2670 PSI
Initial ISIP: 2259 PSI
ISDP: 1487 PSI

@ 10.3 BPM
@ 60.8 BPM
@ 0.672 PSI/FT

(Use weight slips for below amounts)			
TOTAL PROPPANT PUMPED: 171,400 Lbs			
% of Job	Prop	Mesh	Quantity Units
0%	None	20/40	Lbs
0%	TLC	20/40	Lbs
100%	White Sand	20/40	171,400 Lbs
Initial Annulus Pressure 0.0 PSI			
Final Annulus Pressure 0.0 PSI			

Variance			
0.0%			
MB Vari	SS Vari	Dens Vari	SC Vari
1.6%	1.7%	-0.1%	3.6%
Average Annulus Pressure 0.0 PSI			
Change in Annulus Pressure 0.0 PSI			

CLEAN STREAM:		
UV1 HRs	UV2 HRs	Transm.%
523	523	69.0

HES Engineer: Greg Carr
Co. Rep: Joe Duncan
Crew: Red C
Equipment running well
Xlink samples look good
Good job by Crew
3bbl overflush per Co Rep
Achived crosslink in stage 6, per co rep we staged directly into stage 8.

Well Name: Three Rivers 4-36T-820 4 Green River

Date, Time & SO: 10/06/14 2:52 PM 901724450
Top & Bottom Perfs: 5859 TO 6041.0
Mid-Perf: 5972

BHST: 151 °F

HALLIBURTON

Stage	Stage Name	Slurry Vol	Pump Time	Fluid Name	Fluid Volume	Proppant	Slurry	Max Slurry	Pressure	Pressure	Pressure	Prop Conc	Prop Conc	Liquid Additives				Liquid Additives				FR-66	MC B-8614	
														WG-35 9000-30-0 (Gel) (ppt)	BC 140 590-29-4 (Xlinker) (gpt)	sandwedge N 1310-58-3 (Xlinker) (gpt)	BA-20 631-61-8 (Buffer) (gpt)	LoSurf-300D	CLA-Web (Clay Cont.) (gpt)	MC MX 2-2822 (Conduct. Enh.) (gpt)	Optiflo HTE 7727-54-0 (Breaker) (ppt)			SP 7775-27-1 (Breaker) (ppt)
		(bbl)			(gal)	Mass (lb)	Rate (bpm)	Rate (bpm)	Ave (psi)	Max (psi)	Min (psi)	Avg (PPG)	Max (PPG)											
1	Pre-Pad	8	0:00:49	FR Water	346	0	4.7	8.5	2237	2955	1127	0.00	0.00					1.00	0.50			0.30	0.20	
2	0 PPG	24	0:02:23	15 % HCL Acid	1000	0	10.3	11.9	3247	3426	2955	0.00	0.00											
3	0 PPG	1273	0:21:13	FR Water	53457	0	52.5	61.2	3006	3869	2784	0.00	0.00					1.00	0.50	0.43		0.30	0.20	
4	0.5 PPG White Sand	2082	0:34:42	FR Water	85352	0	60.5	960.7	3176	3577	331	0.00	0.54					1.00	0.50	0.43		0.70	0.20	
5	0.5 PPG White Sand	123	0:02:03	FR Water	5029	2.766	60.5	60.5	3330	3348	3225	0.55	0.56					1.00	0.50	2.00		0.70	0.20	
6	0.5 PPG White Sand	121	0:02:01	FR Water	4962	2.779	60.5	60.7	3346	3375	3319	0.56	0.59	16.00	0.40			1.00	0.50	0.25	0.50	0.50	0.70	0.20
7	0 PPG	0	0:00:00	16# Delta 140	1	0								16.00	1.60			1.00	0.50	0.25	1.00	1.00		0.20
8	2 PPG White Sand	490	0:08:10	16# Delta 140	18744	38.800	60.4	60.7	3111	3368	2908	2.07	3.48	16.00	1.60			1.00	0.50	0.25	1.00	1.00		0.20
9	4 PPG White Sand	304	0:05:04	16# Delta 140	10663	41.842	60.4	60.6	2768	2917	2646	3.92	4.07	16.00	1.60			1.00	0.50	0.25	1.00	1.00		0.20
10	6 PPG White Sand	247	0:04:07	16# Delta 140	8004	39.540	60.3	62.4	2555	2663	2240	4.94	6.07	16.00	1.60	1.80		1.00	0.50		1.00	1.00		0.20
						0																		
						0																		
						0																		
						0																		
						0																		
11	Flush	136	0:02:16	FR Water	5723	0	61.0	61.0	3092	3514	2550	0.00	0.00					1.00	0.50				0.30	0.20
						0																		
	Growler @ Flush	57			2400	0								50.00				0.00					0.00	
Calculated Amt														677.98	61.84	71.17	0.00	192.28	96.14	78.65	39.89	39.89	84.60	38.46
Actual Amt														691.00	62.50	70.50		194.00	96.50	78.20	39.20	39.20	85.00	38.50
Percent Variance														1.9%	0.0%	0.0%	0.0%	0.9%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
Strap Amt														691.00	63.00	71.00		195.00	97.00	79.00	41.00	40.00	90.00	39.00
Percent Variance														1.9%	1.9%	0.0%	0.0%	1.4%	0.0%	0.0%	2.8%	0.0%	6.4%	0.0%
Slurry (bbl)		4807																						

Percent Variance is reported as 0% if variance is within 1 gallon.

Slurry (bbl) 4807
Pump Time (Min) 1:22:47
Clean Fluid (gal) 193281
Proppant (lb) 175836

Avg Rate 49.1 BPM
Avg Corrected Rate 54.0 BPM
Max Rate 960.7 BPM
Average Prop Con 1.5
Average Pressure 2986.8 PSI
Maximum Pressure 3869.0 PSI

BREAKDOWN INFORMATION:

Base Fluid: 8.34 PPG
Wellhead Pressure: 1142 PSI
Broke Back: 2658 PSI
Pressure (Prop at Perfs) 2737 PSI
Initial ISIP: 2658 PSI
ISDP: 1613 PSI

@ 6.7 BPM
@ 60.7 BPM
@ 0.704 PSIFT

(Use weight slips for below amounts)			
TOTAL PROPPANT PUMPED: 170,200 Lbs			
% of Job	Prop	Mesh	Quantity
0%	None	20/40	Lbs
0%	TLC	20/40	Lbs
100%	White Sand	20/40	170,200 Lbs

Initial Annulus Pressure 0.0 PSI
Final Annulus Pressure 0.0 PSI

Variance			
0.0%			
MB Vari	SS Vari	Dens Vari	SC Vari
-26.1%	-2.9%	0.0%	97.3%
Average Annulus Pressure 0.0 PSI			
Change in Annulus Pressure 0.0 PSI			

CLEAN STREAM:

UV1 HRs	UV2 HRs	Transm. %
524	524	71.5

HES Engineer: Greg Carr
Co. Rep: Joe Duncan
Crew: Red C
Equipment running well
Xlink samples look good
Good job by Crew
3bbl overflush per Co Rep
In stage 4 we increased FR-76 setpt to a 0.70gpt per Co Rep.
We had a sand screw bind up in stage 8.
Ached crosslink in stage 6, per Co Rep we skipped stage 7.

Well Name: Three Rivers 4-36T-820 5 Green River

Date, Time & SO: 10/06/14 5:27 PM 901724450
Top & Bottom Perfs: 5588 TO 5776.0
Mid-Perf: 5711

BHST: 147 °F

HALLIBURTON

Stage	Stage Name	Slurry Vol (bbl)	Pump Time	Fluid Name	Fluid Volume (gal)	Proppant Mass (lb)	Slurry Rate (bpm)	Max Slurry Rate (bpm)	Pressure Ave (psi)	Pressure Max (psi)	Pressure Min (psi)	Prop Conc Avg (PPG)	Prop Conc Max (PPG)	Liquid Additives					Liquid Additives						
														WG-35 9000-30-0 (Gel) (ppt)	BC 140 590-29-4 (Xlinker) (gpt)	Sandwedge NT 1310-58-3 (Xlinker) (gpt)	BA-20 631-61-8 (Buffer) (gpt)	LoSurf-300D	CLA-Web (Clay Cont.) (gpt)	MC MX 2-2822 (Conduct. Enh.) (gpt)	Optiflo HTE 7727-54-0 (Breaker) (ppt)	SP 7775-27-1 (Breaker) (ppt)	FR-66 (Fric Red) (gpt)	MC B-8614 7681-52-9 (Bactericide) (gpt)	
1	Pre-Pad	25	0:02:29	FR Water	1043	0	5.0	13.0	3034	4098	1276	0.00	0.00				0	1.00	0.50					0.30	0.20
2	0 PPG	24	0:02:23	15 % HCL Acid	2000	0	10.4	21.0	3223	3320	3033						0								
3	PPG	1396	0:23:16	FR Water	58613	0	52.4	63.7	3022	3892	2559						0	1.00	0.50	0.39			0.50	0.20	
4	0.5 PPG White Sand	2149	0:35:49	FR Water	88096	45,017	60.3	60.4	3013	3386	2807	0.51	0.59				0	1.00	0.50	0.41			0.52	0.20	
5	0.5 PPG White Sand	123	0:02:03	FR Water	5033	2,476	60.2	60.2	3283	3307	3259	0.49	0.51				0	1.00	0.50	2.00			0.70	0.20	
6	0.5 PPG White Sand	123	0:02:03	FR Water	5026	2,553	60.2	60.4	3281	3303	3260	0.51	0.56			0.83	0	1.00	0.50	0.25			0.70	0.20	
7	0 PPG	60	0:01:00	16# Delta 140	2501	0	60.5	60.6	3254	3279	3228			16.00	1.60		0	1.00	0.50	0.25	1.00	1.00		0.20	
8	2 PPG White Sand	529	0:08:49	16# Delta 140	20220	39,571	60.3	60.6	3090	3280	2978	1.96	2.16	16.00	1.60		0		0.50	0.25	1.00	1.00		0.20	
9	4 PPG White Sand	328	0:05:28	16# Delta 140	11518	43,757	60.1	60.4	2846	3010	2732	3.80	4.05	16.00	1.60		0		0.50	0.25	1.00	1.00		0.20	
10	6 PPG White Sand	310	0:05:10	16# Delta 140	10049	51,250	57.4	60.1	2537	4092	2537	5.10	6.07	16.00	1.34	1.75	0		0.50		0.84	0.84		0.20	
						0																			
						0																			
						0																			
						0																			
11	Flush	131	0:02:11	FR Water	5508	0	32.6	59.0	2275	3411	2732	0.00	0.00					1.00	0.50				0.30	0.20	
						0																			
	Growler @ Flush	57			2400	0										50.00			0.00				0.00		
														Calculated Amt	708.61	72.42	89.69	0.00	165.82	103.80	78.77	42.68	42.68	84.12	41.52
														Actual Amt	703.00	73.40	90.30		161.40	102.90	78.30	43.00	43.20	83.80	41.80
														Percent Variance	-0.8%	0.0%	0.0%	0.0%	-2.7%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
														Strap Amt	762.00	72.00	92.00		170.00	109.00	75.00	45.00	44.00	81.00	40.50
														Percent Variance	7.5%	0.0%	2.6%	0.0%	2.5%	5.0%	-4.8%	5.4%	3.1%	-3.7%	-2.5%
Slurry (bbl)		5195																							

Percent Variance is reported as 0% if variance is within 1 gallon.

Slurry (bbl) 5195
Pump Time (Min) 1:30:39
Clean Fluid (gal) 208607
Proppant (lb) 195884

Avg Rate 47.2 BPM
Avg Corrected Rate 51.4 BPM
Max Rate 63.7 BPM
Average Prop Con 2.1
Average Pressure 2987.1 PSI
Maximum Pressure 4098.0 PSI

BREAKDOWN INFORMATION:

Base Fluid: 8.36 PPG
Wellhead Pressure: 1280 PSI
Broke Back: 3836 PSI
Pressure (Prop at Perfs) 2840 PSI
Initial ISIP: PSI
ISDP: 2025 PSI

@ 4.3 BPM
@ 60.3 BPM
@ 0.789 PSI/FT

(Use weight slips for below amounts)			
TOTAL PROPPANT PUMPED: 184,000 Lbs			
% of Job	Prop	Mesh	Quantity
0%	None	20/40	
0%	TLC	20/40	
100%	White Sand	20/40	184,000

Initial Annulus Pressure 0.0 PSI
Final Annulus Pressure 0.0 PSI
Average Annulus Pressure 0.0 PSI
Change in Annulus Pressure 0.0 PSI

CLEAN STREAM:		
UV1 HRs	UV2 HRs	Transm.%
525	525	78.1

Variance			
0.0%			
MB Vari	SS Vari	Dens Vari	SC Vari
0.3%	2.4%	1.2%	1.2%

COMMENTS:

HES Engineer: Paul McLean
Co. Rep: Bret Stringham
Crew: Red B
Equipment running well
Xlink samples look good
Good job by Crew
3bbl overflush per Co Rep
Increased FR sp to 0.5 co rep
Over pumped acid by apx 1000 gal @ 15%
Lost tub on blender in stage 3, dropped rate to bring back up.
Increased FR sp to 0.7 co rep in stage 4 due to rising pressure
Stage into stage 5 early per corep
LoSurf-300D tote emptied in stage 8, was not changed to new tote.

Well Name: Three Rivers 4-36T-820 6 Green River

Date, Time & SO: 10/06/14 8:22 PM 901724450
Top & Bottom Perfs: 5075 TO 5347.0
Mid-Perf: 5219

BHST: 139 °F

HALLIBURTON

Stage	Stage Name	Slurry Vol	Pump Time	Fluid Name	Fluid Volume	Proppant	Slurry	Max Slurry	Pressure	Pressure	Pressure	Prop Conc	Prop Conc	Liquid Additives				Liquid Additives							
														WG-35 9000-30-0 (Gel)	BC 140 590-29-4 (Xlinker)	Sandwedge N 1310-58-3 (Xlinker)	BA-20 631-61-8 (Buffer)	LoSurf-300D	CLA-Web (Clay Cont.)	MC MX 2-2822 (Conduct. Enh.)	Optiflo HTE 7727-54-0 (Breaker)	SP 7775-27-1 (Breaker)	FR-66 (Fric Red)	MC B-8614 7681-52-9 (Bactericide)	
		(bbl)			(gal)	Mass (lb)	Rate (bpm)	Rate (bpm)	Ave (psi)	Max (psi)	Min (psi)	Avg (PPG)	Max (PPG)												
1	Pre-Pad	19	0:01:57	FR Water	817	0	4.8	12.3	2137	4022	419	0.00	0.00					1.00	0.50				0.30	0.20	
2	0 PPG	24	0:02:23	15 % HCL Acid	1000	0	9.8	10.7	2985	3065	2835	0.00	0.00												
3	PPG	773	0:12:53	FR Water	32452	0	43.5	60.4	3140	3990	2146	0.00	0.00					1.00	0.50	0.77			0.30	0.20	
4	0.5 PPG White Sand	1108	0:18:28	FR Water	45407	22,431	60.3	60.4	2820	3114	2658	0.49	0.54					1.00	0.50	0.77			0.35	0.20	
5	0.5 PPG White Sand	123	0:02:03	FR Water	5035	2,603	60.3	60.3	2959	3021	2938	0.52	0.53					1.00	0.50	2.00			0.50	0.20	
6	0.5 PPG White Sand	124	0:02:04	FR Water	5090	2,744	60.3	60.4	3261	3325	3020	0.54	0.57	8.00	0.90			1.00	0.50	0.25			0.50	0.20	
7	0 PPG	0	0:00:00	16# Delta 140	1	0	0.0	0.0	0	0	0	0.00	0.00	16.00	1.60			1.00	0.50	0.25	1.00	1.00		0.20	
8	2 PPG White Sand	286	0:04:46	16# Delta 140	10938	22,871	60.2	60.4	3036	3265	2852	2.09	2.24	16.00	1.60			1.00	0.50	0.25	1.00	1.00		0.20	
9	4 PPG White Sand	177	0:02:57	16# Delta 140	6222	24,154	60.0	60.3	2719	2855	2602	3.88	4.10	16.00	1.60			1.00	0.50	0.25	1.00	1.00		0.20	
10	6 PPG White Sand	127	0:02:07	16# Delta 140	4135	24,314	60.0	60.8	2578	2665	2475	5.88	6.24	16.00	1.60	1.50		1.00	0.50		1.00	1.00		0.20	
						0																			
						0																			
						0																			
						0																			
11	Flush	118	0:01:58	FR Water	4949	0	54.5	64.2	2630	3269	1476	0.00	0.00					1.00	0.50				0.30	0.20	
						0																			
	Growler @ Flush	57			2400	0												0.00					0.00		
														Calculated Amt	381.46	38.65	36.47	0.00	115.05	57.52	75.63	21.30	21.30	32.42	23.01
														Actual Amt	377.20	39.40	36.90	0.00	115.50	58.20	75.80	20.90	20.80	32.40	23.30
														Percent Variance	-1.1%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
														Strap Amt	377.00	40.00	35.00		111.00	53.00	76.00	22.00	20.00	33.00	24.00
														Percent Variance	-1.2%	3.5%	-4.0%	0.0%	-3.5%	-7.9%	0.0%	0.0%	-6.1%	0.0%	0.0%
Slurry (bbl)		2879																							

Percent Variance is reported as 0% if variance is within 1 gallon.

Slurry (bbl) 2879
Pump Time (Min) 0:51:35
Clean Fluid (gal) 116046
Proppant (lb) 99340

Avg Rate 43.1 BPM
Avg Corrected Rate 46.9 BPM
Max Rate 64.2 BPM
Average Prop Con 1.5
Average Pressure 2569.5 PSI
Maximum Pressure 4022.0 PSI

BREAKDOWN INFORMATION:

Base Fluid: 8.35 PPG
Wellhead Pressure: 421 PSI
Broke Back: 4022 PSI
Pressure (Prop at Perfs) 2770 PSI
Initial ISIP: PSI
ISDP: 1613 PSI

@ 9.4 BPM
@ 60.2 BPM
@ 0.743 PSI/FT

(Use weight slips for below amounts)			
TOTAL PROPPANT PUMPED: 98,900 Lbs			
% of Job	Prop	Mesh	Quantity
0%	None	20/40	
0%	TLC	20/40	
100%	White Sand	20/40	98,900
Initial Annulus Pressure 0.0 PSI			
Final Annulus Pressure 0.0 PSI			

Variance			
0.0%			
MB Vari	SS Vari	Dens Vari	SC Vari
0.2%	-1.1%	-0.1%	0.5%
Average Annulus Pressure 0.0 PSI			
Change in Annulus Pressure 0.0 PSI			

CLEAN STREAM:		
UV1 HRs	UV2 HRs	Transm.%
526	526	76.5

HES Engineer: Paul McLean
Co. Rep: Bret Stringham
Crew: Red B
Equipment running well
Xlink samples look good
Good job by Crew
3bbl overflush per Co Rep
Took FR to .5 in stage 4 per co rep

Well Name: Three Rivers 4-36T-820 7 Green River

Date, Time & SO: 10/06/14 11:19 PM 901724450
Top & Bottom Perfs: 4900 TO 5014.0
Mid-Perf: 4972

BHST: 136 °F

HALLIBURTON

Stage	Stage Name	Slurry Vol	Pump Time	Fluid Name	Fluid Volume	Proppant	Liquid Additives																	Liquid Additives					
							Mass	Rate	Max Slurry	Pressure	Pressure	Pressure	Prop Conc	Prop Conc	WG-35	BC 140	Sandwedge N	BA-20	LoSurf-300D	CLA-Web	MC MX 2-2822	Optiflo HTE	SP	FR-66	MC B-8614				
		(bbl)			(gal)	(lb)	(bpm)	(bpm)	(psi)	(psi)	(psi)	(PPG)	(PPG)	9000-30-0	590-29-4	1310-58-3	631-61-8		(Clay Cont.)	(Conduct. Enh.)	(Breaker)	(Breaker)	(Fric Red)	(Bactericide)					
1	Pre-Pad	5	0:00:31	FR Water	215	0	2.5	4.8	1755	2126	1152	0.00	0.00						1.00	0.50									
2	0 PPG	24	0:02:23	15 % HCL Acid	1000	0	6.6	23.9	1717	2979	1459	0.00	0.00										0.30	0.20					
3	0 PPG	948	0:15:48	FR Water	39817	1,075	56.2	60.6	2664	3745	2454	0.03	0.05						1.00	0.50	0.61		0.30	0.20					
4	0.5 PPG White Sand	1422	0:23:42	FR Water	58292	29,729	60.4	60.5	2383	2541	2324	0.51	0.54						1.00	0.50	0.61		0.30	0.20					
5	0.5 PPG White Sand	122	0:02:02	FR Water	5018	2,599	60.4	60.5	2371	2388	2355	0.52	0.54						1.00	0.50	2.00		0.30	0.20					
6	0.5 PPG White Sand	324	0:05:24	FR Water	13290	7,243	47.3	60.4	1985	2429	1500	0.55	0.89						1.00	0.50	0.25		0.30	0.20					
7	Flush	171	0:02:51	FR Water	7189	0	14.6	41.7	1270	1504	834	0.00	0.00						1.00	0.50	0.25			0.20					
8	Spacer	112	0:01:52	FR Water	4719	0	31.1	60.1	1797	2814	950	0.00	0.00						1.00	0.50	0.25		0.50	0.20					
9	0 PPG	167	0:02:47	16# Delta 140	7034	0	55.7	60.8	2589	2897	1878	0.00	0.00	16.00	1.60				1.00	0.50	0.25	1.00	1.00	0.20					
10	2 PPG White Sand	351	0:05:51	16# Delta 140	13413	27,604	60.4	60.8	2445	2851	2341	2.06	2.27	16.00	1.60				1.00	0.50		1.00	1.00	0.20					
11	4 PPG White Sand	218	0:03:38	16# Delta 140	7664	30,863	60.1	60.3	2284	2415	2187	4.03	4.24	16.00	1.60				1.00	0.50		1.00	1.00	0.20					
12	6 PPG White Sand	161	0:02:41	16# Delta 140	5216	23,780	60.4	61.9	2149	2234	2067	4.56	6.12	16.00	1.50	1.50			1.00	0.50		0.85	0.85	0.20					
						0																							
						0																							
						0																							
13	Flush	111	0:01:51	FR Water	4665	0	61.1	61.1	2178	2294	2116	0.00	0.00						1.00	0.50				0.30	0.20				
						0																							
						0																							
	Growler @ Flush	57			2400	0								50.00					0.00				0.00						
														533.23	52.80	35.67	0.00		166.53	83.27	78.09	32.54	32.54	38.75	33.31				
														449.80	52.00	34.80			141.10	70.90	81.70	31.60	31.60	38.60	28.30				
														Percent Variance	-15.6%	0.0%	0.0%	0.0%	-15.3%	-14.9%	4.6%	0.0%	0.0%	0.0%	-15.0%				
														Strap Amt	582.00	53.00	35.00		133.50	79.00	87.00	49.00	35.00	41.00	30.00				
														Percent Variance	9.1%	0.0%	0.0%	0.0%	-19.8%	-5.1%	11.4%	50.6%	7.5%	5.8%	-9.9%				
	Slurry (bbl)	4137																											

Percent Variance is reported as 0% if variance is within 1 gallon.

Slurry (bbl) 4137
Pump Time (Min) 1:11:22
Clean Fluid (gal) 167532
Proppant (lb) 127078

Avg Rate 44.4 BPM
Avg Corrected Rate 47.9 BPM
Max Rate 61.9 BPM
Average Prop Con 1.1
Average Pressure 2122.1 PSI
Maximum Pressure 3745.0 PSI

BREAKDOWN INFORMATION:

Base Fluid: 8.35 PPG
Wellhead Pressure: 1153 PSI
Broke Back: 2126 PSI
Pressure (Prop at Perfs) 2431 PSI
Initial ISIP: PSI
ISDP: 1423 PSI

@ 9.8 BPM
@ 60.4 BPM
@ 0.720 PSI/FT

(Use weight slips for below amounts)			
TOTAL PROPPANT PUMPED: 121,900 Lbs			
% of Job	Prop	Mesh	Quantity
0%	None	20/40	Lbs
0%	TLC	20/40	Lbs
100%	White Sand	20/40	121,900 Lbs

Initial Annulus Pressure 0.0 PSI
Final Annulus Pressure 0.0 PSI
Average Annulus Pressure 0.0 PSI
Change in Annulus Pressure 0.0 PSI

CLEAN STREAM:		
UV1 HRs	UV2 HRs	Transm.%
528	528	68.4

Variance 0.0%			
MB Vari	SS Vari	Dens Vari	SC Vari
0.8%	-1.1%	-0.2%	-0.2%

COMMENTS:

HES Engineer: Paul McLean
Co. Rep: Bret Stringham
Crew: Red B

Equipment running well
Xlink samples look good
Good job by Crew

Lost rate in Stage 2, Valve was closed on ADP Blender, Opened valve and rate was reestablished
Dropped Rate in Stage 6, Came online with crosslinkers but no gel was established, got gel back and blender lost its
tub sent to bypass and started coming back then lost LA1 again. Per co rep job was sent to flush.

The Blender coupler is having to be torn apart on the blender suction pump, per co rep we will get back into the job
from where we left off after everything is fixed.